




350384

LPC 16300000 St. Clair Co.
Yvonne Sauget (Trust)
ILD 982073611
SF/HRS



CERCLA Integrated Site Assessment



**Illinois Environmental
Protection Agency**

2200 Churchill Road
P. O. Box 19276
Springfield, IL 62794-9276

Confidential material may be enclosed.

TABLE OF CONTENTS

1.0 INTRODUCTION.....	1
2.0 SITE BACKGROUND.....	4
2.1 INTRODUCTION.....	4
2.2 SITE DESCRIPTION.....	4
2.3 SITE HISTORY.....	4
2.4 APPLICABILITY OF OTHER STATUTES.....	5
3.0 SITE INSPECTION ACTIVITIES & ANALYTICAL RESULTS.....	16
3.1 INTRODUCTION.....	16
3.2 RECONNAISSANCE INSPECTION.....	16
3.3 SITE REPRESENTATIVE INTERVIEW.....	17
3.4 SOIL/SEDIMENT SAMPLING.....	20
3.5 GROUNDWATER SAMPLING.....	23
3.6 SURFACE WATER SAMPLING.....	23
3.7 ANALYTICAL RESULTS.....	23
3.8 KEY SAMPLES.....	24
4.0 IDENTIFICATION OF SOURCES.....	28
4.1 INTRODUCTION.....	28
4.2 CONTAMINATED SOIL.....	28
5.0 MIGRATION PATHWAYS.....	30
5.1 INTRODUCTION.....	30
5.2 GROUNDWATER PATHWAY.....	30
5.3 SURFACE WATER PATHWAY.....	35
5.4 SOIL EXPOSURE PATHWAY.....	36
5.5 AIR PATHWAY.....	37
6.0 BIBLIOGRAPHY.....	39

5626-
Wan
C.

APPENDIXES

SITE FOUR MILE RADIUS MAP.....	A
USEPA FORM 2070-13.....	B
TARGET COMPOUND LIST.....	C
IEPA PHOTOGRAPHS.....	D
WELL LOGS.....	E
IEPA BORING LOGS.....	F
CENTRACTS POPULATION CALCULATIONS.....	G
REMOVAL CRITERIA.....	H
ANALYTICAL RESULTS.....	I

LIST OF FIGURES

2-1 VILLAGE OF SAUGET LOCATION MAP.....	6
2-2 SITE LOCATION MAP.....	7
2-3 1959 AERIAL PHOTOGRAPH.....	8
2-4 1962 AERIAL PHOTOGRAPH.....	9
2-5 1970 AERIAL PHOTOGRAPH.....	10
2-6 1973 AERIAL PHOTOGRAPH.....	11
2-7 1976 AERIAL PHOTOGRAPH.....	12
2-8 1976 AERIAL PHOTOGRAPH.....	13
2-9 1986 AERIAL PHOTOGRAPH.....	14
2-10 1991 AERIAL PHOTOGRAPH.....	15
3-1 SOIL SAMPLE MAP.....	18
3-2 BACKGROUND SOIL SAMPLE MAP.....	19
5-1 REGIONAL GEOLOGY.....	33
5-2 GENERALIZED GEOLOGIC CROSS SECTION.....	34

LIST OF TABLES

3-1 SOIL SAMPLE DESCRIPTIONS.....	20
3-2 SAMPLE SUMMARY... ..	25
3-3 KEY SAMPLES.....	26
5-1 POPULATIONS NEARBY THE SITE.....	37

1. INTRODUCTION

On September 22, 1992 the Illinois Environmental Protection Agency's Site Assessment Program was tasked by the U.S. Environmental Protection Agency (USEPA) to conduct the site inspection portion of an Integrated Assessment of the Yvonne Sauget (Trust) site in Sauget, Illinois.

The site was initially placed in CERCLIS (Comprehensive Environmental Response, Compensation & Liability Information System) in December of 1987 as a result of a request for discovery action initiated by the Illinois Environmental Agency (IEPA). The site received its initial CERCLA evaluation in September of 1988, when Mr. Tim Murphy of the IEPA completed a formal Preliminary Assessment report. In December 1992, the Illinois Environmental Protection Agency's Site Assessment Program prepared and submitted to the Region V offices of the U.S. Environmental Agency a site inspection work plan for the Yvonne Sauget (Trust) site. The sampling portion of the site inspection was conducted on December 8 & 9, 1992 when the inspection team collected a total of sixteen soil samples.

The purpose of the Integrated Assessment has been developed from USEPA directive and guidance information which outlines Site Assessment program strategies. The information states:

The Integrated Assessment will be conducted to: 1) Collect data which would satisfy both site assessment and remedial program activities. This would incorporate hazardous waste, surface water, air, and groundwater concerns. 2) The objectives of the assessment are to determine whether time or non time critical removals are warranted and to determine whether the site is National Priorities List (NPL) caliber. If the determination is made that the site is NPL caliber, additional data will likely be needed to complete the assessment. A sampling plan to

accommodate removal and site assessment needs, as well as initial remedial needs should be developed. 3) Determination of site sampling needs will be accomplished with an understanding to assure adequate data for the removal assessment and the preparation of the Hazard Ranking System (HRS) score as well as the need for possible initial sampling for the remedial investigation. Based on the preliminary HRS score and removal program information, the site will either be designated as No Further Action (NFA), or carried forward as an NPL listing candidate. Sites that are designated NFA or deferred to other statutes are not candidates for an integrated Assessment. 4) Upon completion of the data gathering, there will be a determination of whether the site should be forwarded within the Superfund process, either through the remedial or removal programs.

The initial assessment of a site as it enters the Superfund program within Region V will be conducted by either a Regional On-Scene Coordinator (OSC) and a Site Assessment Manager (SAM) or by State personnel. An OSC and a SAM will be assigned for all new sites entering the Regional Superfund program. If an emergency is found to occur, USEPA or state emergency removal staff will be immediately contacted for action. If the site needs further Superfund activities, a Site Assessment Team (SAT), comprised of the State, the SAM, the Regional Project Manager (RPM), and an OSC will be formed. As necessary, additional data can be generated for the SAT to make a recommendation to the Regional Decision Team (RDT) for further possible action.

The Integrated Assessment will address all the data requirements of the revised HRS using field screening and NPL level Data Quality Objectives (DQOs) prior to data collection. It will also provide needed data in a format to support remedial investigation workplan development. Only sites that appear to score high enough for NPL listing and that have not been deferred to another authority will receive an Integrated Assessment.

USEPA Region 5 offices have requested that the Illinois Environmental Protection Agency identify sites during the Integrated Assessment that may require a CERCLA removal action to remediate an immediate threat to human health and/or the environment. Before the initiation of field activities, a Removal Integrated Site Evaluation (RISE) form pertaining to site specific operations and waste characteristics was completed and forwarded to Region 5 offices.

During the field investigation portion of the Integrated Assessment, a number of environmental samples were collected from the facility, and at points of potential pollutant migration. An analysis of these samples showed that established CERCLA Removal Action Levels (RALs)

were not exceeded in any sample collected during the Integrated Assessment sampling event.

Therefore, a Region 5 On-Scene Coordinator (OSC) was not assigned to Yvonne Sauget (Trust)

During the Integrated Assessment, a number of other Removal Action Criteria were also evaluated. These criteria included the presence of: contaminated drinking water supplies, hazardous substances stored in containers that may pose a threat of release, high level contamination at or near the surface in soils that may migrate, and a threat of fire or explosion (refer to Appendix H for a complete listing of these factors)

Based on the information gathered over the course of the formal Integrated Assessment, the author has concluded that Yvonne Sauget (Trust) does not pose enough of a threat to human health and/or the environment to warrant a time or non-time critical CERCLA removal action.

It should be stressed that the CERCLA removal status can be re-evaluated at such time that additional information suggests that the facility may be posing a threat to human health and/or the environment.

2. SITE BACKGROUND

2.1 INTRODUCTION

This section includes information obtained over the course of the formal CERCLA site inspection investigation, and previous Illinois Environmental Protection Agency activities involving this site.

2.2 SITE DESCRIPTION

Yvonne Sauget (Trust), also known as Site K, consists of a sand pit that has been filled with unknown materials. The site is an estimated two and a half acres in size. The Yvonne Sauget site is located northeast of the intersection of the streets of Queeny and Ogden in Sauget, Illinois. Currently, situated on the majority of the property is a park designated specifically for the residents of Sauget. Land abutting the northwest perimeter of the park is also a portion of the Yvonne Sauget (Trust) site. Currently, this part of the site is occupied by MTS, Inc. MTS, Inc. is a trucking business owned by Paul Sauget who is also the mayor of the Village of Sauget. To the southwest of the site are residential homes. To the far northeast of the site (Trust) is a ball diamond. East and southeast of the site is vacant land. (Please refer to Figure 2-1 and 2-2.)

2.3 SITE HISTORY

In 1988, Ecology and Environment, Inc. (E&E) completed an investigation of several potential hazardous waste sites in the area of the Village of Sauget, Illinois. E&E made use of aerial photographs to observe a pit, now referred to as the Yvonne Sauget (Trust) site or Site K.


E&E used a series of aerial photographs to observe the waste disposal activities that took place

at the Yvonne Sauget (Trust) site. With the aid of a 1950 aerial photograph, E&E observed that excavations at the Yvonne Sauget (Trust) site began in the late 1940's. In 1955, the site remained about the same. A 1962 aerial photograph showed that the pit had been filled. An aerial photograph taken in 1973 reveals the presence of another larger pit situated in the same location as the previous one at the Yvonne Sauget (Trust) site. E&E observed from a 1978 aerial photograph that once again, the pit had been filled. (Please refer to Figures 2-3 through 2-10 for available aerial photographs).

The materials placed in the pit are unknown. Part of E&E's investigation included collected subsurface samples from three twenty-foot borings. In their report, E&E noted that although no waste materials were found, toward the bottom of each boring were black-stained soils. These samples revealed the presence of two volatiles, 17 semivolatiles, elevated concentrations of tin, mercury and cyanide and pesticide and PCB (polychlorinated biphenyl) contaminants such as benzo(a) anthracene, chrysene, benzo(b)fluoranthene, benzo(a)pyrene, Aroclor 1242, Aroclor 1248 and Aroclor 1250; all of which are carcinogens.


2.4 APPLICABILITY OF OTHER STATUTES

There are no known records indicating that the Yvonne Sauget (Trust) site is or ever has been listed as a facility, generator, etc., permitted or not, under any environmental statute including the Resources Conservation and Recovery Act (RCRA), the Atomic Energy Act (AEA), Toxic Substances Control Act (TSCA), Federal Insecticide, Fungicide, and Rodenticide Act (FIFRA) or the Uranium Mill Tailings Radiation Control Act (UMTRCA). This is due to the enactment of environmental regulatory controls postdating the time at which this site was in operation.



YVONNE SAUGET (TRUST)

Figure 2-1



YVONNE SAUGET (TRUST)

Not to Scale

Yvonne Sauget (Trust) Site — — — — —
 Village of Sauget Mini Park — — — — —

Figure 2-2

about the same. A 1962 aerial photograph showed that the pit had been filled. An aerial photograph taken in 1973 reveals the presence of another larger pit situated in the same location as the previous one at the Yvonne Sauget (Trust) site. E&E observed from a 1978 aerial photograph that once again, the pit had been filled. (Please refer to Figures 2-3 through 2-10 for available aerial photographs.)

The materials placed in the pit are unknown. Part of E&E's investigation included collected subsurface samples from three twenty-foot borings. In their report, E&E noted that although no waste materials were found, toward the bottom of each boring were black-stained soils. These samples revealed the presence of two volatiles, 17 semivolatiles, elevated concentrations of tin, mercury and cyanide and pesticide and PCB (polychlorinated biphenyl) contaminants such as benzo(a) anthracene, chrysene, benzo(b)fluoranthene, benzo(a)pyrene, Aroclor 1242, Aroclor 1248 and Aroclor 1250; all of which are carcinogens.

2.4 APPLICABILITY OF OTHER STATUTES

There are no known records indicating that the Yvonne Sauget (Trust) site is or ever has been listed as a facility, generator, etc., permitted or not, under any environmental statute including the Resources Conservation and Recovery Act (RCRA), the Atomic Energy Act (AEA), Toxic Substances Control Act (TSCA), Federal Insecticide, Fungicide, and Rodenticide Act (FIFRA) or the Uranium Mill Tailings Radiation Control Act (UMTRCA). This is due to the enactment of environmental regulatory controls postdating the time at which this site was in operation.




SOURCE: IDOT, 1992

1959 AERIAL PHOTOGRAPH
FIGURE 2-3



SOURCE: IDOT, 1992

1962 AERIAL PHOTOGRAPH
FIGURE 2-4



1970 AERIAL PHOTOGRAPH
FIGURE 2-5



SOURCE: IDOT, 1992

1973 AERIAL PHOTOGRAPH
FIGURE 2-6



SOURCE: IDOT, 1992

1976 AERIAL PHOTOGRAPH
FIGURE 2-7



SOURCE: IDOT, 1992

1976 AERIAL PHOTOGRAPH
FIGURE 2-8



SOURCE: IDOT, 1992

1986 AERIAL PHOTOGRAPH
FIGURE 2-9



SOURCE: IDOT, 1992

1991 AERIAL PHOTOGRAPH
FIGURE 2-10

3. SITE INSPECTION ACTIVITIES AND RESULTS

3.1 INTRODUCTION

This section outlines procedures utilities and observations made during the CERCLA site inspection conducted at the Yvonne Sauget (Trust) site. Individual subsections address the reconnaissance inspection, site representative interview, field sampling procedures, analytical and key samples summary. The site inspection for Yvonne Sauget (Trust) site was conducted in accordance with the site inspection work plan which was developed and submitted to the USEPA Regional Offices prior to the initiation of files activities.

The US Environmental Protection Agency's Potential Hazard Waste Site Inspection Report (Form 2070-13) for the Yvonne Sauget (Trust) site is located in Appendix B of this report.

3.2 RECONNAISSANCE INSPECTION


On November 2, 1992, a reconnaissance visit to the Yvonne Sauget (Trust) site was conducted by Sheila Murphy, project manager, and Kim Nika. During the reconnaissance inspection it was observed that the majority of the site consisted of a village park. To the north northwest of the park and still part of the Yvonne Sauget (Trust) site was MTS, Inc., apparently a trucking company. Photographs were taken of the park. (Please refer to Appendix D for these photographs).

It was during the reconnaissance inspection that IEPA employees encountered a man who told them they were on private property and, thus, trespassing. S. Murphy and K. Nika identified themselves as employees of the Illinois Environmental Protection Agency. Although the man

refused to give his name at this time, it was later revealed that he was Paul Sauget.

3.3 SITE REPRESENTATIVE INTERVIEW

On December 8 and 9, 1992, the IEPA sampling team, consisting of Ken Corkill, Sheila Murphy, Kim Nika and Greg Spencer and the drill rig team, consisting of Paul Mason, Bob Mathis and Bill Walkenback, and geologist Sherri Otto arrived at the Yvonne Sauget (Trust) site at approximately 10:40 AM. At this time, S. Murphy and G. Spencer went to the village hall to have someone unlock the gate to the park and to obtain a copy of the park's sprinkler system plan. No one was available at the village hall to assist the IEPA personnel. Upon returning to the site, Stan Black, with the IEPA and Paul Sauget and Mike Williams, both with the Village of Sauget, had arrived. M. Williams was assigned the task of observing the sampling activities. P. Sauget verbally gave IEPA personnel permission to access the Yvonne Sauget (Trust) property as long as no damage was done. P. Sauget was adamant in his statement that at the first sign of property damage, he would have the IEPA personnel arrested. Before any vehicles were driven into the park, the ground of the park was surveyed. Several ruts at different locations in the park were observed and documented with photographs. (Please refer to Appendix D).




YVONNE SAUGET (TRUST)

SOIL SAMPLE MAP

Not to Scale

Yvonne Sauguet (Trust) Site ————
 Village of Sauguet Mini Park ————

Figure 3-1



YVONNE SAUGET (TRUST)

BACKGROUND SOIL SAMPLE MAP

Not to Scale

Yvonne Sauget (Trust) Site - - - - -

Figure 3-2

3.4 SOIL SEDIMENT SAMPLING

On December 8 and 9, 1992, Illinois Environmental Protection Agency (IEPA) personnel (with the assistance of the drill rig team) collected a total of sixteen soil/sediment samples (see Figures 3-1 and 3-2 for all sampling locations) on site and in the proximity of the site within the areas of suspected contamination. The main objective of these soil/sediment samples was to determine if any USEPA Target Compound List (TCL) contaminants are present at the site or at potential targets of concern. (The Target Compound List is provided in Appendix C of this report.) The following table details individual samples with their locations, depths and physical appearances. (Refer to the analytical data in Appendix I for detection limits associated with each sample point).

Table 3-1 Soil Sample Descriptions

X101	10"-15"	Moist, dark grey clay	East of MTS, Inc.'s main building
X102	18"-24"	1st 12":moist dark grey-black clay; 2nd 12": black tan clay	29' NE of park's SW fence & 115' NW of NW fence
X103	12.5'-17.5'	Wet dark grey to black coarse sand	39.5'W of NE fence & 53'7" S of NW fence
X104	18"-24"	1st 12":light tan sandy clay; 12"-24" dark grey to black silty clay with concrete, brick, debris and gravel	8'10" SSE of NW fence, 11' SW of NE fence

X105	18"	Moist dark grey to black silty clay with small cinders	Residential backyard; 1453 Queeny; 20'9" SW of park 's SW fence, 9'8" E of the most E corner of trailer home at 1451 Queeny
X106	12.5'-15'	Very, wet black fill sand, gravel, asphalt and wood	Center of park; 64'4" E of SW fence, 111' 6" NW of most NE corner park pavilion
X107	18"-24"	Moist tan to black mottled silty clay	Directly beneath W feet of power pole along park's SW fence; 6.5' SE of NW leg & 3.5' NE of SW leg
X108	10'-12.5'	Dark grey clay	11'4" N & 71' NW of electrical pole located in the SE corner of the park
X109	18"	Moist grey to black silty clay w/some cinders	Residential backyard: (1457 &) 1459 Queeny; 20'5" SW of SW park fence, 15'7" SE of most E corner of residential workshop(old garage)
X110	12"-18"	Tan friable silty clay	54'9" E of SW park fence, 18'2" S of most southern corner of park pavilion
X111	18"-24"	Moist tan to black mottled silty clay	Refer to X107

X112	4"-8"	Moist dark grey	S of ball diamond & E of park; 184'2" W of water main standpipe, 75' N of sewer main
X113	12"-18"	Light brown to tan clay, somewhat dry	Extreme S corner of park; 13.5' N of most S corner of the park, from most S fence post
X114	17.5'-20'	Dark grey medium sand to gravel	Center of park; 64'4" E of SW fence, 111'6" NW of most NE corner of park pavilion
X115	18"	Light tan silty sand	Vacant land E of Ogden 68' 4" E of sanitary sewer manhole between Nickel & Queen , 111'2" SSW of SW corner of tennis court
X116	18"-24"	Tan to dark grey silty clay	Residential backyard; 1463 Queeny; 8" NW of SE fence, 7' S of NE fence(runs parallel w/ SW park fence

Sample X101 was collected with the use of a shovel. The rest of the above soil/sediment samples were collected with stainless steel trowels for shallow samples and drill barrels and augers for the deep borings. Decontamination of the trowels was done at the IEPA's warehouse prior to and following the sampling portion of the SSI. Decontamination procedures include the cleaning of the equipment with liquid alconex and warm water, rinsing with tap water, rinsing

with a 50% distilled water mixture, rinsing with warm tap water and a final rinsing of distilled water. The trowels and shovel dried on paper towels and were wrapped in aluminum foil.

3.5 GROUNDWATER SAMPLING

There are no known groundwater wells in the vicinity of the Yvonne Sauget (Trust) site, and therefore, no groundwater samples were taken during the CERCLA site inspection for the Yvonne Sauget (Trust) site.

3.6 SURFACE WATER SAMPLING

Approximately one quarter of a mile west of the Yvonne Sauget (Trust) site is an intermittent stream known as Dead Creek. About one and a half miles further west is the Mississippi River. No surface water samples were collected during the December 8 and 9, 1992 CERCLA site inspection.

3.7 ANALYTICAL RESULTS

This section includes a summary of the analytical results of samples collected during the CERCLA site inspection portion of the Integrated Assessment conducted at the Yvonne Sauget (Trust) site in Sauget, Illinois. Chemical analysis of soil/sediment samples collected by IEPA personnel revealed quantified and estimated values of volatiles, semi-volatiles, pesticides, PCBs, heavy metals and common laboratory artifacts. A quality assurance/quality control review was conducted by the Quality Assurance Section of the Division of Laboratory Services at the IEPA. Please refer to Table 3-2 for the sample summary, chemical analysis are provided in Appendix I.

3.8 KEY SAMPLES

Table 3-3 identifies those samples taken during the CERCLA site inspection for the Yvonne Sauget (Trust) site which were found to contain contaminants at a level significantly higher than the background concentrations. No Removal Action Levels were exceeded.

Acetone, although a common laboratory artifact, was the only volatile that was found significantly over background levels. Acetone was detected in samples X103 and X114.

Levels of semi-volatiles elevated significantly over background were taken from the park and found in samples X104, X106, and X114. These include Phenanthrene, Fluoranthene, Pyrene, Chrysene, Benzo(k)fluoranthene and Benzo(g,h,i)perylene. Of these contaminants, chrysene and Benzo(k)fluoranthene are carcinogens.

TABLE 3-3
KEY SAMPLES

SAMPLING POINT PARAMETER	X101 12-9-92	X102 12-9-92	X103 12-9-92	X104 12-9-92	Target X105 12-9-92	X106 12-9-92	X107 12-9-92	Target X108 12-9-92	X110 12-9-92	X111 12-9-92	X112 12-9-92	X113 12-9-92	X114 12-9-92	Soil Background X115 12-9-92	Target X116 12-9-92
VOLATILES	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB
Acetone	--	--	180.0 J	--	--	--	--	--	--	--	--	--	41.0 J	--	--
SEMIVOLATILES	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB
Phenanthrene	--	--	--	--	--	470.0 J	--	--	--	--	--	--	--	--	--
Fluoranthene	--	--	--	--	--	870.0 J	--	--	--	--	--	--	480.0 J	--	--
Pyrene	--	--	--	--	--	470.0 J	--	--	--	--	--	--	--	--	--
Chrysene	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Benzofluoranthene	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Benz[a]pyrene	--	--	--	--	--	560.0 J	--	--	--	--	--	--	--	--	--
PESTICIDES	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB
Dieldrin	--	--	7.30 J	210.0 PJ	12.0 J	--	--	8.60 JP	--	--	--	--	--	--	6.50 P-
4'-DDE	--	--	23.0 PJ	580.0 PDU	--	--	8.20 J	28.0 J	--	7.80 J	--	--	--	--	36.0 P-
Endrin	--	--	12.0 P	240.0 PD	7.60 P	--	--	8.10 P	--	4.10 JP	--	--	--	--	15.0 P
Endosulfan II	--	--	38.0 P	540.0 PDU	12.0 PJ	--	--	37.0 PJ	--	11.0 PJ	--	--	--	--	70.0 PJ
4'-DDT	8.5 PJ	4.60 PJ	4.60 PJ	--	--	36.0 JD	6.70 PJ	5.60 PJ	--	--	--	--	--	--	--
Endrin Ketone	11.0	--	--	--	13.0 P	--	7.70 P	--	--	--	--	--	--	--	--
Endrin Aldehyde	--	--	--	--	--	28.0 D	--	--	--	--	--	--	--	--	--
alpha-Chloro	--	--	--	--	--	22.0 JPD	--	--	--	--	--	--	--	--	--
gamma-Chloro	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Aroclor-1018	--	--	--	1500.0 D	--	--	--	--	--	--	--	--	6.80 JPD	--	--
Aroclor-1221	--	--	--	310.0 JPD	--	--	--	--	--	--	--	--	--	--	--
Aroclor-1242	--	--	303.0 P	--	--	340.0 JPD	--	80.0 P	57.0 JP	--	--	--	--	--	36.0 P-
Aroclor-1254	--	--	360.0 P	--	130.0 P	360.0 JPD	--	200.0 P	--	--	--	--	--	--	220.0 P
Aroclor-1260	83.0	--	540.0 P	4000.0 PDC	130.0 P	440.0 JD	72.0 P	160.0 P	--	77.0 P	--	--	540.0 PDU	--	350.0 P
INORGANICS	PPM	PPM	PPM	PPM	PPM	PPM	PPM	PPM	PPM	PPM	PPM	PPM	PPM	PPM	PPM
Aluminum	--	--	--	--	--	21700.0	--	--	--	21800.0	20300.0	--	--	--	6.70 J
Antimony	6.60 J	7.60 J	--	8.70 J	10.40 J	6.10 J	8.20 J	7.70 J	--	8.60 J	7.50 J	--	--	--	2.40
Cadmium	2.10	1.40	--	1.20	--	1.30	1.50	8.55	--	2.50	8.50	--	--	--	--
Calcium	--	--	--	9600.0	--	--	--	--	--	--	--	--	--	--	--
Chromium	--	--	--	79.30	--	--	--	--	--	--	--	--	--	--	--
Copper	41.90	48.20	--	53.60	28.80	--	43.80	66.0	--	46.30	78.70	--	--	--	36.30
Lead	56.30	36.40	30.8	228.0	26.40	56.0	65.80	136.20 J	--	81.1	66.10	--	--	--	61.40
Manganese	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Selenium	0.42 BU	0.22 BU	--	0.24 BU	0.19 BU	0.71 BU	0.18 BU	0.21 BU	--	0.18 BU	0.28 BU	--	--	--	0.17 BU
Silver	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Thallium	0.280 B	0.24 B	--	0.15 BU	0.27 B	--	0.28 B	0.16 BU	--	0.28 B	0.21 B	--	--	--	0.21 B
Zinc	165.0	160.0	--	2110.0	118.0	142.0	300.0	2370.0	--	300.0	263.0	--	--	--	221.0
Cyanide	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
TEMPERATURE IDENTIFIED COMPOUNDS	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB
1-ETHYLENE-1H-INDENE	--	--	--	--	--	--	--	--	180.0 AN	--	--	--	--	--	--

TABLE 3-3
 KEY SAMPLES

SAMPLING POINT PARAMETER	X101 12-9-92	X102 12-9-92	X103 12-9-92	X104 12-9-92	Target X105 12-9-92	X106 12-9-92	X107 12-9-92	X108 12-9-92	Target X109 12-9-92	X110 12-9-92	X111 12-9-92	X112 12-9-92	X113 12-9-92	X114 12-9-92	Soil Background X115 12-9-92	Target X116 12-9-92
VOLATILES	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB
Acetone	--	--	180.0 J	--	--	--	--	--	--	--	--	--	--	410.0 J	--	--
SEMI-VOLATILES	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB
Phenanthrene	--	--	--	--	--	470.0 J	--	--	--	--	--	--	--	--	--	--
Fluoranthene	--	--	--	--	--	480.0 J	--	--	--	--	--	--	--	--	--	--
Pyrene	--	--	--	--	--	870.0 J	--	--	--	--	--	--	--	480.0 J	--	--
Chrysene	--	--	--	--	--	470.0 J	--	--	--	--	--	--	--	--	--	--
Benz[a]fluoranthene	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Benz[b]fluoranthene	--	--	--	--	--	580.0 J	--	--	--	--	--	--	--	--	--	--
Benz[a]pyrene	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
PESTICIDES	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB
Dieldrin	--	--	7.30 J	210.0 PJ	--	--	--	--	--	--	--	--	--	--	--	6.50 P
4'-DDE	--	--	23.0 PJ	580.0 PJ	12.0 J	--	8.20 J	6.60 J	28.0 J	--	7.80 J	--	--	--	--	38.0 PJ
Endrin	--	--	--	--	--	17.0 JD	--	--	8.10 P	--	4.10 P	--	--	--	--	15.0 P
Endosulfan II	--	--	12.0 P	240.0 PD	7.80 P	--	--	--	--	--	--	--	--	--	--	--
4'-DDT	--	--	38.0 P	540.0 PJ	12.0 PJ	38.0 JD	8.70 PJ	7.0 PJ	37.0 PJ	--	11.0 PJ	--	--	18.0 JD	--	70.0 PJ
Endrin ketone	8.5 PJ	4.60 PJ	4.60 PJ	--	--	--	--	--	8.60 PJ	--	--	--	--	--	--	--
Endrin aldehyde	11.0	--	--	--	13.0 P	--	7.70 P	--	--	--	--	--	--	--	--	--
alpha-Chloro	--	--	--	--	--	28.0 D	--	--	--	--	--	--	--	--	--	--
gamma-Chloro	--	--	--	--	--	22.0 JPD	--	--	--	--	--	--	--	--	--	--
Aroclor-1018	--	--	--	180.0 D	--	--	--	--	--	--	--	--	--	6.60 JPD	--	--
Aroclor-1221	--	--	--	310.0 JPD	--	--	--	--	--	--	--	--	--	--	--	--
Aroclor-1242	--	--	380.0 P	--	180.0 P	640.0 JPD	--	420.0	80.0 P	37.0 J	--	--	--	--	--	38.0 P
Aroclor-1254	--	--	540.0 P	400.0 PDC	130.0 P	440.0 JD	72.0 P	880.0 P	230.0 P	--	77.0 P	--	--	640.0 PDC	--	220.0 P
Aroclor-1280	80.0	--	540.0 P	--	130.0 P	--	--	110.0 P	180.0 P	--	--	--	--	380.0 JPD	--	350.0 P
INORGANICS	PPM	PPM	PPM	PPM	PPM	PPM	PPM	PPM	PPM	PPM	PPM	PPM	PPM	PPM	PPM	PPM
Aluminum	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Arsenic	8.80 J	7.80 J	--	8.70 J	10.40 J	8.10 J	21.700.0	--	--	--	21.600.0	50300.0	--	--	--	8.70 J
Cadmium	2.10	1.40	--	1.20	--	1.80	1.80	--	8.80	--	8.80	8.80	--	--	--	2.40
Chromium	--	--	--	68800.0	--	--	--	--	--	--	--	--	--	--	--	--
Copper	41.80	46.20	--	78.30	28.60	--	43.80	--	88.0	--	46.30	78.70	--	--	--	38.30
Lead	58.30	38.40	80.8	53.80	28.40	58.0	88.80	--	138.20 J	--	81.1	88.10	--	--	--	81.40
Manganese	--	--	--	228.0	--	--	--	--	--	--	880.0 J	--	--	--	--	--
Selenium	0.42 BJ	0.22 BJ	--	0.24 BJ	0.15 BJ	0.71 BJ	0.18 BJ	--	0.21 BJ	--	0.18 BJ	0.28 BJ	--	--	--	0.17 B
Silver	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Thallium	0.280 B	0.24 B	--	0.15 BJ	0.27 B	--	0.28 B	--	0.18 BJ	--	2.83	0.21 B	--	--	--	0.21 B
Zinc	185.0	180.0	--	2110.0	118.0	142.0	300.0	--	2370.0	--	303.0	280.0	--	--	--	221.0
Cyanide	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
TENTATIVELY IDENTIFIED COMPOUNDS	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB
1-ETHYLDENE-1H-INDENE	--	--	--	--	--	--	--	--	--	120.0 JM	--	--	--	--	--	--

Pesticides and PCBs, several of which are cancer causing compounds, were detected at significant levels in thirteen of the sixteen soil/sediment samples. These contaminants were detected in both shallow and deep samples. Pesticides and PCBs were detected in samples X103, X104, X106, X110, and X114 taken from the park. Unlike the volatiles and semi-volatiles, pesticides and PCB contamination were detected not only on site, but also in samples derived from neighboring backyards. The contaminated samples taken from the residential are X105, X109, and X116. For a review of all contaminants detected in samples taken during the sampling portion of the Integrated Assessment, the reader is referred to Table 3-2 for the Sample Summary Table. (Table 3-2 can also be found at the front of Appendix I).

4. IDENTIFICATION OF SOURCES

4.1 INTRODUCTION

This section discusses the hazardous waste source which has been identified at this site during the initial stages of the CERCLA site investigation.

Information concerning the size, volume and waste composition of each source has been derived throughout the initial Site Assessment and subsequent site inspection sampling action. It should be pointed out however, that the total number and nature of the sources may be subject to change. As the site progresses through the CERCLA site investigation program and receives further investigation. The Yvonne Sauget (Trust) site has one source that can be identified and used of HRS scoring purposes. This source is contaminated soil.

4.2 CONTAMINATED SOIL

In correlation to the soil samples collected during the December 8 and 9, 1992 sampling of the Yvonne Sauget (Trust) site, analytical results indicate that the soil materials that make up the site are contaminated with hazardous substances. These hazardous constituents were detected in soils from the Sauget Mini-Park, on land to the north northwest of the park but still considered on-site (MTS, Inc.), land abutting the park along the park's northeast fence and three neighboring residential yards. Contaminated soils were found as shallow as 10 inches deep and as deep as 20 feet deep. There is no containment for this source. As previously mentioned, the site is an estimated two and a half acres in size.

Aerial photographs indicate that operations at the site began in the late 1940's and remained

steady until sometime between 1976 and 1978. An aerial photograph taken January of 1986 shows that the land where the pit had been located for approximately 25 years had been built up to adjacent topography and had four trailer homes located on it. An aerial photograph taken in December of 1991 shows that the trailer homes had been removed and the Sauget Mini-Park had been built on a large portion of the site.

Analysis of soil samples obtained during the site inspection portion of the Integrated Assessment conducted at Yvonne Sauget revealed elevated levels of contaminants at the site. These hazardous constituents were detected in shallow samples and deep borings. Contaminated shallow samples which as X101, X102, X104, X107, X110, and X111 would suggest that the materials used to fill the hazardous materials. Please note, the pesticide and PCB contaminants found in the shallow samples were also found in the deep samples.

During the sampling of the X114, which went to a depth of 20 feet, drilling went beyond fill material. The contaminated deep samples are an indication of the materials present in the pit during the years of operation. Considering the time period, the lack of environmental concern and/or lack of awareness of the potential damage that hazardous materials can cause to the environment, and the appearance of operations from the aerial photographs, wastes were allowed to accumulate in the ground with little or no clean-up attempted. Due to these practices and the analytical data derived from the site sampling, it appears that contaminated soils still exist at the site.

5. MIGRATION PATHWAYS

5.1 INTRODUCTION

The CERCLA Site Assessment Program identifies three migration pathways and one exposure pathway by which hazardous substances may pose a threat to human health and/or the environment. Consequently, sites are evaluated on their known or potential impact to these four pathways. The pathways evaluated are groundwater migration, surface water migration, soil exposure and air migration.

This section presents and discusses information collected during the site inspection of the Yvonne Sauget (Trust) site, also, known as Site K. This information, together with information documented in other sources, will be utilized in analyzing the site's impact on the four pathways and the various human and environmental targets within the established target distance limits.

Discussions of the pathways will include pathway descriptions, contaminant sources, and targets, such as human populations and endangered species, and other sensitive environments.

5.2 GROUNDWATER PATHWAY

The Yvonne Sauget (Trust) site is located in what is known as the American Bottoms. The uppermost bedrock formations found in the area of the site consist of glacial outwash and unconsolidated alluvium. The two main bedrock formations in the area of the site are the St. Genevieve and St. Louis made up of limestones. According to Ecology and Environment, the St. Genevieve and St. Louis limestone are a part of the Mississippian System. The Mississippian

System can be found lying beneath the Mississippian. Limestone, sandstone and shale are incorporated in the Devonian System. Underneath the Devonian System is the Silurian System which contains several layers of limestone. The Ordovician System is located below the Silurian System. The Ordovician System consists of a variety of formations such as sandstone, limestone, dolomite and shale. Under the latter system is the Cambrian-Age sandstone, limestone, dolomite and shale. The deepest formation known is the Precambrian formation which contains granitic, crystalline rock. (Please refer to Figure 5-1.)

In their study at the Yvonne Sauget (Trust) site, E&E completed 20 foot boring to determine the makeup of the materials at the site. E&E reported to determine the makeup of the materials at the site. E&E reported that 10 to 15 feet of fill material made up of brown silty clay, sand and rock or pieces of brick were established above discontinuous layers of fine to coarse sand and silty clay. (Please refer to figure 5-2.) E&E noted that waste materials were not directly observed but that toward the bottom of each boring the soils were stained black. This was, also, the case for the deep borings collected during the site inspection. Black stained fill material was observed in samples X104, X106, and X114. (Refer to Appendix F for the boring logs.) E&E reached water at seven to ten feet below the surface for each boring. This coincides with the borings collected by the IEPA. During the CERCLA site inspection, the materials in the deep boring were found to be wet starting at the depth of 11 feet.

No groundwater samples were collected during the December 8 and 9, 1992 inspection of the Yvonne Sauget (Trust) site. The groundwater pathway will not be evaluated for the Yvonne Sauget (Trust) site. Although groundwater is found at the shallow depth of approximately 10

feet, there are no known groundwater wells in use within a four-mile radius of the site.

Drinking water in the neighboring area of the Yvonne Sauget (Trust) site is derived for the Mississippi River.

ERA	SYSTEM	GROUP	GEOLOGIC MATERIAL	
CENOZOIC	QUATERNARY			
PALEOZOIC	PENNSYLVANIAN	McLEANSBORO		
		KEWANEE		
		MCCORMICK		
	MISSISSIPPIAN			
		OKAW		
		PAINT CREEK		
		MERAMEC		
		OSAGE		
		NORTH HILL		
	DEVONIAN	NEW ALBANY		
	SILURIAN	BANBRIDGE		
	ORDOVICIAN	MAQUOKETA		
		GALENA		
		PLATTEVILLE		
		ANCELL		
	FRANK DUCHEN			
CAMBRIAN				
PRECAMBRIAN				


LEGEND

	SILT, CLAY, SILTY SAND
	SAND AND GRAVEL
	LIMESTONE
	SANDSTONE
	SHALE
	CHERT
	DOLOMITE, DOLOMITIC LIMESTONE
	GRANITIC, CRYSTALLINE ROCK

SOURCE: ISGS, 1971

Generalized Geologic Column For South-Central Illinois

Figure 5-1



Generalized Geologic Cross Section
Figure 5-2

5.3 SURFACE WATER PATHWAY

Approximately one quarter of a mile west of the Yvonne Sauget (Trust) site is an intermittent stream known as Dead Creek. Dead Creek, divided into six segments, in one of the many other projects that Ecology and Environment investigated during their Expanded Site Investigation and found to be contaminated with hazardous constituents. Approximately one and a half miles further west is the Mississippi River. A little less than one quarter of a mile south southeast of the Yvonne Sauget (Trust) site is a small intermittent stream.

Drainage from the site has the potential to flow in two directions. The most southwestern residential area located on the southwest fence of the site, sits approximately four feet lower than the site itself. This would allow for surface drainage along the southwest portion of the southwest fence to flow toward the residential houses. However, due to surrounding topography on a larger scale, the overall drainage from the site would be likely to runoff in a northeasterly direction.

An estimated two thirds of the Yvonne Sauget (Trust) site is located within an area of a 100-year flood boundary according to the National Flood Insurance Rate Maps.

Illinois American Water provides municipal water for the area of the Yvonne Sauget (Trust) site. This water originates from the Mississippi River. Due to the fact that the surface water drainage from the Yvonne Sauget (Trust) site would be unlikely to flow into the Mississippi River or any other surface water body, no surface water samples were collected during the December 8 and 9, 1992 CERCLA site inspection. Therefore, the surface pathway will be evaluated for this site.

5.4 SOIL EXPOSURE PATHWAY

Soil samples taken during the site inspection were obtained from eleven locations on-site (with a duplicate collected at one of the locations) and five off-site, one being a background sample. Sample results indicate an observed release in the soil exposure pathway by contaminants that are within the top two feet of soil or cover material. Compounds found three times above background concentrations or above detection limits from this sampling effort are considered valid as a confirmed release to the soil exposure pathway (please refer to Tables 3-1 and 3-2). Contributing factors to this contamination have been discussed previously.

During the approximate 25 years of operation, various degrees of surface disturbance has occurred at the site. There is no known record of the number of workers on-site during the years of operation or the number of workers and residents that have been on site since operations ceased in the late 1970's. (The CERCLA Preliminary Assessment Report completed in 1988 documents the existence of four residential homes in the previous location of the pit.) These people could have potentially contacted contaminated air. The same could be said about those individuals who had been or now frequent the site.

Currently the Sauget Mini-Park is situated on the majority of the Yvonne Sauget (Trust) site. The park mainly consists of a volleyball court, a playground area, a pavilion and several picnic tables and grills. The site extends a little further beyond the park to the northwest, which is a gravel road. The park is meant for recreational purposes for adult and children alike. There exists a potential danger, especially where the children are concerned, for coming in contact with contaminated soils, especially if the ground is disturbed (for example, if a child plays in the dirt at

the site). Contamination, below current grade, is known to exist from grade surface to 20 feet below grade. The nearest individuals are located southwest of the southwest fence of the Yvonne Sauget (Trust) site. There are an estimated 13 single family houses in this residential area. They are located approximately 20 feet southwest of site. Analysis of three samples (X105, X109, and X116) collected from three different backyards indicates the presence of pesticides and PCBs that were, also, detected at the Yvonne Sauget (Trust) site. There are no known schools or daycare facilities on or within 200 feet of contaminated areas. Within a 4-mile radius of the site the population is calculated to be approximately 93,931 persons. The following table represents the estimated nearby populations (please refer to Appendix G for the CENTRACTS reports that identifies these populations).

Table 5-1 Populations Nearby the Yvonne Sauget (Trust) Site

DISTANCE	POPULATION
0-1/4 Mile	33
1/4-1/2 Mile	82
1/2-1 Mile	414
1-2 Mile	6,954
2-3 Mile	30,220
3-4 Mile	56,228

According to the Illinois Department of Conservation, there are no known sensitive resources on-site or within the area of concern for this site.

5.5 AIR PATHWAY

A photoionization detector(HNU) with an 11.7 eV lamp and an organic vapor analyzer (OVA)

were used to survey the ambient air that was released from material derived from the borings. The background reading from the OVA was at zero units and the background reading from the HNU was at six units. The high reading on the OVA for sample X103 was 800 units at approximately 13 feet deep. Sample X108 had a reading on the OVA at greater than 1000 units at about 12 feet deep. Soil sample X106 had an OVA reading at greater than 1000 units at approximately two and a half and 15 feet deep. The high reading for sample X114 was greatest reading from the HNU was at eight units above background during the boring of sample X103.

During the site inspection portion of the Integrated Assessment, no documented releases to the air were observed. For this reason the air migration pathway will not be evaluated.

6. BIBLIOGRAPHY

Ecology and Environment, Inc., 1988, Expanded Site Investigation Dead Creek Project Sites at Cahokia/Sauget Illinois; Final Report, Volume 1 of 2.

Illinois Environmental Protection Agency, 1991, Potential Hazardous Waste Site Preliminary Assessment for the Yvonne Sauget (Trust) site, ILD982073611, prepared by Tim Murphy, Springfield, Illinois.

Illinois State Museum by Colten, Craig E., Historical Assessment of Hazardous Waste Management in Madison and St. Clair Counties, Illinois, 1890-1980.

Illinois State Water Survey, 1968, Groundwater Levels and Pumpage on the East St. Louis Area, Illinois, 1962-1966, Circular 95.

SDMS US EPA Region V

Imagery Insert Form

**Some images in this document may be illegible or unavailable in SDMS.
Please see reason(s) indicated below:**

☐

Illegible due to bad source documents. Image(s) in SDMS is equivalent to hard copy.

Specify Type of Document(s) / Comment

☐

Confidential Business Information (CBI).

This document contains highly sensitive information. Due to confidentiality, materials with such information are not available in SDMS. You may contact the EPA Superfund Records Manager if you wish to view this document.

Specify Type of Document(s) / Comment

☒

Unscannable Material: Oversized X or Format.

Due to certain scanning equipment capability limitations, the document page(s) is not available in SDMS. The original document is available for viewing at the Superfund Records center.

Specify Type of Document(s) / Comment

☐

Other:

APPENDIX B

APPENDIX B

USEPA FORM

2070-13



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 1 - SITE LOCATION AND INSPECTION INFORMATION

I. IDENTIFICATION
01 STATE **IL** 02 SITE NUMBER **982073611**

II. SITE NAME AND LOCATION

01 SITE NAME (Legal, common, or descriptive name of site) **Yvonne Sauget (Trust)** 02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER **Park NE of Queens Ave. + Ogden Ave. Intersection**
03 CITY **Sauget** 04 STATE **IL** 05 ZIP CODE **62206** 06 COUNTY **St. Clair** 07 COUNTY CODE **163** 08 CONG DIST **22**
09 COORDINATES
LATITUDE **38° 35' 22"** LONGITUDE **90° 10' 00"** 10 TYPE OF OWNERSHIP (Check one)
☒ A. PRIVATE ☐ B. FEDERAL ☐ C. STATE ☐ D. COUNTY ☐ E. MUNICIPAL
☐ F. OTHER ☐ G. UNKNOWN

III. INSPECTION INFORMATION

01 DATE OF INSPECTION **12/8/92** 02 SITE STATUS ☐ ACTIVE ☒ INACTIVE 03 YEARS OF OPERATION **~ 1950** **~ 1977** ☐ UNKNOWN
MONTH DAY YEAR BEGINNING YEAR ENDING YEAR
04 AGENCY PERFORMING INSPECTION (Check all that apply)
☒ A. EPA ☐ B. EPA CONTRACTOR ☐ C. MUNICIPAL ☐ D. MUNICIPAL CONTRACTOR
☐ E. STATE ☐ F. STATE CONTRACTOR ☐ G. OTHER

05 CHIEF INSPECTOR	06 TITLE	07 ORGANIZATION	08 TELEPHONE NO.
Sheila Murphy	Environmental Protection Specialist	IEPA	(618) 993-7200
09 OTHER INSPECTORS	10 TITLE	11 ORGANIZATION	12 TELEPHONE NO.
Ken Corkill	Environmental Protection Specialist	IEPA	(217) 782-6760
Kim Nika	Environmental Protection Specialist	IEPA	(217) 782-6760
Greg Spencer	Environmental Protection Specialist	IEPA	(217) 782-6760
			()
			()

13 SITE REPRESENTATIVES INTERVIEWED	14 TITLE	15 ADDRESS	16 TELEPHONE NO.
Paul Sauget	Mayor	2897 Falling Springs Rd. Sauget	(618) 337-5267
Mike Williams	Village Employee	2897 Falling Springs Rd. Sauget	(618) 337-5267
			()
			()
			()
			()

17 ACCESS GAINED BY (Check one)
☒ PERMISSION ☐ WARRANT 18 TIME OF INSPECTION **Began at 10:45AM December 8, 1993** 19 WEATHER CONDITIONS **Sunny, about 37° F**

IV. INFORMATION AVAILABLE FROM

01 CONTACT	02 OF (Agency/Organization)	03 TELEPHONE NO.
Paul Sauget	Mayor and Representative of site	(618) 337-5267
04 PERSON RESPONSIBLE FOR SITE INSPECTION FORM	05 AGENCY	06 ORGANIZATION
Sheila Murphy Williams	IEPA	(618) 993-7200
		07 TELEPHONE NO.
		(618) 993-7200
		08 DATE 9/30/93
		MONTH DAY YEAR



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 2 - WASTE INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
IL 982073611

II. WASTE STATES, QUANTITIES, AND CHARACTERISTICS

01 PHYSICAL STATES (Check all that apply) <input type="checkbox"/> A. SOLID <input type="checkbox"/> B. POWDER, FINES <input type="checkbox"/> C. SLUDGE <input type="checkbox"/> D. OTHER _____ (Specify)	02 WASTE QUANTITY AT SITE (Measures of waste quantities must be independent) TONS _____ CUBIC YARDS _____ NO. OF DRUMS _____	03 WASTE CHARACTERISTICS (Check all that apply) <input checked="" type="checkbox"/> A. TOXIC <input type="checkbox"/> B. CORROSIVE <input type="checkbox"/> C. RADIOACTIVE <input checked="" type="checkbox"/> D. PERSISTENT <input type="checkbox"/> E. SOLUBLE <input type="checkbox"/> F. INFECTIOUS <input checked="" type="checkbox"/> G. FLAMMABLE <input type="checkbox"/> H. IGNITABLE <input type="checkbox"/> I. HIGHLY VOLATILE <input type="checkbox"/> J. EXPLOSIVE <input type="checkbox"/> K. REACTIVE <input type="checkbox"/> L. INCOMPATIBLE <input type="checkbox"/> M. NOT APPLICABLE
---	--	--

III. WASTE TYPE

CATEGORY	SUBSTANCE NAME	01 GROSS AMOUNT	02 UNIT OF MEASURE	03 COMMENTS
SLU	SLUDGE	unknown		Materials placed in the previous pit are unknown. The following contaminants were detected: 1 volatile, 6 semi-volatiles, 15 Pesticides/PCBs + 13 metals
OLW	OILY WASTE			
SOL	SOLVENTS			
PSD	PESTICIDES			
OCC	OTHER ORGANIC CHEMICALS			
IOC	INORGANIC CHEMICALS			
ACD	ACIDS			
BAS	BASES			
MES	HEAVY METALS			

IV. HAZARDOUS SUBSTANCES (See Appendix for most frequently cited CAS Numbers)

01 CATEGORY	02 SUBSTANCE NAME	03 CAS NUMBER	04 STORAGE/DISPOSAL METHOD	05 CONCENTRATION	06 MEASURE OF CONCENTRATION
PSD	Dieldrin	—	Disposal onto ground	210.0	PPB
PSD	4,4'-DDE	72-55-9	"	560.0	PPB
PSD	Endrin	—	"	17.0	PPB
PSD	Endosulfan II	33213-65-9	"	240.0	PPB
PSD	Endosulfan Sulfate	1031-07-8	"	38.0	PPB
PSD	4,4'-DDT	—	"	540.0	PPB
PSD	Endrin Ketone	53194-70-5	"	5.6	PPB
PSD	Endrin aldehyde	—	"	13.0	PPB
PSD	alpha-Chlordane	5103-71-9	"	29.0	PPB
PSD	gamma-Chlordane	5103-74-2	"	22.0	PPB
PCB	Aroclor-1221	11104-28-2	"	310.0	PPB
PCB	Aroclor-1242	53469-21-9	"	420.0	PPB
PCB	Aroclor-1254	11097-69-1	"	540.0	PPB
PCB	Aroclor-1260	11096-82-5	"	4000.0	PPB
PCB	Aroclor-1016	12674-11-2	"	1200.0	PPB
	Chrysene	218-01-9	"	470.0	PPB

V. FEEDSTOCKS (See Appendix for CAS Numbers)

CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER	CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER
FDS			FDS		
FDS			FDS		
FDS			FDS		
FDS			FDS		

VI. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

IDOT Historical Aerial Photographs
CERCLA Preliminary Assessment
IEPA Analytical Data
Ecology + Environment, Inc. Expanded Site Investigation, Dead Creek Project Sites



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE **IL** 02 SITE NUMBER **982073611**

II. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

01 ☐ J. DAMAGE TO FLORA
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

None documented or observed.

01 ☐ K. DAMAGE TO FAUNA
04 NARRATIVE DESCRIPTION (include names of species)

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

None documented or observed.

01 ☐ L. CONTAMINATION OF FOOD CHAIN
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

None documented or observed.

01 ☒ M. UNSTABLE CONTAINMENT OF WASTES
(Spills/Runoff/Standing liquids, Leaking drums)

02 ☒ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: _____

04 NARRATIVE DESCRIPTION

Historical aerial photographs documented standing liquids during operations

01 ☐ N. DAMAGE TO OFFSITE PROPERTY
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

None documented or observed.

01 ☐ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

None documented or observed.

01 ☒ P. ILLEGAL/UNAUTHORIZED DUMPING
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

Operations most likely predated any environmental regulations. However, the site is CURRENTLY contaminated.

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

None

III. TOTAL POPULATION POTENTIALLY AFFECTED: _____

IV. COMMENTS

V. SOURCES OF INFORMATION (Cite specific references, e. g., state files, sample analysis, reports)

CERCLA Screening Site Inspection - 12/92
IDOT Historical Aerial Photographs
IEPA Analytical Data



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
IL 982073611

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☒ A. GROUNDWATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

No groundwater samples were collected. However, groundwater contamination is probable. Groundwater was reached at 11'. Contaminated soil/materials were detected to a depth of 20'.

01 ☐ B. SURFACE WATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

None observed or documented.

01 ☐ C. CONTAMINATION OF AIR 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

None documented or observed

01 ☐ D. FIRE/EXPLOSIVE CONDITIONS 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

None documented or observed.

01 ☒ E. DIRECT CONTACT 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

None documented or observed. However, the majority of the site is a recreational park + contamination was found at less than 2' deep.

01 ☒ F. CONTAMINATION OF SOIL 02 ☒ OBSERVED (DATE: 12/8-9/92) ☐ POTENTIAL ☐ ALLEGED
03 AREA POTENTIALLY AFFECTED: 2.5 (Acres) 04 NARRATIVE DESCRIPTION

Contamination was detected as shallow as 10" deep and as deep as 20'.

01 ☐ G. DRINKING WATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

None documented or observed.

01 ☐ H. WORKER EXPOSURE/INJURY 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 WORKERS POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

None documented or observed.

01 ☐ I. POPULATION EXPOSURE/INJURY 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

None documented or observed.



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION
PART 4 - PERMIT AND DESCRIPTIVE INFORMATION

I. IDENTIFICATION

01 STATE **IL** 02 SITE NUMBER **982073611**

II. PERMIT INFORMATION

01 TYPE OF PERMIT ISSUED (Check all that apply)	02 PERMIT NUMBER	03 DATE ISSUED	04 EXPIRATION DATE	05 COMMENTS
<input type="checkbox"/> A. NPDES NONE				
<input type="checkbox"/> B. UIC				
<input type="checkbox"/> C. AIR				
<input type="checkbox"/> D. RCRA				
<input type="checkbox"/> E. RCRA INTERIM STATUS				
<input type="checkbox"/> F. SPCC PLAN				
<input type="checkbox"/> G. STATE (Specify)				
<input type="checkbox"/> H. LOCAL (Specify)				
<input type="checkbox"/> I. OTHER (Specify)				
<input type="checkbox"/> J. NONE				

III. SITE DESCRIPTION

01 STORAGE/ DISPOSAL (Check all that apply)	02 AMOUNT	03 UNIT OF MEASURE	04 TREATMENT (Check all that apply)	05 OTHER
<input checked="" type="checkbox"/> A. SURFACE IMPOUNDMENT	~84,000	Cubic yards	<input type="checkbox"/> A. INCINERATION	<input checked="" type="checkbox"/> A. BUILDINGS ON SITE
<input type="checkbox"/> B. PILES			<input type="checkbox"/> B. UNDERGROUND INJECTION	Pavilion
<input type="checkbox"/> C. DRUMS, ABOVE GROUND			<input type="checkbox"/> C. CHEMICAL/PHYSICAL	
<input type="checkbox"/> D. TANK, ABOVE GROUND			<input type="checkbox"/> D. BIOLOGICAL	
<input type="checkbox"/> E. TANK, BELOW GROUND			<input type="checkbox"/> E. WASTE OIL PROCESSING	
<input type="checkbox"/> F. LANDFILL			<input type="checkbox"/> F. SOLVENT RECOVERY	
<input type="checkbox"/> G. LANDFARM			<input type="checkbox"/> G. OTHER RECYCLING/RECOVERY	
<input type="checkbox"/> H. OPEN DUMP			<input type="checkbox"/> H. OTHER (Specify)	
<input type="checkbox"/> I. OTHER (Specify)				

07 COMMENTS

IV. CONTAINMENT

01 CONTAINMENT OF WASTES (Check one)

☐ A. ADEQUATE, SECURE ☐ B. MODERATE ☒ C. INADEQUATE, POOR ☐ D. INSECURE, UNSOUND, DANGEROUS

02 DESCRIPTION OF DRUMS, DIKING, LINERS, BARRIERS, ETC.

Due to the fact that operations predated any environmental regulations, it is highly unlikely that any form of containment (ex. liner) exists at the Yvonne Sauger (Trust) site.

V. ACCESSIBILITY

01 WASTE EASILY ACCESSIBLE: ☒ YES ☐ NO

02 COMMENTS
Contaminated soil/materials were documented as shallow as 10" below surface - probable contamination closer to the surface.

VI. SOURCES OF INFORMATION (Cite specific references, e.g. state files, sample analysis, reports)

IDOT Historical Aerial Photographs
CERCLA Screening Site Inspection
St. Clair County Tax Assessors Office



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION

01 STATE IL 02 SITE NUMBER 982073611

II. DRINKING WATER SUPPLY

01 TYPE OF DRINKING SUPPLY
(Check as applicable)

SURFACE WELL
COMMUNITY A. ☒ B. ☐
NON-COMMUNITY C. ☒ D. ☐

02 STATUS

ENDANGERED AFFECTED MONITORED
A. ☐ B. ☐ C. ☒
D. ☐ E. ☐ F. ☒

03 DISTANCE TO SITE

A. 1.5 (mi)
B. _____ (mi)

III. GROUNDWATER

01 GROUNDWATER USE IN VICINITY (Check one)

☐ A. ONLY SOURCE FOR DRINKING ☐ B. DRINKING
(Other sources available)
COMMERCIAL, INDUSTRIAL, IRRIGATION
(No other water sources available)
☐ C. COMMERCIAL, INDUSTRIAL, IRRIGATION
(Limited other sources available)
☒ D. NOT USED, UNUSEABLE

02 POPULATION SERVED BY GROUND WATER 0

03 DISTANCE TO NEAREST DRINKING WATER WELL NA (mi)

04 DEPTH TO GROUNDWATER

~11 (ft)

05 DIRECTION OF GROUNDWATER FLOW

unknown

06 DEPTH TO AQUIFER
OF CONCERN

N.A. (ft)

07 POTENTIAL YIELD
OF AQUIFER

N.A. (gpd)

08 SOLE SOURCE AQUIFER

☐ YES ☐ NO

09 DESCRIPTION OF WELLS (including useage, depth, and location relative to population and buildings)

N.A.

10 RECHARGE AREA

☐ YES COMMENTS
☐ NO

11 DISCHARGE AREA

☐ YES COMMENTS
☐ NO

IV. SURFACE WATER

01 SURFACE WATER USE (Check one)

☒ A. RESERVOIR, RECREATION
DRINKING WATER SOURCE ☐ B. IRRIGATION, ECONOMICALLY
IMPORTANT RESOURCES ☐ C. COMMERCIAL, INDUSTRIAL ☐ D. NOT CURRENTLY USED

02 AFFECTED/POTENTIALLY AFFECTED BODIES OF WATER

NAME: None suspected to be affected by this site.

AFFECTED

DISTANCE TO SITE

V. DEMOGRAPHIC AND PROPERTY INFORMATION

01 TOTAL POPULATION WITHIN

0-1 mile

ONE (1) MILE OF SITE

A. 527
NO. OF PERSONS

1-2 miles

TWO (2) MILES OF SITE

B. 6954
NO. OF PERSONS

2-3 miles

THREE (3) MILES OF SITE

C. 30,220
NO. OF PERSONS

02 DISTANCE TO NEAREST POPULATION

20 feet (mi)

03 NUMBER OF BUILDINGS WITHIN TWO (2) MILES OF SITE

>1,000

04 DISTANCE TO NEAREST OFF-SITE BUILDING

20 feet (mi)

05 POPULATION WITHIN VICINITY OF SITE (Provide narrative description of nature of population within vicinity of site, e.g., rural, village, densely populated urban area)

The area in the vicinity of Yvonne Sarget (Trust) site is densely populated with residential homes and industries.



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
IL 92073611

VI. ENVIRONMENTAL INFORMATION

01 PERMEABILITY OF UNSATURATED ZONE (Check one)

☐ A. 10^{-8} - 10^{-6} cm/sec ☐ B. 10^{-4} - 10^{-6} cm/sec ☒ C. 10^{-4} - 10^{-3} cm/sec ☐ D. GREATER THAN 10^{-3} cm/sec

02 PERMEABILITY OF BEDROCK (Check one)

☐ A. IMPERMEABLE (Less than 10^{-8} cm/sec) ☐ B. RELATIVELY IMPERMEABLE (10^{-4} - 10^{-6} cm/sec) ☒ C. RELATIVELY PERMEABLE (10^{-2} - 10^{-4} cm/sec) ☐ D. VERY PERMEABLE (Greater than 10^{-2} cm/sec)

03 DEPTH TO BEDROCK

~20 (ft)

04 DEPTH OF CONTAMINATED SOIL ZONE

10"-20'+ (ft)

05 SOIL pH

-

06 60% PRECIPITATION

35.4 80 year avg. (in)

07 ONE YEAR 24 HOUR RAINFALL

(in)

08 SLOPE

SITE SLOPE 0%

DIRECTION OF SITE SLOPE

Northeast

TERRAIN AVERAGE SLOPE

0%

09 FLOOD POTENTIAL

SITE IS IN 100 YEAR FLOODPLAIN

10

☐ SITE IS ON BARRIER ISLAND, COASTAL HIGH HAZARD AREA, RIVERINE FLOODWAY

11 DISTANCE TO WETLANDS (5 acre minimum)

ESTUARINE

A. 1 7/8 (mi)

OTHER

B. - (mi)

12 DISTANCE TO CRITICAL HABITAT (of endangered species)

None (mi)

ENDANGERED SPECIES: None

13 LAND USE IN VICINITY

DISTANCE TO:

COMMERCIAL/INDUSTRIAL

RESIDENTIAL AREAS, NATIONAL/STATE PARKS, FORESTS, OR WILDLIFE RESERVES


AGRICULTURAL LANDS
PRIME AG LAND AG LAND

A. adjacent to site

B. adjacent to site

C. >2 (mi) D. - (mi)

14 DESCRIPTION OF SITE IN RELATION TO SURROUNDING TOPOGRAPHY



VII. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

ISGS 7.5 Topo Map
CERCLA Screening Site Inspection
National Flood Insurance Rate Map
Ecology + Environment, Inc. Expanded Site Investigation



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 6 - SAMPLE AND FIELD INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
IL 992073611

II. SAMPLES TAKEN

SAMPLE TYPE	01 NUMBER OF SAMPLES TAKEN	02 SAMPLES SENT TO	03 ESTIMATED DATE RESULTS AVAILABLE
GROUNDWATER			
SURFACE WATER			
WASTE			
AIR			
RUNOFF			
SPILL			
SOIL	16	IEPA Laboratories	4/6/93
VEGETATION			
OTHER			

III. FIELD MEASUREMENTS TAKEN

01 TYPE	02 COMMENTS
Samples	Measurements were taken for the location of samples.

IV. PHOTOGRAPHS AND MAPS

01 TYPE <input checked="" type="checkbox"/> GROUND <input checked="" type="checkbox"/> AERIAL	02 IN CUSTODY OF IEPA <small>(Name of organization or individual)</small>
03 MAPS <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	04 LOCATION OF MAPS onsite + vicinity

V. OTHER FIELD DATA COLLECTED (Provide narrative description)

VI. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

CERCLA Screening Site Inspection
IDOT Historical Aerial Photographs
IEPA Laboratories

EPA FORM 2070-13 (7-81)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 8 - OPERATOR INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
IL 982073611

II. CURRENT OPERATOR (Provide if different from owner)

OPERATOR'S PARENT COMPANY (If applicable)

01 NAME Park Village of Sauget		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.) 2897 Falling Springs Rd.		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY Sauget		06 STATE IL	07 ZIP CODE 62206	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION ~2 years	09 NAME OF OWNER Village of Sauget						

III. PREVIOUS OPERATOR(S) (List most recent first; provide only if different from owner)

PREVIOUS OPERATORS' PARENT COMPANIES (If applicable)

01 NAME Yvonne Lame Sauget Trust		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.) 17 Thornhurst Ct		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY Columbia		06 STATE IL	07 ZIP CODE 62236	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION ~25	09 NAME OF OWNER DURING THIS PERIOD Yvonne Lame Sauget Trust						

01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION	09 NAME OF OWNER DURING THIS PERIOD						
01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION	09 NAME OF OWNER DURING THIS PERIOD						

IV. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

St. Clair County Tax Assessor's Office



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 9 - GENERATOR/TRANSPORTER INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
IL 982073611

II. ON-SITE GENERATOR

01 NAME N.A.		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE	
05 CITY	06 STATE	07 ZIP CODE	

III. OFF-SITE GENERATOR(S)

01 NAME N.A.		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE	
05 CITY	06 STATE	07 ZIP CODE		05 CITY	06 STATE	07 ZIP CODE	
01 NAME		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE	
05 CITY	06 STATE	07 ZIP CODE		05 CITY	06 STATE	07 ZIP CODE	

IV. TRANSPORTER(S)

01 NAME N.A.		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE	
05 CITY	06 STATE	07 ZIP CODE		05 CITY	06 STATE	07 ZIP CODE	
01 NAME		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE	
05 CITY	06 STATE	07 ZIP CODE		05 CITY	06 STATE	07 ZIP CODE	

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
IL 982073611

II. PAST RESPONSE ACTIVITIES

01 ☐ A. WATER SUPPLY CLOSED

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

None

01 ☐ B. TEMPORARY WATER SUPPLY PROVIDED

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

None

01 ☐ C. PERMANENT WATER SUPPLY PROVIDED

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

None

01 ☐ D. SPILLED MATERIAL REMOVED

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

None

01 ☐ E. CONTAMINATED SOIL REMOVED

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

None

01 ☐ F. WASTE REPACKAGED

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

None

01 ☐ G. WASTE DISPOSED ELSEWHERE

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

None

01 ☐ H. ON SITE BURIAL

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

None

01 ☐ I. IN SITU CHEMICAL TREATMENT

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

None

01 ☐ J. IN SITU BIOLOGICAL TREATMENT

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

None

01 ☐ K. IN SITU PHYSICAL TREATMENT

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

None

01 ☐ L. ENCAPSULATION

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

None

01 ☐ M. EMERGENCY WASTE TREATMENT

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

None

01 ☐ N. CUTOFF WALLS

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

None

01 ☐ O. EMERGENCY DIKING/SURFACE WATER DIVERSION

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

None

01 ☐ P. CUTOFF TRENCHES/SUMP

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

None

01 ☐ Q. SUBSURFACE CUTOFF WALL

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

None



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
IL 982073611

II. PAST RESPONSE ACTIVITIES (Continued)

01 ☐ R. BARRIER WALLS CONSTRUCTED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None

01 ☐ S. CAPPING/COVERING
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

Site had fill material (contaminated) put on it to grade to surrounding topography.

01 ☐ T. BULK TANKAGE REPAIRED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None

01 ☐ U. GROUT CURTAIN CONSTRUCTED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None

01 ☐ V. BOTTOM SEALED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None

01 ☐ W. GAS CONTROL
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None

01 ☐ X. FIRE CONTROL
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None

01 ☐ Y. LEACHATE TREATMENT
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None

01 ☐ Z. AREA EVACUATED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None

01 ☐ 1. ACCESS TO SITE RESTRICTED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

Site is accessible.

01 ☐ 2. POPULATION RELOCATED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None

01 ☐ 3. OTHER REMEDIAL ACTIVITIES
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None

III. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

CERCLA Screening Site Inspection
IDOT Aerial Photographs.



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 11 - ENFORCEMENT INFORMATION

I. IDENTIFICATION

01 STATE

02 SITE NUMBER

IL

98207364

II. ENFORCEMENT INFORMATION

01 PAST REGULATORY/ENFORCEMENT ACTION ☐ YES ☒ NO

02 DESCRIPTION OF FEDERAL, STATE, LOCAL REGULATORY/ENFORCEMENT ACTION

None.

III. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

Operations occurred prior to Environmental Regulations.

APPENDIX C

TARGET COMPOUND

LIST

TARGET COMPOUND LIST

Volatile Target Compounds

Chloromethane	1,2-Dichloropropane
Bromomethane	cis-1,3-Dichloropropene
Vinyl Chloride	Trichloroethene
Chloroethane	Dibromochloromethane
Methylene Chloride	1,1,2-Trichloroethane
Acetone	Benzene
Carbon Disulfide	trans-1,3-Dichloropropene
1,1-Dichloroethene	Bromoform
1,1-Dichloroethane	4-Methyl-2-pentanone
1,2-Dichloroethene (total)	2-Hexanone
Chloroform	Tetrachloroethene
1,2-Dichloroethane	1,1,2,2-Tetrachloroethane
2-Butanone	Toluene
1,1,1-Trichloroethane	Chlorobenzene
Carbon Tetrachloride	Ethylbenzene
Vinyl Acetate	Styrene
Bromodichloromethane	Xylenes (total)

Base/Neutral Target Compounds

Hexachloroethane	2,4-Dinitrotoluene
bis(2-Chloroethyl) Ether	Diethylphthalate
Benzyl Alcohol	N-Nitrosodiphenylamine
bis(2-Chloroisopropyl) Ether	Hexachlorobenzene
N-Nitroso-Di-n-Propylamine	Phenanthrene
Nitrobenzene	4-Bromophenyl-phenylether
Hexachlorobutadiene	Anthracene
2-Methylnaphthalene	Di-n-Butylphthalate
1,2,4-Trichlorobenzene	Fluoranthene
Isophorone	Pyrene
Naphthalene	Butylbenzylphthalate
4-Chloroaniline	bis(2-Ethylhexyl) Phthalate
bis(2-chloroethoxy) Methane	Chrysene
Hexachlorocyclopentadiene	Benzo(a) Anthracene
2-Chloronaphthalene	3,3'-Dichlorobenzidene
2-Nitroaniline	Di-n-Octyl Phthalate
Acenaphthylene	Benzo(b) Fluoranthene
3-Nitroaniline	Benzo(k) Fluoranthene
Acenaphthene	Benzo(a) Pyrene
Dibenzofuran	Indeno(1,2,3-cd) Pyrene
Dimethyl Phthalate	Dibenz(a,h) Anthracene
2,6-Dinitrotoluene	Benzo(g,h,i) Perylene
Fluorene	1,2-Dichlorobenzene
4-Nitroaniline	1,3-Dichlorobenzene
4-Chlorophenyl-phenylether	1,4-Dichlorobenzene

Acid Target Compounds

Benzoic Acid	2,4,6-Trichlorophenol
Phenol	2,4,5-Trichlorophenol
2-Chlorophenol	4-Chloro-3-methylphenol
2-Nitrophenol	2,4-Dinitrophenol
2-Methylphenol	2-Methyl-4,6-dinitrophenol
2,4-Dimethylphenol	Pentachlorophenol
4-Methylphenol	4-Nitrophenol
2,4-Dichlorophenol	

Pesticide/PCB Target Compounds

alpha-BHC	Endrin Ketone
beta-BHC	Endosulfan Sulfate
delta-BHC	Methoxychlor
gamma-BHC (Lindane)	alpha-Chlorodane
Heptachlor	gamma-Chlorodane
Aldrin	Toxaphene
Heptachlor epoxide	Aroclor-1016
Endosulfan I	Aroclor-1221
4,4'-DDE	Aroclor-1232
Diieldrin	Aroclor-1242
Endrin	Aroclor-1248
4,4'-DDD	Aroclor-1254
Endosulfan II	Aroclor-1260
4,4'-DDT	


Inorganic Target Compounds

Aluminum	Manganese
Antimony	Mercury
Arsenic	Nickel
Barium	Potassium
Beryllium	Selenium
Cadmium	Silver
Calcium	Sodium
Chromium	Thallium
Cobalt	Vanadium
Copper	Zinc
Iron	Cyanide
Lead	Sulfide
Magnesium	Sulfate

APPENDIX D


IEPA

PHOTOGRAPHS

DATE: 11/2/92	SITE ILD#: 982073611 COUNTY: St. Clair
TIME: 12:13 PM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: S. MURPHY	
COMMENTS: Picture taken toward:	
NORTHWEST	
PHOTO #1	


DATE: 11/2/92
TIME: 12:14 PM
PHOTOGRAPH TAKEN BY: S. MURPHY
COMMENTS: Picture taken toward:
NORTHWEST
PHOTO #2



DATE: 11/2/92	SITE ILD#: 982073611 COUNTY: St. Clair
TIME: 12:17 PM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: S. MURPHY	
COMMENTS: Picture taken toward:	
NORTH NORTHWEST	
PHOTO #3	

DATE: 11/2/92
TIME: 12:18 PM
PHOTOGRAPH TAKEN BY: S. MURPHY
COMMENTS: Picture taken toward:
NORTHWEST
PHOTO #4



DATE: 11/2/92	SITE ILD#: 982073611 COUNTY: St. Clair
TIME: 12:20 PM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: S. MURPHY	
COMMENTS: Picture taken toward:	
SOUTH SOUTHEAST	
PHOTO #5	

DATE: 11/2/92
TIME: 12:20 PM
PHOTOGRAPH TAKEN BY: S. MURPHY
COMMENTS: Picture taken toward:
SOUTH
PHOTO #6



DATE: 12/8/92	SITE ILD#: 982073611 COUNTY: St. Clair
TIME: 11:20 AM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: S. MURPHY	
COMMENTS: Picture taken toward:	
SOUTH SOUTHWEST	
PHOTO A-1	

DATE: 12/8/92
TIME: 11:23 AM
PHOTOGRAPH TAKEN BY: K. CORKILL
COMMENTS: Picture taken toward:
NORTHWEST
PHOTO A-2




DATE: 12/8/92	SITE ILID#: 982073611 COUNTY: St. Clair
TIME: 11:25 AM	SITE NAME: YVONNE SAUGET (TRUST)

PHOTOGRAPH TAKEN BY: K. CORKILL
COMMENTS: Picture taken toward:
SOUTHEAST
PHOTO A-3




DATE: 12/8/92
TIME: 11:35 AM
PHOTOGRAPH TAKEN BY: K. CORKILL
COMMENTS: Picture taken toward:
SOUTH SOUTHWEST
PHOTO A-4



DATE: 12/8/92	SITE IL# #: 982073611 COUNTY: St. Clair
TIME: 11:35 AM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: K. CORKILL	
COMMENTS: Picture taken toward:	
SOUTHWEST	
PHOTO A-5	


DATE: 12/8/92
TIME: 11:35 AM
PHOTOGRAPH TAKEN BY: K. CORKILL
COMMENTS: Picture taken toward:
SOUTHWEST
PHOTO A-6



DATE: 12/8/92	SITE ILD#: 982073611 COUNTY: St. Clair
TIME: 11:40 AM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: K. CORKILL	
COMMENTS: Picture taken toward:	
SOUTHEAST	
PHOTO A-7	

DATE: 12/8/92
TIME: 11:40 AM
PHOTOGRAPH TAKEN BY: K. CORKILL
COMMENTS: Picture taken toward:
SOUTHWEST
PHOTO A-8



DATE: 12/8/92	SITE ILD#: 982073611 COUNTY: St. Clair
TIME: 11:46 AM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: K. CORKILL	
COMMENTS: Picture taken toward:	
SOUTH	
PHOTO A-9	


DATE: 12/8/92
TIME: 11:50 AM
PHOTOGRAPH TAKEN BY: K. CORKILL
COMMENTS: Picture taken toward:
NORTH NORHTWEST
PHOTO A-10



DATE: 12/8/92	SITE IL# #: 982073611 COUNTY: St. Clair
TIME: 11:51 AM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: K. CORKILL	
COMMENTS: Picture taken toward:	
WEST NORTHWEST	
PHOTO A-11	

DATE: 12/8/92
TIME: 11:55 AM
PHOTOGRAPH TAKEN BY: K. CORKILL
COMMENTS: Picture taken toward:
WEST NORTHWEST
PHOTO A-12



DATE: 12/8/92	SITE ILID#: 982073611 COUNTY: St. Clair
TIME: 11:57 AM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: K. CORKILL	
COMMENTS: Picture taken toward:	
SOUTHEAST	
PHOTO A-13	

DATE: 12/8/92
TIME: 1:00 PM
PHOTOGRAPH TAKEN BY: K. CORKILL
COMMENTS: Picture taken toward:
NORTHEAST
PHOTO B-1




DATE: 12/8/92	SITE ILD#: 982073611 COUNTY: St. Clair
TIME: 1:00 PM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: K. CORKILL	
COMMENTS: Picture taken toward:	
NORTHWEST	
PHOTO B-2	



Site: Yvonne Sauget Trust
 Date: 12-8-92 Time: 1:00 PM
 Sample: 108
 Depth: 15'


DATE: 12/8/92
TIME: 3:25 PM
PHOTOGRAPH TAKEN BY: K. NIKA
COMMENTS: Picture taken toward:
SOUTH
PHOTO B-3




Site: Yvonne Sauget Trust
 Date: 12-8-92 Time: 3:25 PM
 Sample: 108
 Depth: 15'

DATE: 12/8/92	SITE ILD#: 982073611 COUNTY: St. Clair
TIME: 3:26 PM	SITE NAME: YVONNE SAUGET (TRUST)

PHOTOGRAPH TAKEN BY: K. NIKA
COMMENTS: Picture taken toward:
NORTHEAST
PHOTO B-4





DATE: 12/8/92
TIME: 3:26 PM
PHOTOGRAPH TAKEN BY: K. NIKA
COMMENTS: Picture taken toward:
NORTHEAST
PHOTO B-5



DATE: 12/8/92	SITE ILID#: 982073611 COUNTY: St. Clair
TIME: 3:54 PM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: G. SPENCER	
COMMENTS: Picture taken toward:	
NORTH NORTHEAST	
PHOTO B-6	


DATE: 12/8/92
TIME: 3:54 PM
PHOTOGRAPH TAKEN BY: G. SPENCER
COMMENTS: Picture taken toward:
NORTH NORTHWEST
PHOTO B-7



DATE: 12/8/92	SITE IL# #: 982073611 COUNTY: St. Clair
TIME: 4:40 PM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: G. SPENCER	
COMMENTS: Picture taken toward:	
SOUTH SOUTHWEST	
PHOTO B-8	

DATE: 12/8/92
TIME: 4:42 PM
PHOTOGRAPH TAKEN BY: G. SPENCER
COMMENTS: Picture taken toward:
NORHTWEST
PHOTO B-9



DATE: 12/9/92	SITE ILID#: 982073611 COUNTY: St. Clair
TIME: 10:05 AM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: K. NIKA	
COMMENTS: Picture taken toward:	
SOUTH	
PHOTO B-10	

DATE: 12/9/92
TIME: 10:05 AM
PHOTOGRAPH TAKEN BY: K. NIKA
COMMENTS: Picture taken toward:
WEST NORTHWEST
PHOTO B-11



DATE: 12/9/92

SITE ILD#: 982073611

COUNTY: St. Clair

TIME: 10:20 AM

SITE NAME: YVONNE SAUGET (TRUST)

PHOTOGRAPH TAKEN
BY: S. MURPHY

COMMENTS: Picture
taken toward:

NORTH

PHOTO B-12



DATE: 12/9/92

TIME: 10:21 AM


PHOTOGRAPH TAKEN
BY: S. MURPHY

COMMENTS: Picture
taken toward:

NORTHWEST


PHOTO C-1



DATE: 12/9/92	SITE IL# #: 982073611 COUNTY: St. Clair
TIME: 10:25 AM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: G. SPENCER	
COMMENTS: Picture taken toward:	
WEST	
PHOTO C-2	


DATE: 12/9/92
TIME: 10:26 AM
PHOTOGRAPH TAKEN BY: G. SPENCER
COMMENTS: Picture taken toward:
NORTHWEST
PHOTO C-3



DATE: 12/9/92	SITE ILD#: 982073611 COUNTY: St. Clair
TIME: 10:40 AM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: G. SPENCER	
COMMENTS: Picture taken toward:	
WEST	
PHOTO C-4	


DATE: 12/9/92
TIME: 10:40 AM
PHOTOGRAPH TAKEN BY: G. SPENCER
COMMENTS: Picture taken toward: NORTHWEST
PHOTO C-5



DATE: 12/9/92	SITE IL# #: 982073611 COUNTY: St. Clair
TIME: 11:10 AM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: G. SPENCER	
COMMENTS: Picture taken toward:	
SOUTHWEST	
PHOTO C-6	

DATE: 12/9/92
TIME: 11:10 AM
PHOTOGRAPH TAKEN BY: G. SPENCER
COMMENTS: Picture taken toward:
NORTHEAST
PHOTO C-7



DATE: 12/9/92	SITE ILD#: 982073611 COUNTY: St. Clair
TIME: 11:40 AM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: G. SPENCER	
COMMENTS: Picture taken toward:	
SOUTHWEST	
PHOTO C-8	

DATE: 12/9/92
TIME: 11:40 AM
PHOTOGRAPH TAKEN BY: G. SPENCER
COMMENTS: Picture taken toward:
SOUTHWEST
PHOTO C-9



DATE: 12/9/92	SITE ILID#: 982073611 COUNTY: St. Clair
TIME: 11:40 AM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: G. SPENCER	
COMMENTS: Picture taken toward:	
NORTHEAST	
PHOTO C-10	


DATE: 12/9/92
TIME: 12:11 PM
PHOTOGRAPH TAKEN BY: G. SPENCER
COMMENTS: Picture taken toward:
SOUTHWEST
PHOTO C-11



DATE: 12/9/92	SITE ILD#: 982073611 COUNTY: St. Clair
TIME: 12:11 PM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: G. SPENCER	
COMMENTS: Picture taken toward:	
EAST	
PHOTO C-12	

DATE:
TIME:
PHOTOGRAPH TAKEN BY:
COMMENTS: Picture taken toward:

NO
PHOTO

DATE: 12/9/92	SITE ILD#: 982073611 COUNTY: St. Clair
TIME: 12:40 PM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: S. MURPHY	
COMMENTS: Picture taken toward:	
NORTH	
PHOTO D-1	

DATE: 12/9/92
TIME: 12:40 PM
PHOTOGRAPH TAKEN BY: S. MURPHY
COMMENTS: Picture taken toward:
SOUTH
PHOTO D-2




DATE: 12/9/92	SITE ILD#: 982073611 COUNTY: St. Clair
TIME: 12:50 PM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: GREG SPENCER	
COMMENTS: Picture taken toward:	
SOUTHWEST	
PHOTO D-3	




DATE: 12/9/92
TIME: 12:50 PM
PHOTOGRAPH TAKEN BY: G. SPENCER
COMMENTS: Picture taken toward:
NORTHEAST
PHOTO D-4



DATE: 12/9/92	SITE ILD#: 982073611 COUNTY: St. Clair
TIME: 12:55 PM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: G. SPENCER	
COMMENTS: Picture taken toward:	
SOUTHWEST	
PHOTO D-5	


DATE: 12/9/92
TIME: 12:55 PM
PHOTOGRAPH TAKEN BY: G. SPENCER
COMMENTS: Picture taken toward:
NORTHEAST
PHOTO D-6



DATE: 12/9/92	SITE ILD#: 982073611 COUNTY: St. Clair
TIME: 1:40 PM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: G. SPENCER	
COMMENTS: Picture taken toward:	
EAST	
PHOTO D-7	

DATE: 12/9/92
TIME: 1:40 PM
PHOTOGRAPH TAKEN BY: G. SPENCER
COMMENTS: Picture taken toward:
SOUTHWEST
PHOTO D-8



DATE: 12/9/92	SITE ILD#: 982073611 COUNTY: St. Clair
TIME: 2:05 PM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: G. SPENCER	
COMMENTS: Picture taken toward:	
SOUTHWEST	
PHOTO D-9	

DATE: 12/9/92
TIME: 2:05 PM
PHOTOGRAPH TAKEN BY: G. SPENCER
COMMENTS: Picture taken toward:
NORTHEAST
PHOTO D-10




DATE: 12/9/92	SITE ILD#: 982073611 COUNTY: St. Clair
TIME: 2:25 PM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: G. SPENCER	
COMMENTS: Picture taken toward:	
SOUTHWEST	
PHOTO D-11	




DATE: 12/9/92
TIME: 2:25 PM
PHOTOGRAPH TAKEN BY: G. SPENCER
COMMENTS: Picture taken toward:
NORTHEAST
PHOTO D-12



DATE: 12/9/92	SITE ILD#: 982073611 COUNTY: St. Clair
TIME: 2:55 PM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: G. SPENCER	
COMMENTS: Picture taken toward:	
SOUTHWEST	
PHOTO D-13	

DATE: 12/9/92
TIME: 2:55 PM
PHOTOGRAPH TAKEN BY: G. SPENCER
COMMENTS: Picture taken toward:
SOUTH
PHOTO E-1



DATE: 12/9/92	SITE ILID#: 982073611 COUNTY: St. Clair
TIME: 2:55 PM	SITE NAME: YVONNE SAUGET (TRUST)
PHOTOGRAPH TAKEN BY: G. SPENCER	
COMMENTS: Picture taken toward:	
NORTH	
PHOTO E-2	

APPENDIX E

WELL LOGS

Plotted on Cahokia Quad.

137

LOG OF WATER WELL

Property owner Midwest Rubber Co. Well No. #4
East St. Louis May

Drilled by _____ Year 1951

Formations passed through	Thick- ness	Depth of Bottom
<u>Clay</u>	<u>7</u>	<u>7</u>
<u>dry yellow sand</u>	<u>21</u>	<u>28</u>
<u>Building sand</u>	<u>17</u>	<u>45</u>
<u>Fine gray sand</u>	<u>9</u>	<u>54</u>
<u>Med. Coarse sand</u>	<u>6</u>	<u>60</u>
<u>Ext. fine very dirty sand & silt</u>	<u>18</u>	<u>78</u>
<u>Coarse sand & boulder</u>	<u>32</u>	<u>110</u>

[Continue on back if necessary]

Finished in _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. 36' 10" ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen _____

Slot _____ Diam. _____ Length _____ Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. _____ Sec. 26

Description of location _____ Twp. 2N

_____ Rge. 10W

Location by known location _____ County St. Clair

Signed _____
ST. CLAIR
Copy for Illinois State Geological Survey
NO ENVELOPE 26-2N-10W
Index:

REQUESTED AND MAIL ORIGINAL TO STATE
HEALTH PROTECTION, 535 WEST
DO NOT REACH GEOLOGICAL/WATER
PROPER LOCATION.

GEOLOGICAL AND WATER SURVEYS WELL RECORD

Completed 4-12-76

10. Property owner Clayton Chemical Co. Well No. _____

Address 101 S. Brentwood Clayton Mo.

Driller Charles Miller License No. 102-50

11. Permit No. 45480 Date 3-22-76

12. Water from Land & gravel 13. County St. Clair

at depth 40 to 78 ft. Sec. 26

14. Screen: Diam. _____ in. Twp. 2N

Length: 10 ft. Slotted ☒ Rge. 10W

Elev. _____

15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)
<u>6 5/8</u>	<u>PVC</u>	<u>0</u>	<u>78</u>

SHOW
LOCATION IN
SECTION PLAT

562'SL, 587'WL
SW (permit)

6. Size Hole below casing: 10 in.

7. Static level 15 ft. below casing top which is _____ ft.

above ground level. Pumping level _____ ft. when pumping at 200+

gpm for _____ hours. Sub. pump set at 60'.

8. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
<u>Clay</u>	<u>40</u>	<u>40</u>
<u>Land & Gravel</u>	<u>38</u>	<u>78</u>

RECEIVED

SEP 20 1993

Environmental Protection Agency
MARION REGIONAL OFFICE

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Robert W. Wells DATE 5-4-76

ST. CLAIR

COUNTY No. 74077

26-2N-10W

1589
 Blot in California Quad.
LOG OF WATER WELL

Property owner Midwest Rubber Reclaiming Co. Well No. 2

Drilled by Thorge (Morgan) Year ?

Formations passed through	Thick- ness	Depth of Bottom
<u>Sandy soil</u>	<u>27</u>	<u>27</u>
<u>Loose silt</u>	<u>8</u>	<u>35</u>
<u>Coarse sand + pea gravel</u>	<u>8</u>	<u>43</u>
<u>Ext. fine sand + silt</u>	<u>21</u>	<u>64</u>
<u>Very coarse sand</u>	<u>6</u>	<u>70</u>
<u>Coarse sand, wood, pegs, etc.</u>	<u>11</u>	<u>81</u>
<u>Very coarse sand</u>	<u>5</u>	<u>86</u>
<u>Very coarse sand + gravel</u>	<u>28</u>	<u>114</u>

[Continue on back if necessary]

Finished in _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. 25' 6" ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen _____

Slot _____ Diam. _____ Length _____ Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. _____ Sec. 26

Description of location _____ Twp. 2N

_____ Rge. 10W

Location by _____ County St. Clair

Signed _____

Copy for Illinois State Geological Survey **NO ENVELOPE** Index: 26-2N-10W

LOG OF WATER WELL

Property owner Midwest Rubber Co. Well No. 3

Drilled by Thorge (Morgan) Year 1951

Formations passed through	Thick- ness	Depth of Bottom
<u>Hard fill</u>	<u>3</u>	<u>3</u>
<u>Fine log sand + silt</u>	<u>34</u>	<u>37</u>
<u>Med. fine sand very dirty</u>	<u>14</u>	<u>51</u>
<u>Med. coarse sand, dirty</u>	<u>11</u>	<u>62</u>
<u>Building sand some fine gravel</u>	<u>9</u>	<u>71</u>
<u>Clean coarse sand</u>	<u>23</u>	<u>94</u>
<u>Coarse sand + boulders</u>	<u>8</u>	<u>102</u>
<u>Med. coarse sand</u>	<u>10</u>	<u>112</u>

[Continue on back if necessary]

Finished in _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. 35' ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen _____

Slot _____ Diam. _____ Length _____ Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. _____ Sec. 26

Description of location _____ Twp. 2N

_____ Rge. 10W

Location by _____ County St. Clair

Signed _____

Copy for Illinois State Geological Survey **NO ENVELOPE** Index: 26-2N-10W

RECEIVED
 SEP 28 1993
 DIVISION OF GEOLOGICAL SURVEY
 ILLINOIS REGIONAL OFFICE

LOG OF WATER WELL

Property owner Monsanto Chem. Co. Well No. 15Drilled by H. L. Watson (Moritt) Year Feb. 1941
Mar. 1941

Formations passed through	Thick- ness	Depth of Bottom
<u>No log</u>	<u>70</u>	
<u>Fine sand</u>	<u>5</u>	<u>75</u>
<u>Fine sand + gravel</u>	<u>5</u>	<u>80</u>
<u>Coarse sand + gravel</u>	<u>5</u>	<u>85</u>
" " "	<u>5</u>	<u>90</u>
<u>Coarse sand</u>	<u>5</u>	<u>95</u>
<u>Coarse sand + gravel</u>	<u>5</u>	<u>100</u>
" " "	<u>5</u>	<u>105</u>
<u>Sand + gravel</u>	<u>1 1/2</u>	<u>106 1/2</u>

[Continue on back if necessary]

Finished in _____ at _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. 34' ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. in _____ in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen JohnsonSlot 40-80-100 Diam. 16" Length 25' Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. _____ Sec. 26Description of location SW, NE Sec. 26 Twp. 2 NT 2 N, R 10 W

Location by Brown water Div. _____ St. _____

Signed _____ County _____

Copy for Illinois State Geological Survey

NO ENVELOPE

Index:

26-2N-10W

LOG OF WATER WELL

Property owner Monsanto Chem. Co. Well No. #16Drilled by Watson (Waly) Year June 1941

Formations passed through	Thick- ness	Depth of Bottom
<u>Fill</u>	<u>10</u>	<u>10</u>
<u>Mud</u>	<u>8</u>	<u>18</u>
<u>Fine yellow sand</u> → ?		
<u>Sand</u>	<u>20'</u>	<u>38</u>
<u>Gravel</u>	<u>38</u>	<u>76</u>
<u>Fine gravel</u>	<u>5</u>	<u>81</u>
<u>Gray gravel</u>	<u>10</u>	<u>91</u>
<u>Gravel</u>	<u>10</u>	<u>101</u>
<u>Gravel</u>	<u>5</u>	<u>106</u>

[Continue on back if necessary]

Finished in _____ at _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. 30 ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. in _____ in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen JohnsonSlot _____ Diam. 16" Length 30' Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. _____ Sec. 26Description of location SW, NE Sec. 26 Twp. 2 NT 2 N, R 10 W

Location by Brown water Div. _____ St. _____

Signed _____ County _____

Copy for Illinois State Geological Survey

NO ENVELOPE

Index:

26-2N-10W

RECEIVED
SEP 28 1993
Environmental Protection Agency
MARCON REGIONAL OFFICE

LOG OF WATER WELL

#17

Property owner Monsanto Chem. Co.Well No. 8Drilled by H.L. Western (Walz)Year July 1941

Formations passed through

Thick-
ness Depth of
Bottom

Fill	10	10
Mud	8	18
Yellow sand	10	28
Gray sand (getting coarser)	35	63
#30 sand	15	78
#40 gravel	5	83
#50 "	5	88
#60 "	17	105 TD

[Continue on back if necessary]

Finished in _____ to _____ ft.

Cased with _____ inch from 0 to _____ ft.

and _____ inch from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. 30 ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen JohnsonSlot 40 Diam. 16 Length 30 Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. _____ Sec. 26Description of location SW, NE Sec. 26,T 2 N, R 10 WLocation by Brown Water Div. St. ClairSigned St. Clair County _____Copy for Illinois State Geological Survey NO ENVELOPE Index: 26-2N-10W

LOG OF WATER WELL

Property owner Monsanto Chem. Co.
(80' S + E of main entrance gate)Well No. 19K.W. # 2Drilled by Wayne Western (Z. Salter)Year Aug. 1948

Formations passed through

Thick-
ness Depth of
Bottom

Cinder + clay fill	2	2
Brown sand	14	16
Brown + blue clay	2	18
Brown silt, sand	27	45
Med. gray sand	5	50
Med. fine clammy gray sand	5	55
Med. coarse sand + gravel, which rotten wood	6	61
Coarse sand + gravel	5	66
Black med sand, some gravel	7	73
Coarse sand + gravel	2	75
Coarse brown sand	5	80
Med. brownish gray sand + boulders	4	84
Coarse gray sand	10	90
" " " + gravel	18	108

[Continue on back if necessary]

Finished in _____ to _____ ft.

Cased with _____ inch from 0 to _____ ft.

and _____ inch from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. _____ ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen ShuttleSlot _____ Diam. _____ Length 2.5 Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. _____ Sec. 26Description of location NE NE Sec. 26,T 2 N, R 10 W

Signed _____ County _____

Copy for Illinois State Geological Survey NO ENVELOPE Index: 26-2N-10W

Plotted on photo LOG OF WATER WELL

Property owner Monasanto Chemical Co. Well No. 20
East of bldg. B1 in plant 15'E. from R.R. spur.
 Drilled by Lagne-Weston (Milliken) Year 7-13-49
 W.C. # 3

Formations passed through	Thick- ness	Depth of Bottom
Clay	1	1
Cinders	1	2
Clay	2	5
Sandy clay	26	31
Blk. fine sand	30	61
Med. sand, gray	13	74
Med. to coarse sand	5	79
Rock + coarse sand	2	81
Coarse sand	3	84
Coarse sand + gravel + small rocks	19	103

[Continue on back if necessary]

Finished in _____ at _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. _____ ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. _____ in. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen Shutter

Slot _____ Diam. _____ Length 25 Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. _____ Sec. 26

Description of location NE 1/4 Sec. 26 Twp 2 N

T 2 N, R 10 W

Rge. 10 W

Signed _____ County S.F. Clair

CLAIR NO ENVELOPE Index: 26-2N-10W

Plotted on photo 1F39 71000.0.15. Log # 437 LOG OF WATER WELL

Property owner Midwest Rubber Pickin' Co. Well No. 1
 Drilled by Thayer (Morgan) Year ?
 Formations passed through

Formations passed through	Thick- ness	Depth of Bottom
Sandy loam	10	10
Dry sand	14	24
Coarse sand	14	38
Coarse sand, some gravel	4	42
Fine sand	24	66
Ext. fine sand	8	74
Coarse sand + boulders	8	82
Very coarse sand + gravel	24	106

[Continue on back if necessary]

Finished in _____ at _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. 28' 2" ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. _____ in. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen _____

Slot _____ Diam. _____ Length _____ Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. _____ Sec. 26

Description of location _____ Twp 2 N

Rge. 10 W

Signed _____ County Clair Co.

CLAIR NO ENVELOPE Index: 26-2N-10W

LOG OF WATER WELL

Property owner Monsanto Chem. Co. Well No. 2Drilled by Layne-Western (F. Sallee) Year Feb. 1948

Formations passed through

Formations passed through	Thick- ness	Depth of Bottom
Cinder fill	8	8
Hard green clay	4	12
Clay blocks sand turning brown	3	15
Black & brown sand w/ clay	5	20
Brown sand	10	30
" " turning gray	5	35
Fine to med. gray sand	5	40
Med. gray sand	10	50
Med. to coarse gray sand	15	65
Med. gray sand	5	70
Sand & boulders, blue clay showing	5	75
Fine to med. sand, silt, few boulders	5	80
Med. sand, some gravel	5	85
Med. to coarse sand & gravel	15	100
Coarse sand, gravel & boulders	8	108
2 1/2 inch at 108		

[Continue on back if necessary]

Finished in _____ at _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. _____ ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen _____

Slot _____ Diam. _____ Length _____ Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. 410 _____ Sec. 26Description of location NE 1/4 Sec. 26 Twp. 2NT 2N, R 10W Rge. 10WSigned _____ County St. Clair

St. CLAIR No ENVELOPE 26-2N-10W

Copy for Illinois State Geological Survey Index:

LOG OF WATER WELL

Property owner Monsanto Chem. Co. Well No. 4Drilled by Layne-Western (F. Sallee) Year Feb. 1948

Formations passed through

Formations passed through	Thick- ness	Depth of Bottom
Cinder	1	1
Brown to yellow clay	7	10
Brown sandy clay	20	30
Brown sand clay showing	10	40
Brown, pebbled sand	3	43
Med. sand, some gravel, clay showing	7	50
Fine pebbled sand & gravel	10	60
Med. sand some coarse gravel - w/d at 68-70	5	70
Med. sand, some gravel	5	75
Fine to coarse sand & gravel, boulders	10	85
Medium fine sand, some gravel	5	90
Medium to coarse sand & gravel boulders	19' 8"	109' 8"
2 1/2 inch at 109' 8"		

[Continue on back if necessary]

Finished in _____ at _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. _____ ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen _____

Slot _____ Diam. _____ Length _____ Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. _____ Sec. 26Description of location NE 1/4 Sec. 26 Twp. 2NT 2N, R 10W Rge. 10WSigned _____ County St. Clair

St. CLAIR No ENVELOPE 26-2N-10W

Copy for Illinois State Geological Survey Index:



(575-6M-7-23)

OWN Cahokia

TOWNSHIP

MAP No. 4W

COMPANY Union Electric Light & Power

LOW

ARM 100 ft. S. of N. property line

AUTHORITY 258 ft. E. of Eastern Inner

LEVATION Harbor line. HOLE No. 1

COLLECTOR

DATE DRILLED

2					Proj.
N					23

COUNTY NO.	STRATA	THICKNESS		DEPTH	
		FEET	IN.	FEET	IN.
1730	Mud, black and fine sand	30		30	
	Sand, fine	4		34	
	Sand, coarse	2		36	
	5% 1/8 in. gravel				
	25% 1/4 in. gravel	2		38	
	30% 2 1/2 in. gravel	2		40	
	Sand, coarse	8		48	
	30% 1/8 to 1 in. gravel				
	Sand, coarse	4		52	
	10% 1/4 in. gravel				



(575-5M-7-23)

rown Cahokia

TOWNSHIP

MAP No. 4W

COMPANY Union Electric Light and Power

107

FARM 300 ft. S. of N. Property Line

AUTHORITY 250 ft. E. of Eastern Inner

ELEVATION Harbor line

HOLE No.

COLLECTOR

DATE DRILLED

2	-			-		
N	*					

2
N

Proj.
23

No.	COUNTY NO. 173 STRATA	THICKNESS		DEPTH	
		FEET	IN.	FEET	IN.
	Sand, fine	10		10	
	Sand, very fine	8		18	
	Mud, black	6		24	
	Mud, black and fine sand mixed	11		33	
	Sand, fine. 10% 1/4 in. gravel	5		38	
	Sand, coarse. 15% 1/2 in. gravel	5		43	
	Sand, coarse 20% 1/2 in. gravel	5		48	
	Sand, fine	5		53	
	Sand, coarse. Pieces of soapstone	5		58	
	Sand, coarse 5% 1/4 in. gravel	8		66	
	Sand, coarse 10% 1/2 in. gravel	6		72	
	Sand, coarse 20% 4 in. gravel	4		76	
	Sand, coarse, 20% 3/4 in. gravel	15		91	
	Sand, coarse	10		101	
	Minus 73.66 Rock				

OWNER **E. St. Louis-Monsanto P. O.**COMPANY **F. Thorpe-Engineer**ARM **Evans-Wallower Zinc Co. 2**AUTHORITY **F. Thorpe**

ELEVATION

COLLECTOR

CONFIDENTIAL

Map No. **4W**
R. **10W**Sec. **24 ?**DATE DRILLED **March 1929**

COUNTY NO. 1740	STRATA		Thickness		Depth	
	Feet	In.	Feet	In.	Feet	In.
Subsoil & clay	16		16			
Sand, extremely fine	11		27			
Sand, very fine, loamy	8		35			
Sand, very fine	11		46			
Sand, fine	6		52			
Sand, very fine	3		55			
Sand, fine, gritty	7		62			
Boulders up to 4" with some sand	5		67			
Regular building sand	14		81			
Sand, medium coarse	2		83			
Sand, very coarse	19		102			
<p>"During the month of March, 1929, I installed a porous concrete well 30" I.D. and 40" O.D. at the plant of the Evans-Wallower Zinc Co. at Monsanto P.O., East St. Louis, Ill. and the above is the log of all the strata we went through in Well #2.</p> <p>"The static level of water varies with the river level." (Letter of F. Thorpe rec'd. 4-3-29)</p>						
NO ENVELOPE						

County **St. Clair**


Index No.

04W24

T.-DRILL RECORD

24-2N-10W

17893 4M 5 29

TOWN **East St. Louis** TOWNSHIP
COMPANY **Thorpe Concrete Well Co.**FARM **Certain-tyed Products No. 3**AUTHORITY **Written log**ELEVATION **416 topo.**COLLECTOR **Ireland** DATE DRILLED **4-34**

CONFIDENTIAL

18th and BroadwayMap No. **4W**
R. **10W**

T. 2				Sec. 24
N				

No.	COUNTY NO. 1739	STRATA		Thickness		Depth	
		Feet	In.	Feet	In.	Feet	In.
		Cinder fill	6			6	
		Gumbo	4			10	
		Soil, sandy	7			17	
		Sand, fine	10			27	
		Sand, extremely fine	13			40	
		Sand, fine, loamy	13			53	
		Sand, fine, gritty	7			60	
		Clay, blue	4			64	
		Sand, quick	26			90	
		Sand, fine	2			92	
		Sand, gritty	9			101	
		Gravel, fine	6			107	
		Sand, coarse	2			109	
		Boulders 2" to 10"	7			116	
		Baits drilled 3 wells	1-21			120	
			7-17			120	
			11-17			119	
NO ENVELOPE							

County **ST. CLAIR**

Index No.

04W 24

T.-DRILL RECORD

24-2N-10W

47327-10M-4.35

4 Illinois Geological Survey, Urbana.

ILLINOIS GEOLOGICAL SURVEY, URBANA

1

	Thickness	Top	Bottom
Gravel, sandy	1	0	1
Clay with sand lenses	2	1	3
Silty sand	3	3	6
Fat clay	1½	6	7½
Sandy silt	6	7½	13½
Very fine sand	5	13½	18½
Fine sand	6	18½	24½
Clay	1½	24½	26
Silty sand	4	26	30
No record		30	83
Fine to medium sand	10	83	93
Fine sand	6	93	99
Medium to coarse, gravely sand	5	99	104
Fine to coarse sand	5	104	109
Medium sand	5	109	114
Medium to fine sand	5	114	119
Medium sand	5	119	124
Fine to coarse sand	3	124	127
Refusal			

**1.62 miles N of 38° 35', 3600' W of 90° 10'

*Corps of Engineers

NO ENVELOPE

South end of
warehouse
LOG OF WATER WELL

Plot in California Quad.

Property owner A + P Food Stores Well No. _____Mississippi Ave.
Drilled by H. L. Watson (Bud Graves) Year June 1946

Formations passed through	Thick- ness	Depth of Bottom
<u>Gravel</u>	<u>30</u>	<u>30</u>
<u>Quick sand + gravel</u>	<u>5</u>	<u>35</u>
<u>Medium sand + gravel</u>	<u>10</u>	<u>45</u>
<u>Fine sand</u>	<u>10</u>	<u>55</u>
<u>Medium sand</u>	<u>5</u>	<u>60</u>
<u>Fine sand</u>	<u>5</u>	<u>65</u>
<u>Mud</u>	<u>3</u>	<u>68</u>
<u>Medium sand + gravel</u>	<u>7</u>	<u>75</u>
<u>Good sand</u>	<u>5</u>	<u>80 TO</u>
<u>Fine bottom</u>		

[Continue on back if necessary]

Finished in _____ at _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

COUNTY NO. 1925

Size hole below casing _____ inch. Static level from surf. 25' ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. _____ in. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen _____

Slot _____ Diam. 6" Length 10' Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. _____

Description of location SE, SW Sec 23T 2N R 10WLocation of Warehouse _____

Signed _____ County _____

Copy for Illinois State Geological Survey

Index:

23-2N-10W

MPANY

IRM

ITE DRILLED

ITHORITY

EVATION

CATION


UNTY

*Waterways Experiment Station W-77

1952-53 COUNTY NO. 1923

**118' L.S. of L of Levee, E side L.

ST. CLAIR & S. Dist. L Sta. 1127+50




23-2N-10W

ILLINOIS GEOLOGICAL SURVEY, URBANA

PERMIT # NF 08825	Thickness	Top	Bottom
A 4" test hole was first drilled to a depth of 111', then filled in with sand and later re-drilled with a bigger bit. Both records follow.			
TEST HOLE			
Clay		0	11
Silty sand brown		12	21
Fine sand brown		22	30
Fine sand gray		31	41
Medium sand gray		42	51
Coarse sand gray with pea gravel		52	56
Coarse sand gray with pea gravel		57	61
Coarse sand gray with pea gravel		62	86
Very coarse sand gray with 3/8" gravel		87	91
Very coarse sand gray with 1/2" gravel		92	96
Very coarse sand gray with 1/2" gravel		97	101
Very coarse sand gray with 1/2" gravel		102	104
Very coarse sand gray with 1/2" gravel		105	111
			TD
WELL RECORD			
Clay		0	18
Sand coarse gray			20
Sand coarse gray with gravel			25
Sand fine			30
Sand coarse gray with gravel			35
Sand coarse gray with gravel			40
Sand coarse gray with 1" gravel			45
Sand coarse gray with 1" gravel		55	60
Sand coarse gray with 3/4" gravel		65	70

COMPANY Luhr Brothers, Inc.
 FARM Cerro Copper & Brass Co. NO. 1
 DATE DRILLED July 10, 1970 COUNTY NO. 3208
 AUTHORITY Company
 ELEVATION
 LOCATION 1000' N line, 400' W line of NW
 COUNTY ST. CLAIR



26-2N-10W

ILLINOIS GEOLOGICAL SURVEY, URBANA

	Thickness	Top	Bottom
Sand very coarse gray			75
Sand very coarse gray with cobbles to 5"		80	110 1/2 TD
Well Casing:			
Material - Steel coated with bituminous			
Diameter: 20" outside diameter			
Length - 78.73'			
Wall Thickness - .075			
Final Casing Elevation Above Grade: 1'			
Size of Drilled Hole:			
40" to 20"			
38" to bottom			
Well Screen:			
Material - Stainless steel #304			
Diameter - 20" nominal			
Length - 31.82			
Slot Size - .100			
Type Make - UOP Johnson			
Depth of Screen set at 110.55'			
Gravel Filter:			
Used 23 tons Muscatine, 1/16" - 3/16"			
No. 3			
Wall Thickness - 8 1/2"			
Feet Above Screen - 26'			
Static Level: 23.86'			
S.S. # 57106.			

COUNTY Luhr Bros., Inc. Cerro Copper & Brass Co. #1
 ST. CLAIR 26-2N-10W

LOG OF WATER WELL

sent well

Well No. 2

Year Feb. 1948

(Continue on back if necessary)

COUNTY No. 1941

and _____ inch _____ from _____ to _____ ft.

Tested capacity_____gal. per min. Temperature_____°F.

Water lowered to _____ ft. _____ in. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen _____

Slot _____ Diam. _____ Length _____ Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. 412

--	--	--	--

 Sec. 26

Description of location SW NE Sec. 46

	X	

 Twp. 2 N

Town K 100

Signed _____

Signed _____ County _____
 St. Clair *NO* ENVELOPE
 Copy for Illinois State Geological Survey Index: 26-2N-10W

26-2N-10W

- Soil
- Sand
- Fine gravel
- Gravel & sand
- Gravel & boulders
- Gravel
- Coarse gravel & boulders

Thickness	Top	Bottom
-----------	-----	--------

Tested 1400 gallons per minute.

Water stands 12'6" from surface of ground.

Water stands 26'6" when pumping 1400
gallons per minute.

Size of well 24". .

20 cubic yards of gravel.

Material used in well:

50' of 38" Pit,
106'8" of 24" which includes 58' of 24"
Shutter Screen & 48'4" of 24" Pit.

Kind of seal used Steel Plug.

*50'N and 50'E of crossing of Alton &
Southern R.R. & Falling Springs Rd.

COMPANY	Layne & Bowler Company	
FARM	Monsanto Chemical Works	NO. 1
DATE DRILLED	May 8, 1920	COUNTY NO. 1741
AUTHORITY	Layne & Bowler Co.	
ELEVATION	410' \pm	
LOCATION	*	
COUNTY	ST. CLAIR	Project

Projected 26-2N-10W

LOG OF WATER WELL

Property owner Levin-Matthes Well No. _____

Drilled by H.L. Watson (Mell) Year June 1948

Formations passed through	Thick- ness	Depth of Bottom
<u>Shredded</u>	<u>3</u>	<u>3</u>
<u>Fine sand</u>	<u>12</u>	<u>15</u>
" "	<u>20</u>	<u>35</u>
" " + gravel	<u>10</u>	<u>45</u>
<u>Med sand + gravel</u>	<u>2</u>	<u>47</u>
<u>Log</u>	<u>1</u>	<u>48</u>
<u>Med. Sand + gravel</u>	<u>4</u>	<u>52</u>
" " " " + rock	<u>10</u>	<u>62</u>
" " " "	<u>8</u>	<u>70</u>
" " " "	<u>5</u>	<u>75</u>
" " " " + rock	<u>5</u>	<u>80</u>
<u>Coarse sand</u>	<u>5</u>	<u>85</u>
<u>Coarse sand + rock</u>	<u>5</u>	<u>90</u>
<u>Coarse sand</u>	<u>5</u>	<u>95</u>
<u>Boulder</u>	<u>1</u>	<u>96</u>
<u>Coarse sand + rock</u>	<u>5</u>	<u>101</u>

[Continue on back if necessary]

Finished in _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. _____ ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. in. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen _____

Slot _____ Diam. _____ Length _____ Bottom set at _____ ft.
[Show location in Section Plat]Township name _____ Elev. _____ Sec. 26Description of location NE, SW Sec. 26 Twp. 2NT2N, R10W Rge. 10WLocation by Dr. H. L. Watson
Signed _____ County _____SE CLAIR No ENVELOPE 26-2N-10W
Copy for Illinois State Geological Survey Index:

LOG OF WATER WELL

Property owner Levin-Matthes-Monaco, M. Well No. _____

Drilled by H.L. Watson (Graves) Year Feb. 1947

Formations passed through	Thick- ness	Depth of Bottom
<u>Fine sand</u>	<u>70</u>	<u>70</u>
<u>Fine sand + gravel</u>	<u>8</u>	<u>78</u>
<u>Good formation</u>	<u>26</u>	<u>104 TD</u>

COUNTY No. 1936

[Continue on back if necessary]

Finished in _____ at _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. _____ ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. in. in _____ hrs. _____ min.


Length of test _____ hrs. _____ min. Screen _____

Slot 30 Diam. 12" Length 26'5" Bottom set at _____ ft.
[Show location in Section Plat]Township name _____ Elev. _____ Sec. 26Description of location NE, SW Sec. 26 Twp. 2NT2N, R10W Rge. 10WLocation by Dr. H. L. Watson
Signed _____ County _____SE CLAIR No ENVELOPE 26-2N-10W
Copy for Illinois State Geological Survey Index:

Page 1 ILLINOIS GEOLOGICAL SURVEY, URBANA

INDUSTRIAL Permit #NFL849	Thickness	Top	Bottom
Yellow brown clay		0	10
Fine sand brown		10	25
Medium coarse sand brown		25	30
Coarse sand brown with pea gravel		30	35
Coarse sand brown		35	40
Medium coarse sand brown		40	55
Medium fine sand brown		55	60
Fine sand brown		60	70
Very coarse sand gray with 1½" gravel		70	80
Very coarse sand gray with ¾" gravel		80	85
Very coarse sand gray with ¾" gravel		85	90
Very coarse sand gray with ½" gravel		90	95
Very coarse sand gray with 3/8" gravel		95	100
Very coarse sand gray with 1" gravel		100	105
Very coarse sand gray with ¾" gravel		105	107
Very coarse sand gray with ¾" gravel		107	113
Very coarse sand gray with ½" gravel		113	116
			TD
Size of hole 38"			
Casing: 88" - 18" outside diameter steel			
Casing elevation 2' above grade			
Static water level 36.9' top of casing			
24 tons gravel pack 11" wall 45' above screen			
Screen: Johnson Stainless Steel 18" nominal diameter. Length 30' set at 116'			
Slot size: .060'			
Two well 300' apart were drilled under Permit #NFL849 S.S. # 55984			
NO ENVELOPE			
* North Reservoir			


COMPANY Luhr Brothers, Inc.
 FARM Midwest Rubber Reclaiming Co. 10
 DATE DRILLED September 3, 1968 COUNTY NO. 2856
 AUTHORITY Luhr Bros. Inc.
 ELEVATION
 LOCATION Lot 209 Third Subdivision of Cahokia
 COUNTY ST. CLAIR Commonfields 237-2N-10 W



Page 1 ILLINOIS GEOLOGICAL SURVEY, URBANA

INDUSTRIAL Permit #NFL849	Thickness	Top	Bottom
Brown Clay		0	5
Brown silty sand		5	20
Fine sand brown		20	25
Fine sand gray		25	30
Coarse sand gray with pea gravel		30	35
Medium coarse sand gray		35	40
Coarse sand gray		40	45
Medium fine sand gray		45	55
Very coarse sand gray with pea gravel		55	60
Medium coarse sand gray		60	65
Very coarse sand gray with ¾" gravel		65	70
Medium coarse sand gray with pea gravel		70	75
Very coarse sand gray with ¾" gravel		75	110
Very coarse sand gray with 1" gravel		110	115.5
			TD
Size of hole 38"			
Casing: 88.70' - 18" outside diameter steel			
Casing elevation 3.2' above grade			
Static water level 37'			
26.5 tons gravel pack 11" wall 55' above screen.			
Screen: Johnson Stainless Steel 16" nominal diameter. Length 30' set at 115.5'			
Slot size: .060			
Two wells 300' apart were drilled under Permit #NFL849 NO ENVELOPE			
* Southwest Reservoir S.S. #55983			

COMPANY Luhr Brothers, Incorporated.
 FARM Midwest Rubber Reclaiming Co. 11
 DATE DRILLED September 6, 1968 COUNTY NO. 2857
 AUTHORITY Luhr Bros. Inc.
 ELEVATION
 LOCATION Lot 209 Third Subdivision of Cahokia
 COUNTY ST. CLAIR Commonfields 237-2N-10 W



ILLINOIS GEOLOGICAL SURVEY, URBANA

Page 1


ILLINOIS GEOLOGICAL SURVEY, URBANA

Strata	Thickness	Top	Bottom
Boring No. 1 at Pier No. 4 Elevation 400'± MSL			
Water	8-10		8-10
Black Muck	13-0		21-10
Black muck mixed with sand	6-0		27-10
River sand	1-0		28-10
At this depth 20' hole was abandoned acc't casing breaking.			
NOTE: At 8', 12', 13', and 19' depths old wooden hulls were found (Pine Timber.)			
Boring did not reach rock.			
Reference drawings 4108 p2 -1 sheets 1 and 2, and 4108 p2 -3 sheet 2 in map files.			
Cahokia quadrangle			

COMPANY St. Louis City, Mo.
 FARM MacArthur (Municipal) Bridge
 DATE DRILLED 1909
 AUTHORITY Boller & Hodge, Consulting Engineers
 ELEVATION 400'± MSL
 LOCATION SW.,NW.,NW.
 COUNTY St. Clair

Pier No. 4
 NO. 1

COUNTY NO. 1866




23-2N-10W

Strata	Thickness	Top	Bottom
Boring No. 2 at Pier No. 4 Elevation 400'± MSL			
Water	7-7		7-7
Black muck mixed with sand	17-0		24-7
Struck old sunken oak timbers			
Black muck mixed with sand	1-0		25-7
Struck old sunken oak timbers			
Alluvial sand mixed with fine gravel	10-0		35-7
Fine sand and gravel	41-2		76-9
Elevation 323'± MSL Limestone rock (Boulder)			
Boring No. 4 at Pier No. 4 Elevation 406'± MSL			
Water	17-1		17-1
Black muck mixed with sand	10-2		27-3
Recent alluvial sands	4-10		32-1
Alluvial sands and fine gravel	70-4		102-5
Struck boulder (broken up and drill went down)			
Alluvial sands with drift of gravel	16-8		119-1
Elevation 287'± MSL solid bedrock			
Reference drawings 4108 p2 -1 sheets 1 and 2, and 4108 p2 -3 sheet 2 in map files.			
Cahokia quadrangle			

COMPANY St. Louis City, Mo.
 FARM MacArthur (Municipal) Bridge
 DATE DRILLED 1909
 AUTHORITY Boller & Hodge, Consulting Engineers
 ELEVATION
 LOCATION SW.,NW.,NW.
 COUNTY St. Clair

Pier No. 4
 NO. 2 & 4

COUNTY NO.



23-2N-10W

ILLINOIS GEOLOGICAL SURVEY, URBANA


Page 2

ILLINOIS GEOLOGICAL SURVEY, URBANA

	Thickness	Top	Bottom
Bridge Boring #H-1 Station 52+68 Centerline			
Topsoil			1
Very soft gray-mottled sandy clay			7
Medium brown sandy clay			12
Medium gray fatty clay			22
Medium very fine gray sand			29
Dense fine gray sand			32
Medium fine gray sand			37
Dense fine gray sand			42
Medium fine gray sand			44.5
Very dense fine gray sand			49.5
Dense fine gray sand			52
Medium fine gray sand with small well graded gravel			62
Very dense gray sand			67
Dense gray sand			69.5
Very dense fine gray sand			72
Dense very fine gray silty sand			77
Dense very fine gray silty sand with rounded to sub-aug poorly graded gravel			79
Very dense fine gray silty sand			84.5
Dense fine gray silty sand			87
Medium coarse gray sand with occasional small well graded gravel			99.5
Loose coarse gray sand with occasional small well graded gravel			102
Medium coarse gray sand with occasional small well graded gravel			117

Strata	Thickness	Top	Bottom
Medium gray sand with rounded to sub- angular poorly graded gravel			127
Rock (Limestone)			130
			T.D.
<p>Typed by Engineering Geology</p> <p>Copy of Highway Division log filed in Groundwater Section</p> <p>NO ENVELOPE</p> <p>*FAI 55 & 70 Interchange Complex at East St. Louis</p>			

MPANY Illinois Division of Highways
IM FAI 55 & 70 Interchange* NO. H-1
TE DRILLED April 1963 COUNTY NO. 23824
THORITY Log by Division of Highways
VATION 404.7' G.L.
ATION NE NE NW
JNTY ST. CLAIR



Proj. 23-2N-10W

COUNTY

Ill. Div. of Highways #H-1 FAI 55 & 70 Interchange*
ST. CLAIR Proj. 23-2N-10W

ILLINOIS GEOLOGICAL SURVEY, URBANA

ILLINOIS GEOLOGICAL SURVEY, URBANA

Page 1

Strata	Thickness	Top	Bottom
Boring No. 3 at Pier No. 4 Elevation 406'+ MSL			
Water	11-1		11-1
Black muck mixed with sand	9-6		20-7
Struck old sunken hull (oak timber) about 4" thick.			
Recent alluvial sands	4-2		24-9
Struck old sunken hull (oak timber)			
Alluvial sands	74-0		98-9
Struck bolder of limestone rock	1-2		99-11
Drilled through and broken up.			
Alluvial sands with drifts of gravel.	21-1		121-0
Elevation 285'+ MSL. Solid limestone bedrock. Drilled into rock about 8 inches.			
Reference drawings 4108 p2-1 sheets 1 and 2. and 4108 p2-3 sheet 2 in map files.			
Cahokia quadrangle			


Strata	Thickness	Top	Bottom
Boring No. 5 at Pier No. 4 Elevation 406'+ MSL			
Water	9-10		9-10
Black muck mixed with sand	10-0		19-10
Recent alluvial sands	8-0		27-10
Coarse alluvial sands	16-0		43-10
Coarse sand and gravel	21-0		64-10
Alluvial sands with drifts of gravel	54-2		119-0
Elevation 287'+ MSL. Solid limestone bedrock.			
Boring No. 6 at Pier No. 4 Elevation 406'+ MSL.			
Water	12-7		12-7
Black muck mixed with sand	14-7		27-2
Struck old barge or boat (oak timber)			
Recent alluvial sand	13-0		40-2
Coarse sand and gravel	1-5		41-7
Coarse sand with drifts of gravel	79-0		120-7
Elevation 285'+ MSL. Solid limestone bedrock			
Reference drawings 4108 p2-1 sheets 1 and 2. and 4108 p2-3 sheet 2 in map files.			
Cahokia quadrangle			

COMPANY St. Louis City, Mo.
 ARM MacArthur (Municipal) Bridge
 DATE DRILLED 1909
 AUTHORITY Boller & Hodge, Consulting Engineers
 ELEVATION 406'+ MSL
 LOCATION SW., NW., NW.
 COUNTY St. Clair

Pier No. 4

NO. 3

COUNTY NO. 1569




23-2N-10W

COMPANY St. Louis City, Mo.
 FARM MacArthur (Municipal) Bridge
 DATE DRILLED 1909
 AUTHORITY Boller & Hodge, Consulting Engrs.
 ELEVATION
 LOCATION SW., NW., NW.
 COUNTY St. Clair

Pier No. 4

NO. 5 & 6

COUNTY NO.



23-2N-10W

ILLINOIS GEOLOGICAL SURVEY, URBANA

Page 2

ILLINOIS GEOLOGICAL SURVEY, URBANA

MIT # NF 08825

* test hole was first drilled to a depth of 111', then filled in with sand and later re-drilled with a bigger bit. Both records follow.


T HOLE

	Thickness	Top	Bottom
		0	11
ty sand brown		12	21
e sand brown		22	30
e sand gray		31	41
lum sand gray		42	51
rse sand gray with pea gravel		52	56
rse sand gray with pea gravel		57	61
rse sand gray with pea gravel		62	86
r coarse sand gray with 3/8" gravel		87	91
r coarse sand gray with 1/2" gravel		92	96
r coarse sand gray with 1/2" gravel		97	101
r coarse sand gray with 1/2" gravel		102	104
r coarse sand gray with 1/2" gravel		105	111
			TD

RECORD

		0	18
coarse gray			20
coarse gray with gravel			25
fine			30
coarse gray with gravel			35
coarse gray with gravel			40
coarse gray with 1" gravel			45
coarse gray with 1" gravel		55	60
coarse gray with 3/4" gravel		65	70

Y Luhr Brothers, Inc.
Cerro Copper & Brass Co. No. 1
DILLED July 10, 1970 COUNTY NO. 3208
ITY Company



26-2N-10W

N 1000' N line, 400' W line of NW
ST. CL 1

	Thickness	Top	Bottom
Sand very coarse gray			75
Sand very coarse gray with cobbles to 5"		80	110 1/2 TD
Well Casing:			
Material - Steel coated with bituminous			
Diameter: 20" outside diameter			
Length - 78.73'			
Wall Thickness - .075			
Final Casing Elevation Above Grade: 1'			
Size of Drilled Hole:			
40" to 20'			
38" to bottom			
Well Screen:			
Material - Stainless steel #304			
Diameter - 20" nominal			
Length - 31.82			
Slot Size - .100			
Type Make - UOP Johnson			
Depth of Screen set at 110.55'			
Gravel Filter:			
Used 23 tons Muscatine, 1/16" - 3/16"			
No. 3			
Wall Thickness - 8 1/2"			
Feet Above Screen - 26'			
Static Level: 23.86'			
S.S. # 57106.			

Y Luhr Bros., Inc.
ST. CLAIR

Cerro Copper & Brass Co. '1
26-2N-10W

LOG OF WATER WELL

LOG OF WATER WELL

Start well _____

Property owner Monsanto Chem. Co. Well No. #1

Drilled by Laguer-Wentzen (F. Sallie) Year Feb. 1948

Formations passed through	Thickness	Depth of Bottom
Soil Fill	1	1
Cinder fill	4	5
Cinders, blue, green clay	5	10
Cinders + fine black sand	5	15
Fine black sand + clay	5	20
" " , streak red gray sand	5	25
Fine black muddy sand, wind & get sample	20	45
sand coarse gray sand	10	55
Coarse gray sand	5	60
Fine, sandy, gray-brown sand boulder from 176 ft	14	74
Sand + gravel, packed w/ much fine sand	3	77
Packed sand, gravel + boulders	3	80
Packed sand, gravel + boulders	13	93
Sand + boulders	9	102
(Formation increased in verticality)		TD

Cased with _____ inch _____ from 0 to _____ ft

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. _____ ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowred to _____ ft. _____ in. in _____ hrs. _____ min.

Length of test _____ hr _____ min. Screen _____

Slot _____ Diam. _____ Length _____ Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. 410

--	--	--	--

 Sec 26.

Description of location SW NE Sec. 26

		X	

Twp. 1 N

Town Road

--	--	--	--	--

 Road

Signed _____ County S. F. Collins

CLARK No ENVELOPE 26-21 OW
for Illinois State Geological Survey Index:

Projected 26-2N-10W


ILLINOIS GEOLOGICAL SURVEY, URBANA

Strata	Thickness	Top	Bottom
edish sandy and blue silt		0	15
rey sand little silt		15	20
rey sand		20	25
lue and grey sand		25	30
ine grey sand		30	35
ine grey sand and blue silt		35	40
ine blue and grey sand		40	45
o recovery wash sample. Fine blue and grey sand		40	50
o recovery wash sample. fine blue and grey sand.		50	55
ine blue sand, No recovery		55	60
lue sand and wood no recovery		60	65
rey and blue sand. No recovery		65	70
ine blue sand. No recovery		70	75
ine blue sand. No recovery		75	80
edium blue sand. No recovery		80	85
ixed grey and blue sand no recovery		85	90
ixed grey and blue sand. No recovery		90	95
ixed blue and grey sand. Could not drive sample Barrell. Felt like gravel		95	100
lue and grey sand. No spoon sample taken.		100	105
lue and redish sand. no spoon sample taken. Drove casing to 110' 4". Set well screen at 108' 11". Could not get any deeper as sand was running under casing.		105	110
otal Depth			110' 4" TD

Location plat filed.
 I.S. # 29700

NY Wabash Drilling Co.
 Monsanto Chemical Co.
 DRILLED November 1956
 CITY Wabash Drilling Co.
 ION 412' 5" refusal (MSL)
 ON 680' W of 90° 10' W longitude, 4310' N
 Y 35° north latitude
 ST. CL A

NO. SP-2
 COUNTY NO. 1987



Projected 26- 2N-10W

Plot in photo
 LOG OF WATER WELL

Property owner Monsanto Chem. Co. (Plant 'B') Well No. 12

Drilled by <u>H. C. Watson</u>	Year _____	
Formations passed through	Thick-ness	Depth of Bottom
<u>No log</u>	<u>70</u>	
<u>7 in sand</u>	<u>5</u>	<u>75</u>
<u>Coarse sand & gravel</u>	<u>5</u>	<u>80</u>
<u>Coarse sand & gravel</u>	<u>5</u>	<u>85</u>
<u>" " " "</u>	<u>5</u>	<u>90</u>
<u>" " " "</u>	<u>5</u>	<u>95</u>
<u>" " " "</u>	<u>5</u>	<u>100</u>
<u>Sand & gravel</u>	<u>5</u>	<u>105</u>
<u>" " " "</u>	<u>5</u>	<u>110</u>
<u>7 in boulders</u>	<u>2</u>	<u>112</u>

[Continue on back if necessary]

Finished in _____ at _____ to _____ ft.
 Cased with _____ inch _____ from 0 to _____ ft.
 and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. 39' 6" ft.

Tested capacity 1250 gal. per min. Temperature _____ °F.

Water lowered to _____ ft. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen Johnson

Slot 60-80-100 Diam. 16 Length 27 1/2 Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. _____ Sec. 26

Description of location SE, NE Sec. 26, Twp. 2N

T 2 N R 10 W Rge. 10 W

Location by Groundwater

Signed _____ County _____

Copy for Illinois State Geological Survey Index: 26-2N 10W

LOG OF WATER WELL

Property owner Midwest Rubber, Calumet Co. Well No. 2

Drilled by Thayer (Morgan) Year 1951

Formations passed through	Thick-ness	Depth of Bottom
Hard soil	27	27
Loose silt	8	35
Coarse sand + pea gravel	8	43
2 1/2" fine sand + silt	21	64
Very coarse sand	6	70
Coarse sand, wood, etc.	11	81
Very coarse sand	5	86
Very coarse sand + gravel	28	114

[Continue on back if necessary]

Finished in _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. 25' 6" ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen _____

Slot _____ Diam. _____ Length _____ Bottom set at _____ ft.

(Show location in Section Plat)

Township name _____ Elev. _____ Sec. 26

Description of location _____ Twp. 2N

Range _____ Rge. 10W

Location by _____ County St. Clair

NO ENVELOPE 26-2N-10W

Illinois State Geological Survey Index

LOG OF WATER WELL

Property owner Midwest Rubber, Calumet Co. Well No. 3

Drilled by Thayer (Morgan) Year 1951

Formations passed through	Thick-ness	Depth of Bottom
Hard fill	3	3
Fine log sand + silt	34	37
Med. fine sand very dirty	14	51
Med. coarse sand, dirty	11	62
Building sand some fine gravel	9	71
Clean coarse sand	23	94
Coarse sand + boulders	8	102
Med. coarse sand	10	112

[Continue on back if necessary]

Finished in _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. 35' ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen _____

Slot _____ Diam. _____ Length _____ Bottom set at _____ ft.

(Show location in Section Plat)

Township name _____ Elev. _____ Sec. 26

Description of location _____ Twp. 2N

Range _____ Rge. 10W

Location by _____ County St. Clair

NO ENVELOPE 26-2N-10W

Illinois State Geological Survey Index

LOG OF WATER WELL

Property owner American Zinc Co. - Monrovia
United Engineering & Const. Co., Inc., P.O. Box 11537 Well No. 6

Drilled by H. L. Watson (Sandusville) Year Nov. 1940

Formations passed through	Thick- ness	Depth of Bottom
<u>Clashes + Mud</u>	<u>15</u>	<u>15</u>
<u>Fine sand</u>	<u>60</u>	<u>75</u>
<u>good water bearing formation</u>	<u>30</u>	<u>105</u>
<u>Quartz sand to 300 ft.</u>	<u>2</u>	<u>107</u>

(Continue on back if necessary)

Finished in _____ at _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. 34 ft.

Tested capacity 1500 gal. per min. Temperature _____ °F.

Water lowered to _____ ft. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen Cool

Slot 1/20 Diam. 16 Length 30' Bottom set at _____ ft.

(Show location in Section Plat)

Township name _____ Elev. _____ Sec. 23

Description of location SE, SE Sec 23 Twp 2N

T 2N, R 10W Rge. 10W

Location by Monrovia Signed _____ County St. Clair

CLAIR Copy for Illinois State Geological Survey 23-2N-10W

LOG OF WATER WELL

Property owner United Engineering Well No. 7
American Zinc Co. - Monrovia, Ill.

Drilled by Watson (Moretti & Caridge) Year Jan. 1942

Formations passed through	Thick- ness	Depth of Bottom
<u>Shit</u>	<u>5</u>	
<u>Fine sand</u>	<u>45</u>	<u>50</u>
<u>Coarse sand</u>	<u>25</u>	<u>75</u>
<u>gravel</u>	<u>30</u>	<u>105</u>

(Continue on back if necessary)

Finished in _____ at _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. 33' 6" ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen _____

Slot 40+50 Diam. 16" Length 30' Bottom set at _____ ft.

(Show location in Section Plat)

Township name _____ Elev. 404 Sec. 23
TOPO

Description of location SE, SE Sec 23, T 2N, R 10W Twp 2N

800' N 90° 10' 7000' N 30° 35' Rge. 10W

Location by Monrovia Signed _____ County St. Clair

CLAIR Copy for Illinois State Geological Survey 23-2N-10W



(575-6M-7-23)

TOWNSHIP

MAP No. 4W

ANY Union Electric Light and Power

300 ft. S. of North property Line

ORITY 50 ft. E. of Eastern Inner

ATION Harbor Line

HOLE No. 6

2
NProj.
23

ECTOR

DATE DRILLED

COUNTY NO. 1A	THICKNESS		DEPTH	
	FEET	IN.	FEET	IN.
Water	16		16	
Sand, fine	12		28	
Sand, coarse	10		38	
Sand, very coarse	10		48	
1/2 in. gravel				
Sand, coarse	27		75	
Sand, coarse	4		79	
5% 1/2 in. gravel				
Sand, coarse	4		83	
25% 1/2 in. gravel				
Sand, coarse	3		86	
40% 3 in. gravel				
Sand with gravel	12	8	104	8

Minus 76.06 rock



(575-6M-7-23)

TOWNSHIP

MAP No. 4W

TOWN Onhokin

COMPANY Union Electric Light & Power

FARM 100 ft. S. of N. property Line on

AUTHORITY Eastern Inner Harbor Line.

ELEVATION

HOLE No. 7

2
NProj.
23

COLLECTOR

DATE DRILLED

No.	COUNTY NO. 1A	THICKNESS		DEPTH	
		FEET	IN.	FEET	IN.
		35		35	
		5		40	
		10		50	
		15		65	
		12		77	

Water
Sand, fine
Sand, coarse
5% 2 in. gravel
Sand, coarse
15% 1/8 in. gravel
Sand, coarse
20% 1 1/2 and 10%
1/8 in. gravel

St. Clair

ntly
WILL RECORD

Index No.

Projected 23-2N-10W

St. Clair

County

DRILL RECORD

Index No.

Projected 23-2N-10W

LOG OF WATER WELL

Property owner American Pine Co. Well No. 5

Drilled by H.L. Watson Year Feb. 1946

Formations passed through	Thick- ness	Depth of Bottom
<u>Gravel</u>	<u>20</u>	<u>20'</u>
<u>Quick sand</u>	<u>30</u>	<u>50'</u>
<u>Sand</u>	<u>16</u>	<u>66'</u>
<u>Med. Sand</u>	<u>10</u>	<u>76</u>
<u>No log</u>	<u>26</u>	<u>102</u>
TD = 102		

[Continue on back if necessary]

Finished in _____ at _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. _____ ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen Cole

Slot _____ Diam. 1/4 Length 30' Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. _____ Sec. 23

Description of location SE, SE Sec. 23 Twp. 2N

T2N, R10W Rge. 10W

Location by Brown & White

County St. Clair

Copy for Illinois State Geological Survey No. ENVELOPE Index: 23-2N-10W

LOG OF WATER WELL

Property owner American Pine Co. Well No. 9

Drilled by H.L. Watson (G.W. Finch) Year Nov. 1950

Formations passed through	Thick- ness	Depth of Bottom
<u>Mud</u>	<u>35</u>	<u>35</u>
<u>Sand</u>	<u>45</u>	<u>80</u>
<u>Medium sand</u>	<u>20</u>	<u>100</u>
<u>sand & coarse gravel</u>	<u>4</u>	<u>104</u>
TD = 104'		

[Continue on back if necessary]

Finished in _____ at _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. _____ ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen _____

Slot _____ Diam. 1/4" Length 60' Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. _____ Sec. 23

Description of location SW, SE Sec. 23 Twp. 2N

T2N, R10W Rge. 10W

Location by Brown & White

County St. Clair

Copy for Illinois State Geological Survey No. ENVELOPE Index: 23-2N-10W

APPENDIX F

IEPA BORING LOGS



DATE: December 14, 1992

TO: Division File

FROM: Sherry Otto *SMD*

SUBJECT: Soil sampling at:
LPC #1630000000 -- St. Clair County
Yvonne Sauget Trust Site K

Three borings were drilled on December 8 and 9 at a playground located in Sauget. All work was performed in accordance with the Unit's Standard Operating Procedures. A detailed description of the materials encountered and the OVA readings are on the attached Field Boring Logs. The attached map shows the location of these borings. Samples for chemical analyses were collected by Sheila Murphy, Ken Corkill, Greg Spencer and Kim Nika.

SMD:jsm

cc: Sheila Murphy
Unit File
Collinsville Regional File

STATE OF ILLINOIS
ENVIRONMENTAL PROTECTION AGENCY


IL 532-0357
ADM 39
054-002

Subject _____

Data _____

Reviewed by _____ Date _____

LPC #1630000000 St. Clair County
Yvonne Sauget Trust Site K



Site not drawn to scale

⊗ B-1 Bore hole locations

--- 9.6 --- Distance from bore hole to site structures



Illinois Environmental Protection Agency

Field Boring Log

Page 1 of 2Site File No 163000000 County St. ClairBoring No 1 Monitor Well No NASite File Name Yvonne Sauget Trust / Site KSurface Elev _____ Completion Depth 20Fed ID No IL0 982073611Auger Depth 20 Rotary Depth NA

Quadrangle _____ Sec. _____ T _____ R _____

Date Start 12-8-92 Finish 12-8-92Boring Location 39.5' SW of the NE site chain link fence
and 53.7' SE of the NW site chain link fenceDrilling Equipment CME 75 3/4 HSA

SAMPLES						Personnel
Sample No	Sample Type	Sample Recovery	Penetration	N Valves (blows)	OVA (in ft)	G. S. O'to
						D. P. Masch
						H. B. Mathis Jr.
						H. B. Walkenbach

Elev.	DESCRIPTION	Depth in feet	Sample No	Sample Type	Sample Recovery	Penetration	N Valves (blows)	OVA (in ft)	REMARKS
	Interval 0-5 ft. Silt, yellowish brown 10 YR 5/4, moist	0 1 2 3 4 5							OVA shoe 2 Head 1
	Interval 5-10 ft. Poor recovery .3mm x .3mm piece of limestone rock in shoe	6 7 8 9 10							OVA shoe 0 Head 20
	Interval 10-12.5 ft. Fill Mat. Silt, black 10 YR 2/1 with Sand 15% med. grain, gravel 10% 2-5 mm in size, piece of slag 20 x 20 mm. Wet	11 12 13							OVA Shoe 100 Head 2100
	Interval 12.5-15 Fill Mat. Black Top .25 Sand very coarse grain. Bottom .65 Sand med.-coarse grain Wet.	14 15							OVA Shoe 800 Head 10

Site File No 11630000000 County St. Clair Boring No 1 Monitor Well No _____Site File Name Yvonne Sauget Trust / Site K Surface Elev _____ Completion Depth _____

Fed ID No _____ Auger Depth _____ Rotary Depth _____

Quadrangle _____ Sec. _____ T _____ R _____ Date Start _____ Finish _____

Boring Location _____

Drilling Equipment _____

Elev.	DESCRIPTION	Depth in feet	SAMPLES						Personnel
			Sample No	Sample Type	Sample Recovery	Penetrometer	N Values (blows)	OVA in HNU readings	G. O. H. H.
	Interval 15-17.5 Sand Dark gray 10YR 4/1 med. grain, wet.	15 16 17							
	Interval 17.5-20 Hit hard Fill Mat. locked up augers and broke off sampler, no sample retrieved.	18 19 20							
	Boring Completed at 20								

OVA
Head 200
Stee 400

Site File No 163000000 County St. Clair Boring No 2 Monitor Well No NASite File Name Yvonne Sauget Trust / Site K Surface Elev _____ Completion Depth 15Fed ID No ILD 982073611 Auger Depth 15 Rotary Depth NAQuadrangle _____ Sec. _____ T _____ R _____ Date Start 12-8-92 Finish 12-8-92Boring Location 9.6' NE of NE chain link fence and 71'NW of light pole on SE corner of siteDrilling Equipment CME 75 3 1/4 HSA

Elev.	DESCRIPTION	Depth in feet	SAMPLES					Personnel
			Sample No	Sample Type	Sample Recovery	Penetrometer	N Values (blows)	OVA in (ft) (readings)
								G. S. Otto D. P. Masch H. B. Mathis Jr. H. B. Walkenbach
								REMARKS
	Interval 0-2.5 ft. Silt Dark brown 10YR 4/3 with gravel 20% 5-10 mm in size	0						OVA while drilling 40 OVA Head 0 Shoe 11
	Interval 2.5-5 ft. Silt very dark brown 10YR 2/2, sand 30% very coarse grain, gravel 20% 5-10 mm in size.	1						
		2						
		3						Shoe 3 Head 0
		4						
		5						
		6						
	No Recovery	7						
		8						Shoe 0 Head 7
	No Recovery Fill Mat. Rock and wood in sample Shoe	9						
		10						
	Interval 10-12.5 clay, dark gray 10YR 4/1.	11						Shoe 200 Head >1000
		12						
		13						OVA while drilling 0
	No Recovery	14						
		15						

Boring Completed at 15 ft



Illinois Environmental Protection Agency

Field Boring Log

Page 1 of 2Site File No 1630000000 County St. ClairBoring No 3 Monitor Well No NASite File Name Yvonne Sauget Trust / Site KSurface Elev Completion Depth 20Fed ID No ILD 982073611Auger Depth 20 Rotary Depth NAQuadrangle Sec. T R Date Start 12-9-92 Finish 12-9-92Boring Location 64.4 ft. East of SW fence 111.6 ft NWof the most eastern side of park pavilionDrilling Equipment CME 75 3 1/4 HSA

SAMPLES

Personnel

Sample No	Sample Type	Sample Recovery	Penetrometer	N Valves (blows)	OVA in MNU readings

G - S. O + to
D - P. Mason
H - B. Mathis Jr.
H - B. Walkenbach

Elev.

DESCRIPTION

Depth
in feet

REMARKS

Interval 0-2.5 ft. Dark yellowish brown Sand
10YR 4/6, very fine grain,
top 0.15 roots and grass

1

CS 2

OVA Shoe 0
Head 0

2

Interval 2.5-5 Top 1 ft. Dark yellowish
brown Sand 10YR 4/6,
very fine grain.
Bottom 1.7 ft. Sand and
Gravel Fill 30% gravel
consisting of white rock

3

CS 2.7

OVA Shoe >1000
Head 0*

4

5

Interval 5-7.5 Black Sand and Gravel
Fill

6

CS 6

OVA Shoe 0 *
Head 0

7

Interval 7.5-10 Black Sand, Gravel
and asphalt Fill

8

CS 2

OVA Shoe 0 *
Head 20

9

10

* Note: Flame Out

Interval 10-12.5 Black Sand, Gravel,
asphalt and wood, wet.

11

CS 9

OVA Shoe 6
Head 200

12

Interval 12.5-15. Black Sand, Gravel,
asphalt, and wood Fill
very wet

13

CS 7

OVA Shoe 7
Head >1000

14

15

X 106

Site File No 1630000000 County St. Clair Boring No 3 Monitor Well No _____Site File Name Yvonne Sauget Trust / Site K Surface Elev _____ Completion Depth _____

Fed ID No _____ Auger Depth _____ Rotary Depth _____

Quadrangle _____ Sec. _____ T _____ R _____ Date Start _____ Finish _____

Boring Location _____

Drilling Equipment _____

Elev.	DESCRIPTION	Depth in feet	SAMPLES						Personnel
			Sample No	Sample Type	Sample Recovery	Penetration	N Values (blows)	OVA (in HNU) readings	G. O. H. H.
	Interval 15-17.5 Black Fill Mat. Same as above	15 16 17							
	Interval 17.5-20 Sand, very dark gray, 10YR 3/1, med. to coarse grain, 5% Gravel 2-5mm in size, Natural in situ Sand.	18 19 20							
	Boring Complete at 20								

OVA Shoe > 1000
Head > 1000While drilling 200
Shoe 0
Head 20

APPENDIX G

CENTRACTS POPULATION CALCULATIONS

FROST ASSOCIATES

P.O. Box 495, Essex, Connecticut 06426
(203) 767-1254 Fax (203) 767-7069

Tom Crause
Manager Site Assessment Program
Illinois EPA
2200 Churchill Road
Springfield, Illinois 62794

RECEIVED

DEC 21 1992

EPA/DLPC

Dear Mr. Crause,

Thank you for the opportunities to demonstrate CENTRACTS.

Enclosed are two reports of the Sauget site prepared using the Census Bureau's 1990 Block Group data and boundaries. The one labeled 1 reflects the Illinois data. The second, labeled 2, shows the 4, 3 and 2 mile rings that overlapped into St Louis.

Please note that the Census Bureau's water sources data is not yet available for the mid-western states. The Census Bureau recalled the STF-3A files, containing the water data, in August and has just recently begun to re-issue the files on a state by state basis. Illinois' STF-3A files on CD ROM are expected soon.

This data is available, however, through the Illinois state data center. If they will download these four fields onto a floppy disk, we will incorporate this data into any future reports. Any CENTRACTS reports prepared for your department before the STF-3A water source data is received will be re-run at no charge.

Below is a description of the source data and the methodology used to prepare each report. This description is also included with each report. Also enclosed is a copy of a letter from Sharon Hayes at EPA, Superfund Support Section, Region 1, allowing the states in Region 1 to use CENTRACTS under the MSCA.

The CENTRACTS report below identifies the population, households, and private water wells of each Block Group that lies within, or partially within, the 4, 3, 2, 1, .5, and .25, mile "rings" of the latitude and longitude coordinates above. CENTRACTS may have up to ten radii of any length. 1000 block groups, and 15000 block group sides.

CENTRACTS uses the 1990 Block Group population and Block Group house count data found in the Census Bureau's 1990 STF-1A files. The sources of water supply data are from the Bureau's 1990 STF-3A files. The boundary line coordinates of the Block Groups were extracted from the Census Bureau's 1990 TIGER/Line Files.

CENTRACTS reports are created with programs written by Frost Associates, P.O. Box 495, Essex, Conn. The code was written using Microsoft's Quick-Basic Ver. 4.5.

Latitude and Longitude coordinates identifying a site are entered in degrees and decimal degrees. One or more county files holding Block Group boundary lines are selected for use by CENTRACTS by determining whether the site coordinates fall within the minimum and maximum Lat/Lon coordinates of each county in the state.

Each Block Group line segment has Lat\Lon coordinates representing the "From" and "To" ends of that line. All coordinates from the selected county files are read and converted from degrees, decimal degrees to X\Y miles from the site location. Each line segment is then examined whether it lies within or partially within the maximum ring from the site.

The unique Block Group ID numbers of each line segment that lie within the maximum ring are retained. All Block Group boundary lines matching the Block Group numbers are then extracted from the respective county files to obtain all sides of the included Block Groups. Boundary records are then sorted in adjacent side order to determine the shape and area of each Block Group polygon.

A method to solve for the area of a polygon is to take one-half the sum of the products obtained by multiplying each X-coordinate by the difference between the adjacent Y-coordinates. For a polygon with coordinates at adjacent angles A, B, C, D, and E. The formula can be expressed:

$$\text{Area} = 1/2\{X_a(Y_e - Y_b) + X_b(Y_a - Y_c) + X_c(Y_b - Y_d) + X_d(Y_c - Y_e) + X_e(Y_d - Y_a)\}$$

For each ring, the selected Block Groups will be inside, outside, or intersected by the ring. When a polygon is intersected, the partial Block Group area within that ring is calculated using the method described below.

When a ring intersects a Block Group, the intersect points are solved and plotted at the points where the ring enters and exits the shape. The chord line, a line within the circle connecting the intersect points is determined. This chord line is used to calculate the segment area, the half moon shape between the chord line and the ring, and the sub-polygon created by the chord line and the Block Group boundaries that lie outside the ring.

The segment area is subtracted from the sub-polygon area to determine the area of the sub-polygon outside the ring. The area outside the ring is then subtracted from the area of the entire polygon to arrive at the inside area. This inside area is then divided by the tract's total area to determine the percentage of area within the ring. This process is repeated for each block group that is intersected by one of the rings. The total area, partial area, and percentage of partial area of those block groups within, or partially within a ring, are held in memory for the report.

On occasion, the algorithm described above is unable to determine the area of the partial area. Within the report program is a "Paint" routine which allows an enclosed shape to be highlighted. Another routine calculates the percentage of highlighted screen pixels to the pixels within the polygon. A manual entry is allowed. Both the "paint" method and manual entry method over ride the calculated method.

CENTRACTS lists, starting on page 3, all Block Groups in State, County, Census Tract, and Block Group ID order that lie within, or partially within, the maximum ring. Each Block Group is identified by a City or Town name and by the Block Group's State, County, Tract and Block Group ID number. Following is the Block Group's 1990 population and house count extracted from the Census Bureau's 1990 STF-1A files.

The next four columns display water source data from the 1990 STF-3A files. The first column is "Units with Public system or private company source of water", followed by "Units with individual well, Drilled, source of water"; "Units with individual well, Dug, source of water" and "Units with Other source of water".

For each ring, CENTRACTS then shows the Block Groups that are within that ring, the Block Group's total area in square miles, the partial area of the Block Group within that ring, and the partial percentage within the ring. The areas of the included Block Group and the partial areas are then totaled.

The last section tallies the demographic data within each ring. The percentage of area for each Block Group is multiplied times the census data for that Block Group and totaled for all Block Group's within the ring. Ring totals are then determined by subtracting the three mile data from the four mile, the two mile from the three mile, one from the two, etc.. Population on private wells is calculated using the formula: $((\text{Drilled} + \text{Dug Wells}) / \text{Households}) * \text{Population}$

We propose that the Illinois Environmental Protection Agency retain Frost Associates to prepare CENTRACTS reports as part of their site assessment and inspection work for the state of Illinois and their cooperative work with the U.S. Environmental Protection Agency.

The price is \$100.00 per report for CENTRACTS at the Tract level and \$125.00 per report if CENTRACTS is ordered at the Block Group level. Each Tract may have up to ten Block groups. In rural environments, the Block Group resolution is recommended.

Each report will resemble the enclosed reports. Each page will have the Name and Address as supplied by your department, the CERCLIS number and any other identification supplied and the Date prepared.

We propose that the Illinois Environmental Protection Agency FAX their request to (203) 767-7069. The FAX will be your department's Purchase Order to have Frost Associates prepare these reports.

Thank you again for your interest. If you have any questions, please call at (203) 767-1254.

Sincerely,



Robert H. Frost



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION I

J.F. KENNEDY FEDERAL BUILDING, BOSTON, MASSACHUSETTS 02203-2211

October 13, 1992

Mr. Harish Panchal (617) 554-1118 [Boston Office]
Bureau of Waste Site Cleanup
Department of Environmental Protection
One Winter Street, Fifth Floor
Boston, MA 02108

Dear Mr. Panchal:

The Region has been made aware of a reasonably priced product/service available which would speed up the collection of private well and population information and meet CERCLA reporting and HRS requirements. Robert Frost, of Frost Associates, is capable of generating private well and population data by rings given a site's latitude and longitude. The cost for this product is approximately \$100/site and would be allowable under the MSCA.

I have enclosed a brief description of the process used to generate this information as well as the results of a test site located in Wilmington, Massachusetts. If you choose to use this approach for your MSCA reports, please include the description of the process and the results as an appendix to the report for documentation purposes.

Please do not hesitate to contact Nancy Smith or Robert Frost for further information regarding this process.

Sincerely,

Sharon M. Hayes
Superfund Support Section
Waste Management Division

cc: Carl DeLoi, Chief
Nancy Smith
Robert Frost

- Regional
Offices
- Ida Babroudi MA DEP Northern Region (617) 935-2140
 - Mary Ellen McBrine MA DEP Southern Region (508) 946-2862
 - Don Hanson MA DEP Central Region (508) 792-7653
 - Lisa Jones MA DEP Western Region (413) 784-1100





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION I

J.F. KENNEDY FEDERAL BUILDING, BOSTON, MASSACHUSETTS 02203-2211

October 13, 1992

Robert Frost
Frost Associates
P.O. Box 495
Essex, CT 06426

Dear Mr. Frost:

The following EPA Contractors have been authorized to utilize the private well and population reports that you can prepare for Site Assessment work, if they so choose. As I understand, the approximate cost per site will be \$100.

Gary Glennon
NUS Corporation
187 Ballardvale Street
Suite A-100
Wilmington, MA 01887
(508) 658-7899

Diane Stallings
TRC Environmental Corporation
Boot Mills South
Foot of John Street
Lowell, MA 01852
(508) 970-5600

Jocelyn Boesch
Roy F. Weston
Landmark One
One Van De Graaff Drive
Burlington, MA 01803
(617) 229-2050

Tara Taft
CDM Federal Programs Corporation
98 North Washington Street
Suite 200
Boston, MA 02114
(617) 742-2659

Please do not hesitate to call me at (617) 573-5709 if you have any questions.

Sincerely,

Sharon M. Hayes
EPA ARCS Work Assignment Manager

cc: Carl DeLoi
SAG
Gary Glennon, NUS
Diane Stallings, TRC
Jocelyn Boesch, Weston
Tara Taft, CDM



FROST ASSOCIATES

P.O. Box 495, Essex, Connecticut 06426
(203) 767-1254 Fax (203) 767-7069

Dec 16, 1992

To: Tom Crause
Illinois Environmental Protection Agency
7200 Churchill Road
Springfield, Illinois 62794

Fr: Bob Frost
Frost Associates
P.O. Box 495
Essex, CT 06426

Tel: (203) 767-1254
Fax: (203) 767-7069

Sub: CENTRACTS Demonstration
Sauget IL,
Illinois Portion

CIRCLIS:

Site Longitude: 90.167503
Site Latitude : 38.589439

The CENTRACTS report below identifies the population, households, and private water wells of each Block Group that lies within, or partially within, the 4, 3, 2, 1, .5, and .25, mile "rings" of the latitude and longitude coordinates above. CENTRACTS may have up to ten radii of any length. 1000 block groups, and 15000 block group sides.

CENTRACTS uses the 1990 Block Group population and Block Group house count data found in the Census Bureau's 1990 STF-1A files. The sources of water supply data are from the Bureau's 1990 STF-3A files. The boundary line coordinates of the Block Groups were extracted from the Census Bureau's 1990 TIGER/Line Files.

CENTRACTS reports are created with programs written by Frost Associates, P.O. Box 495, Essex, Conn. The code was written using Microsoft's Quick-Basic Ver. 4.5.

Latitude and Longitude coordinates identifying a site are entered in degrees and decimal degrees. One or more county files holding Block Group boundary lines are selected for use by CENTRACTS by determining whether the site coordinates fall within the minimum and maximum Lat/Lon coordinates of each county in the state.

Each Block Group line segment has Lat/Lon coordinates representing the "From" and "To" ends of that line. All coordinates from the selected county files are read and converted from degrees, decimal degrees to X/Y miles from the site location. Each line segment is then examined whether it lies within or partially within the maximum ring from the site.

The unique Block Group ID numbers of each line segment that lie within the maximum ring are retained. All Block Group boundary lines matching the Block Group numbers are then extracted from the respective county files to obtain all sides of the included Block Groups. Boundary records are then sorted in adjacent side order to determine the shape and area of each Block Group polygon.

A method to solve for the area of a polygon is to take one-half the sum of the products obtained by multiplying each X-coordinate by the difference between the adjacent Y-coordinates. For a polygon with coordinates at adjacent angles A, B, C, D, and E. The formula can be expressed:

$$\text{Area} = 1/2\{X_a(Y_e - Y_b) + X_b(Y_a - Y_c) + X_c(Y_b - Y_d) + X_d(Y_c - Y_e) + X_e(Y_d - Y_a)\}$$

For each ring, the selected Block Groups will be inside, outside, or intersected by the ring. When a polygon is intersected, the partial Block Group area within that ring is calculated using the method described below.

When a ring intersects a Block Group, the intersect points are solved and plotted at the points where the ring enters and exits the shape. The chord line, a line within the circle connecting the intersect points is determined. This chord line is used to calculate the segment area, the half moon shape between the chord line and the ring, and the sub-polygon created by the chord line and the Block Group boundaries that lie outside the ring.

The segment area is subtracted from the sub-polygon area to determine the area of the sub-polygon outside the ring. The area outside the ring is then subtracted from the area of the entire polygon to arrive at the inside area. This inside area is then divided by the tract's total area to determine the percentage of area within the ring. This process is repeated for each block group that is intersected by one of the rings. The total area, partial area, and percentage of partial area of those block groups within, or partially within a ring, are held in memory for the report.

On occasion, the algorithm described above is unable to determine the area of the partial area. Within the report program is a "Paint" routine which allows an enclosed shape to be highlighted. Another routine calculates the percentage of highlighted screen pixels to the pixels within the polygon. A manual entry is allowed. Both the "paint" method and manual entry method override the calculated method.

CENTRACTS lists, starting on page 4, all Block Groups in State, County, Census Tract, and Block Group ID order that lie within, or partially within, the maximum ring. Each Block Group is identified by a City or Town name and by the Block Group's State, County, Tract and Block Group ID number. Following is the Block Group's 1990 population and house count extracted from the Census Bureau's 1990 STF-1A files.

The next four columns display water source data from the 1990 STF-3A files. The first column is "Units with Public system or private company source of water", followed by "Units with individual well, Drilled, source of water"; "Units with individual well, Dug, source of water" and "Units with Other source of water".

For each ring, CENTRACTS then shows the Block Groups that are within that ring, the Block Group's total area in square miles, the partial area of the Block Group within that ring, and the partial percentage within the ring. The areas of the included Block Group and the partial areas are then totaled.

The last section tallies the demographic data within each ring. The percentage of area for each Block Group is multiplied times the census data for that Block Group and totaled for all Block Group's within the ring. Ring totals are then determined by subtracting the three mile data from the four mile, the two mile from the three mile, one from the two, etc... Population on private wells is calculated using the formula: $((\text{Drilled} + \text{Dug Wells}) / \text{Households}) * \text{Population}$

Dec 16, 1992

No.	City	Block Group ID	Blk Grp People	House Holds	Public Water	Drilled Wells	Dug Wells	Other
1	East St. Louis	17163 5004	2 611	179	00	00	00	00
2	East St. Louis	17163 5004	3 439	148	00	00	00	00
3	East St. Louis	17163 5004	4 872	444	00	00	00	00
4	East St. Louis	17163 5004	5 250	77	00	00	00	00
5	East St. Louis	17163 5004	6 928	507	00	00	00	00
6	East St. Louis	17163 5005	5 794	488	00	00	00	00
7	East St. Louis	17163 5006	1 206	79	00	00	00	00
8	East St. Louis	17163 5006	2 580	219	00	00	00	00
9	East St. Louis	17163 5006	3 438	171	00	00	00	00
10	East St. Louis	17163 5006	4 268	112	00	00	00	00
11	East St. Louis	17163 5006	5 266	98	00	00	00	00
12	East St. Louis	17163 5006	6 200	80	00	00	00	00
13	East St. Louis	17163 5008	1 0	0	00	00	00	00
14	East St. Louis	17163 5008	3 0	0	00	00	00	00
15	East St. Louis	17163 5009	1 679	285	00	00	00	00
16	East St. Louis	17163 5009	2 991	459	00	00	00	00
17	East St. Louis	17163 5009	3 1147	464	00	00	00	00
18	East St. Louis	17163 5009	4 1056	463	00	00	00	00
19	East St. Louis	17163 5009	5 550	248	00	00	00	00
20	East St. Louis	17163 5009	6 996	445	00	00	00	00
21	East St. Louis	17163 5009	7 1322	486	00	00	00	00
22	East St. Louis	17163 5010	1 482	224	00	00	00	00
23	East St. Louis	17163 5010	2 208	97	00	00	00	00
24	East St. Louis	17163 5010	3 492	183	00	00	00	00
25	East St. Louis	17163 5010	4 583	308	00	00	00	00
26	East St. Louis	17163 5010	5 796	370	00	00	00	00
27	East St. Louis	17163 5010	6 740	303	00	00	00	00
28	East St. Louis	17163 5010	7 383	159	00	00	00	00
29	East St. Louis	17163 5011	1 664	308	00	00	00	00
30	East St. Louis	17163 5011	2 448	192	00	00	00	00
31	East St. Louis	17163 5011	3 701	225	00	00	00	00
32	East St. Louis	17163 5011	4 686	255	00	00	00	00
33	East St. Louis	17163 5011	5 317	161	00	00	00	00
34	East St. Louis	17163 5012	1 523	162	00	00	00	00
35	East St. Louis	17163 5012	2 738	240	00	00	00	00
36	East St. Louis	17163 5012	3 259	101	00	00	00	00
37	East St. Louis	17163 5012	4 1264	466	00	00	00	00
38	East St. Louis	17163 5012	5 360	126	00	00	00	00
39	East St. Louis	17163 5012	6 1060	370	00	00	00	00
40	East St. Louis	17163 5012	7 715	253	00	00	00	00
41	East St. Louis	17163 5012	8 779	273	00	00	00	00
42	East St. Louis	17163 5013	5 1086	409	00	00	00	00
43	East St. Louis	17163 5013	6 405	138	00	00	00	00
44	East St. Louis	17163 5013	7 648	251	00	00	00	00
45	East St. Louis	17163 5013	8 714	257	00	00	00	00
46	Centreville	17163 5023	1 11	6	00	00	00	00
47	Centreville	17163 5023	2 186	82	00	00	00	00
48	Centreville	17163 5025	1 346	144	00	00	00	00
49	Centreville	17163 5025	2 529	163	00	00	00	00
50	Centreville	17163 5025	3 1496	477	00	00	00	00
51	Centreville	17163 5025	4 554	190	00	00	00	00
52	Centreville	17163 5027	1 397	159	00	00	00	00

Dec 16, 1992

53	Centreville	17163 5027	2	813	314	00	00	00	00
54	Centreville	17163 5027	3	361	114	00	00	00	00
55	Centreville	17163 5027	4	74	35	00	00	00	00
56	Centreville	17163 5028	1	1147	432	00	00	00	00
57	Centreville	17163 5028	2	1003	339	00	00	00	00
58	Centreville	17163 5028	3	286	131	00	00	00	00
59	Centreville	17163 5029	1	846	302	00	00	00	00
60	Centreville	17163 5029	3	484	196	00	00	00	00
61	Centreville	17163 5029	4	163	78	00	00	00	00
62	East St. Louis	17163 5041	2	725	256	00	00	00	00
63	East St. Louis	17163 5041	3	53	27	00	00	00	00
64	East St. Louis	17163 5041	4	7	8	00	00	00	00
65	East St. Louis	17163 5041	5	0	0	00	00	00	00
66	East St. Louis	17163 5041	6	4	1	00	00	00	00
67	East St. Louis	17163 5044	1	50	31	00	00	00	00
68	East St. Louis	17163 5044	2	1050	351	00	00	00	00
69	East St. Louis	17163 5044	3	9	10	00	00	00	00
70	East St. Louis	17163 5044	4	3	5	00	00	00	00
71	East St. Louis	17163 5044	5	0	0	00	00	00	00
72	East St. Louis	17163 5044	6	114	42	00	00	00	00
Totals:				38355	15176	0	0	0	0

Dec 16, 1992

For Radius of 4 Mi., Circle Area = 50.265482

No.	City	Block Group ID	Total Area	Partial Area	% Within Radius
1	East St. Louis	17163 50042	0.083424	0.017326	20.77
2	East St. Louis	17163 50043	0.109497	0.099573	90.94
3	East St. Louis	17163 50044	0.308985	0.289649	93.74
4	East St. Louis	17163 50045	0.309614	0.309614	100.00
5	East St. Louis	17163 50046	0.218200	0.065038	29.81
6	East St. Louis	17163 50055	0.128000	0.021989	17.18
7	East St. Louis	17163 50061	0.052645	0.052645	100.00
8	East St. Louis	17163 50062	0.065500	0.065500	100.00
9	East St. Louis	17163 50063	0.075351	0.075351	100.00
10	East St. Louis	17163 50064	0.070534	0.070534	100.00
11	East St. Louis	17163 50065	0.070325	0.070325	100.00
12	East St. Louis	17163 50066	0.076836	0.076836	100.00
13	East St. Louis	17163 50081	0.000000	0.000000	100.00
14	East St. Louis	17163 50083	0.000487	0.000487	100.00
15	East St. Louis	17163 50091	0.150079	0.150079	100.00
16	East St. Louis	17163 50092	0.133888	0.133888	100.00
17	East St. Louis	17163 50093	0.122807	0.122807	100.00
18	East St. Louis	17163 50094	0.165493	0.165493	100.00
19	East St. Louis	17163 50095	0.227226	0.227226	100.00
20	East St. Louis	17163 50096	0.127674	0.127674	100.00
21	East St. Louis	17163 50097	0.221997	0.221997	100.00
22	East St. Louis	17163 50101	0.113464	0.113464	100.00
23	East St. Louis	17163 50102	0.289556	0.289556	100.00
24	East St. Louis	17163 50103	0.123087	0.123087	100.00
25	East St. Louis	17163 50104	0.150682	0.150682	100.00
26	East St. Louis	17163 50105	0.137898	0.137898	100.00
27	East St. Louis	17163 50106	0.231513	0.231513	100.00
28	East St. Louis	17163 50107	0.986039	0.986039	100.00
29	East St. Louis	17163 50111	0.123358	0.123358	100.00
30	East St. Louis	17163 50112	0.283128	0.283128	100.00
31	East St. Louis	17163 50113	0.124965	0.124965	100.00
32	East St. Louis	17163 50114	0.121074	0.121074	100.00
33	East St. Louis	17163 50115	0.201467	0.201467	100.00
34	East St. Louis	17163 50121	0.141351	0.141351	100.00
35	East St. Louis	17163 50122	0.085991	0.085991	100.00
36	East St. Louis	17163 50123	0.512995	0.512995	100.00
37	East St. Louis	17163 50124	0.210728	0.210728	100.00
38	East St. Louis	17163 50125	0.083292	0.083292	100.00
39	East St. Louis	17163 50126	0.142109	0.142109	100.00
40	East St. Louis	17163 50127	0.156306	0.156306	100.00
41	East St. Louis	17163 50128	0.215884	0.215884	100.00
42	East St. Louis	17163 50135	0.237790	0.072423	30.46
43	East St. Louis	17163 50136	0.425351	0.334668	78.68
44	East St. Louis	17163 50137	0.089695	0.089695	100.00
45	East St. Louis	17163 50138	0.200175	0.200175	100.00
46	Centreville	17163 50231	1.434302	1.434302	100.00
47	East St. Louis	17163 5042016	0.117870	0.117870	100.00
	Centreville	17163 50251	0.423470	0.423470	100.00

Dec 16, 1992

49	Centreville	17163	50252	0.255455	0.255455	100.00
50	Centreville	17163	50253	0.946751	0.831506	87.83
51	Centreville	17163	50254	0.176466	0.176466	100.00
52	Centreville	17163	50271	0.129215	0.129215	100.00
53	Centreville	17163	50272	0.115952	0.115952	100.00
54	Centreville	17163	50273	0.369399	0.369399	100.00
55	Centreville	17163	50274	0.142026	0.142026	100.00
56	Centreville	17163	50281	1.064547	0.724460	68.05
57	Centreville	17163	50282	0.430636	0.381149	88.51
58	Centreville	17163	50283	0.190958	0.190958	100.00
59	Centreville	17163	50291	0.197752	0.055985	28.31
60	Centreville	17163	50293	0.216492	0.216492	100.00
61	Centreville	17163	50294	2.327304	1.247017	53.58
62	East St. Louis	17163	50412	0.399015	0.008262	2.07
63	East St. Louis	17163	50413	0.832056	0.397041	47.72
64	East St. Louis	17163	50414	1.871335	1.252189	66.91
65	East St. Louis	17163	50415	1.337484	1.337484	100.00
66	East St. Louis	17163	50416	0.334426	0.334426	100.00
67	East St. Louis	17163	50441	0.150641	0.150641	100.00
68	East St. Louis	17163	50442	0.139271	0.139271	100.00
69	East St. Louis	17163	50443	0.064767	0.064767	100.00
70	East St. Louis	17163	50444	0.104993	0.104993	100.00
71	East St. Louis	17163	50445	0.129233	0.129233	100.00
72	East St. Louis	17163	50446	0.072267	0.072267	100.00
73	Canteen	17163	5024013	0.119796	0.030780	25.69
74	Canteen	17163	5024016	0.080744	0.032480	40.23
75	Canteen	17163	5024017	0.300949	0.073330	24.37
76	Canteen	17163	5024031	2.967739	0.163613	5.51
77	Centreville	17163	5026011	0.568392	0.568392	100.00
78	Centreville	17163	5026012	0.451550	0.451550	100.00
79	Centreville	17163	5026013	0.226820	0.226820	100.00
80	Centreville	17163	5026014	0.380730	0.380730	100.00
81	Centreville	17163	5026015	0.291504	0.291504	100.00
82	Centreville	17163	5026016	0.495249	0.495249	100.00
83	Centreville	17163	5026017	3.427231	3.314454	96.71
84	Centreville	17163	5026021	0.227255	0.227255	100.00
85	Centreville	17163	5026022	0.472728	0.472728	100.00
86	Centreville	17163	5026023	0.358357	0.358357	100.00
87	Centreville	17163	5026024	1.058617	1.058617	100.00
88	Centreville	17163	5026025	0.123175	0.123175	100.00
89	Centreville	17163	5026026	0.320571	0.320571	100.00
90	Centreville	17163	5026031	1.096811	1.096811	100.00
91	Centreville	17163	5026032	0.853137	0.835000	97.87
92	Centreville	17163	5026033	0.288524	0.288524	100.00
93	Centreville	17163	5026034	3.637022	3.637022	100.00
94	Sugar Loaf	17163	5031011	1.029880	0.974485	94.62
95	Sugar Loaf	17163	5031012	5.382745	1.330750	24.72
96	Sugar Loaf	17163	5031015	9.564408	1.252388	13.09
97	Sugar Loaf	17163	5031022	6.264924	1.523712	24.32
98	East St. Louis	17163	5042011	0.135338	0.135338	100.00
99	East St. Louis	17163	5042012	0.108865	0.108865	100.00
100	East St. Louis	17163	5042013	0.106360	0.106360	100.00

Dec 16, 1992

101 East St. Louis	17163 5042014	0.185220	0.185220	100.00
102 East St. Louis	17163 5042015	0.130498	0.130498	100.00
103 Centreville	17163 50232	0.929248	0.929248	100.00

Totals:		63.664928	39.422001	

For Radius of 3 Mi., Circle Area = 28.274334

No.	City	Block Group ID	Total Area	Partial Area	% Within Radius
7	East St. Louis	17163 50061	0.052645	0.047742	90.69
8	East St. Louis	17163 50062	0.065500	0.065500	100.00
9	East St. Louis	17163 50063	0.075351	0.075351	100.00
10	East St. Louis	17163 50064	0.070534	0.070534	100.00
11	East St. Louis	17163 50065	0.070325	0.069964	99.49
12	East St. Louis	17163 50066	0.076836	0.041869	54.49
13	East St. Louis	17163 50081	0.000000	0.000000	100.00
14	East St. Louis	17163 50083	0.000487	0.000487	100.00
15	East St. Louis	17163 50091	0.150079	0.150079	100.00
16	East St. Louis	17163 50092	0.133888	0.133888	100.00
17	East St. Louis	17163 50093	0.122807	0.122807	100.00
18	East St. Louis	17163 50094	0.165493	0.165493	100.00
19	East St. Louis	17163 50095	0.227226	0.227226	100.00
20	East St. Louis	17163 50096	0.127674	0.127674	100.00
21	East St. Louis	17163 50097	0.221997	0.221997	100.00
22	East St. Louis	17163 50101	0.113464	0.113464	100.00
23	East St. Louis	17163 50102	0.289556	0.289556	100.00
24	East St. Louis	17163 50103	0.123087	0.123087	100.00
25	East St. Louis	17163 50104	0.150682	0.150682	100.00
26	East St. Louis	17163 50105	0.137898	0.137898	100.00
27	East St. Louis	17163 50106	0.231513	0.231513	100.00
28	East St. Louis	17163 50107	0.986039	0.986039	100.00
29	East St. Louis	17163 50111	0.123358	0.123358	100.00
30	East St. Louis	17163 50112	0.283128	0.283128	100.00
31	East St. Louis	17163 50113	0.124965	0.124965	100.00
32	East St. Louis	17163 50114	0.121074	0.121074	100.00
33	East St. Louis	17163 50115	0.201467	0.201467	100.00
36	East St. Louis	17163 50123	0.512995	0.408486	79.63
37	East St. Louis	17163 50124	0.210728	0.101013	47.94
38	East St. Louis	17163 50125	0.083292	0.048372	58.08
39	East St. Louis	17163 50126	0.142109	0.142109	100.00
40	East St. Louis	17163 50127	0.156306	0.156306	100.00
41	East St. Louis	17163 50128	0.215884	0.095131	44.07
46	Centreville	17163 50231	1.434302	1.434302	100.00
48	Centreville	17163 50251	0.423470	0.423470	100.00
49	Centreville	17163 50252	0.255455	0.252362	98.79
50	Centreville	17163 50253	0.946751	0.167614	17.70
51	Centreville	17163 50254	0.176466	0.176466	100.00
52	Centreville	17163 50271	0.129215	0.129215	100.00
53	Centreville	17163 50272	0.115952	0.115952	100.00
54	Centreville	17163 50273	0.369399	0.369399	100.00
	Centreville	17163 50274	0.142026	0.142026	100.00

Dec 16, 1992

56	Centreville	17163	50281	1.064547	0.124453	11.69
58	Centreville	17163	50283	0.190958	0.108314	56.72
60	Centreville	17163	50293	0.216492	0.040771	18.83
61	Centreville	17163	50294	2.327304	0.023347	1.00
64	East St. Louis	17163	50414	1.871335	0.162889	8.70
65	East St. Louis	17163	50415	1.337484	1.337484	100.00
66	East St. Louis	17163	50416	0.334426	0.108861	32.55
67	East St. Louis	17163	50441	0.150641	0.150641	100.00
68	East St. Louis	17163	50442	0.139271	0.093683	67.27
69	East St. Louis	17163	50443	0.064767	0.058618	90.51
70	East St. Louis	17163	50444	0.104993	0.104993	100.00
71	East St. Louis	17163	50445	0.129233	0.129233	100.00
72	East St. Louis	17163	50446	0.072267	0.072267	100.00
77	Centreville	17163	5026011	0.568392	0.568392	100.00
78	Centreville	17163	5026012	0.451550	0.451550	100.00
79	Centreville	17163	5026013	0.226820	0.226820	100.00
80	Centreville	17163	5026014	0.380730	0.362023	95.09
81	Centreville	17163	5026015	0.291504	0.225847	77.48
82	Centreville	17163	5026016	0.495249	0.449742	90.81
83	Centreville	17163	5026017	3.427231	2.588878	75.54
84	Centreville	17163	5026021	0.227255	0.227255	100.00
85	Centreville	17163	5026022	0.472728	0.472728	100.00
86	Centreville	17163	5026023	0.358357	0.358357	100.00
87	Centreville	17163	5026024	1.058617	1.003654	94.81
88	Centreville	17163	5026025	0.123175	0.123175	100.00
89	Centreville	17163	5026026	0.320571	0.320571	100.00
91	Centreville	17163	5026031	1.096811	0.309780	28.24
92	Centreville	17163	5026032	0.853137	0.107174	12.56
93	Centreville	17163	5026033	0.288524	0.162242	56.23
94	Centreville	17163	5026034	3.637022	3.637022	100.00
94	Sugar Loaf	17163	5031011	1.029880	0.093532	9.08
96	Sugar Loaf	17163	5031015	9.564408	0.004312	0.05
97	Sugar Loaf	17163	5031022	6.264924	0.006911	0.11
99	East St. Louis	17163	5042012	0.108865	0.000913	0.84
103	Centreville	17163	50232	0.929248	0.929248	100.00
Totals:				49.940140	23.714750	

For Radius of 2 Mi., Circle Area = 12.566371

No.	City	Block Group ID	Total Area	Partial Area	% Within Radius
13	East St. Louis	17163 50081	0.000000	0.000000	100.00
14	East St. Louis	17163 50083	0.000487	0.000487	100.00
19	East St. Louis	17163 50095	0.227226	0.186010	81.86
20	East St. Louis	17163 50096	0.127674	0.077675	60.84
21	East St. Louis	17163 50097	0.221997	0.113650	51.19
22	East St. Louis	17163 50101	0.113464	0.113464	100.00
23	East St. Louis	17163 50102	0.289556	0.289556	100.00
24	East St. Louis	17163 50103	0.123087	0.123087	100.00
25	East St. Louis	17163 50104	0.150682	0.150682	100.00
26	East St. Louis	17163 50105	0.137898	0.137898	100.00

Dec 16, 1992

27	East St. Louis	17163 50106	0.231513	0.231513	100.00
28	East St. Louis	17163 50107	0.986039	0.968321	98.20
30	East St. Louis	17163 50112	0.283128	0.036900	13.03
31	East St. Louis	17163 50113	0.124965	0.103870	83.12
32	East St. Louis	17163 50114	0.121074	0.121074	100.00
33	East St. Louis	17163 50115	0.201467	0.194247	96.42
46	Centreville	17163 50231	1.434302	1.431179	99.78
48	Centreville	17163 50251	0.423470	0.013047	3.08
52	Centreville	17163 50271	0.129215	0.014626	11.32
54	Centreville	17163 50273	0.369399	0.052385	14.18
55	Centreville	17163 50274	0.142026	0.044738	31.50
65	East St. Louis	17163 50415	1.337484	0.654774	48.96
70	East St. Louis	17163 50444	0.104993	0.016102	15.34
71	East St. Louis	17163 50445	0.129233	0.003585	2.77
72	East St. Louis	17163 50446	0.072267	0.069854	96.66
77	Centreville	17163 5026011	0.568392	0.568392	100.00
78	Centreville	17163 5026012	0.451550	0.451550	100.00
79	Centreville	17163 5026013	0.226820	0.202136	89.12
80	Centreville	17163 5026014	0.380730	0.009133	2.40
82	Centreville	17163 5026016	0.495249	0.056855	11.48
83	Centreville	17163 5026017	3.427231	1.222606	35.67
84	Centreville	17163 5026021	0.227255	0.227255	100.00
85	Centreville	17163 5026022	0.472728	0.164654	34.83
87	Centreville	17163 5026024	1.058617	0.034093	3.22
88	Centreville	17163 5026025	0.123175	0.016567	13.45
89	Centreville	17163 5026026	0.320571	0.191318	59.68
100	Centreville	17163 5026034	3.637022	2.525013	69.43
103	Centreville	17163 50232	0.929248	0.929248	100.00
Totals:			19.801237	11.747541	

For Radius of 1 Mi., Circle Area = 3.141593

No.	City	Block Group ID	Total Area	Partial Area	% Within Radius
23	East St. Louis	17163 50102	0.289556	0.073870	25.51
27	East St. Louis	17163 50106	0.231513	0.081223	35.08
28	East St. Louis	17163 50107	0.986039	0.076498	7.76
46	Centreville	17163 50231	1.434302	0.431074	30.05
77	Centreville	17163 5026011	0.568392	0.540808	95.15
78	Centreville	17163 5026012	0.451550	0.034707	7.69
83	Centreville	17163 5026017	3.427231	0.224147	6.54
93	Centreville	17163 5026034	3.637022	0.761181	20.93
103	Centreville	17163 50232	0.929248	0.918085	98.80
Totals:			11.954854	3.141593	

For Radius of .5 Mi., Circle Area = 0.785398

Block	Total	Partial	% Within
-------	-------	---------	----------

Dec 16, 1992

No.	City	Group ID	Area	Area	Radius
46	Centreville	17163 50231	1.434302	0.011297	0.79
77	Centreville	17163 5026011	0.568392	0.196863	34.64
83	Centreville	17163 5026017	3.427231	0.000529	0.02
103	Centreville	17163 50232	0.929248	0.576709	62.06
Totals:			6.359174	0.785398	

For Radius of .25 Mi., Circle Area = 0.196350

No.	City	Block Group ID	Total Area	Partial Area	% Within Radius
77	Centreville	17163 5026011	0.568392	0.030862	5.43
103	Centreville	17163 50232	0.929248	0.165487	17.81
Totals:			1.497641	0.196350	

===== Site Data =====

Population: 33540.01
 Households: 13163.88
 Drilled Wells: 0.00
 Dug Wells: 0.00
 Other Wells: 0.00

===== Partial (RING) data =====

---- Within Ring: 4 Mile(s) and 3 Mile(s) ----

Population: 10511.19
 Households: 3917.71
 Drilled Wells: 0.00
 Dug Wells: 0.00
 Other Wells: 0.00

** Population On Private Wells: 0.00

---- Within Ring: 3 Mile(s) and 2 Mile(s) ----

Population: 15548.30
 Households: 6081.22
 Drilled Wells: 0.00
 Dug Wells: 0.00
 Other Wells: 0.00

** Population On Private Wells: 0.00

---- Within Ring: 2 Mile(s) and 1 Mile(s) ----

Population: 6951.06
 Households: 2938.74
 Drilled Wells: 0.00
 Dug Wells: 0.00
 Other Wells: 0.00

** Population On Private Wells: 0.00

---- Within Ring: 1 Mile(s) and .5 Mile(s) ----

Population: 413.95
 Households: 175.27
 Drilled Wells: 0.00
 Dug Wells: 0.00
 Other Wells: 0.00

** Population On Private Wells: 0.00

---- Within Ring: .5 Mile(s) and .25 Mile(s) ----

Population:	82.40
Households:	36.33
Drilled Wells:	0.00
Dug Wells:	0.00
Other Wells:	0.00

** Population On Private Wells: 0.00

---- Within Ring: .25 Mile(s) and 0 Mile(s) ----

Population:	33.12
Households:	14.60
Drilled Wells:	0.00
Dug Wells:	0.00
Other Wells:	0.00

** Population On Private Wells: 0.00

** Total Population On Private Wells: 0.00

FROST ASSOCIATES

P.O. Box 495, Essex, Connecticut 06426
(203) 767-1254 Fax (203) 767-7069

Dec 16, 1992

To: Tom Crause
Illinois Environmental Protection Agency
7200 Churchill Road
Springfield, Illinois 62794

Fr: Bob Frost
Frost Associates
P.O. Box 495
Essex, CT 06426

Tel: (203) 767-1254
Fax: (203) 767-7069

Sub: CENTRACTS Demonstration
Sauget IL,
Missouri Portion

CIRCLIS:

Site Longitude: 90.167503
Site Latitude : 38.589439

The CENTRACTS report below identifies the population, households, and private water wells of each Block Group that lies within, or partially within, the 4, 3, 2, 1, .5, and .25, mile "rings" of the latitude and longitude coordinates above. CENTRACTS may have up to ten radii of any length, 1000 block groups, and 15000 block group sides.

CENTRACTS uses the 1990 Block Group population and Block Group house count data found in the Census Bureau's 1990 STF-1A files. The sources of water supply data are from the Bureau's 1990 STF-3A files. The boundary line coordinates of the Block Groups were extracted from the Census Bureau's 1990 TIGER/Line Files.

CENTRACTS reports are created with programs written by Frost Associates, P.O. Box 495, Essex, Conn. The code was written using Microsoft's Quick-Basic Ver. 4.5.

Latitude and Longitude coordinates identifying a site are entered in degrees and decimal degrees. One or more county files holding Block Group boundary lines are selected for use by CENTRACTS by determining whether the site coordinates fall within the minimum and maximum Lat/Lon coordinates of each county in the state.

Each Block Group line segment has Lat/Lon coordinates representing the "From" and "To" ends of that line. All coordinates from the selected county files are read and converted from degrees, decimal degrees to X/Y miles from the site location. Each line segment is then examined whether it lies within or partially within the maximum ring from the site.

The unique Block Group ID numbers of each line segment that lie within the maximum ring are retained. All Block Group boundary lines matching the Block Group numbers are then extracted from the respective county files to obtain all sides of the included Block Groups. Boundary records are then sorted in adjacent side order to determine the shape and area of each Block Group polygon.

2

A method to solve for the area of a polygon is to take one-half the sum of the products obtained by multiplying each X-coordinate by the difference between the adjacent Y-coordinates. For a polygon with coordinates at adjacent angles A, B, C, D, and E. The formula can be expressed:

$$\text{Area} = 1/2\{X_a(Y_e - Y_b) + X_b(Y_a - Y_c) + X_c(Y_b - Y_d) + X_d(Y_c - Y_e) + X_e(Y_d - Y_a)\}$$

For each ring, the selected Block Groups will be inside, outside, or intersected by the ring. When a polygon is intersected, the partial Block Group area within that ring is calculated using the method described below.

When a ring intersects a Block Group, the intersect points are solved and plotted at the points where the ring enters and exits the shape. The chord line, a line within the circle connecting the intersect points is determined. This chord line is used to calculate the segment area, the half moon shape between the chord line and the ring, and the sub-polygon created by the chord line and the Block Group boundaries that lie outside the ring.

The segment area is subtracted from the sub-polygon area to determine the area of the sub-polygon outside the ring. The area outside the ring is then subtracted from the area of the entire polygon to arrive at the inside area. This inside area is then divided by the tract's total area to determine the percentage of area within the ring. This process is repeated for each block group that is intersected by one of the rings. The total area, partial area, and percentage of partial area of those block groups within, or partially within a ring, are held in memory for the report.

On occasion, the algorithm described above is unable to determine the area of the partial area. Within the report program is a "Paint" routine which allows an enclosed shape to be highlighted. Another routine calculates the percentage of highlighted screen pixels to the pixels within the polygon. A manual entry is allowed. Both the "paint" method and manual entry method override the calculated method.

CENTRACTS lists, starting on page 4, all Block Groups in State, County, Census Tract, and Block Group ID order that lie within, or partially within, the maximum ring. Each Block Group is identified by a City or Town name and by the Block Group's State, County, Tract and Block Group ID number. Following is the Block Group's 1990 population and house count extracted from the Census Bureau's 1990 STF-1A files.

The next four columns display water source data from the 1990 STF-3A files. The first column is "Units with Public system or private company source of water", followed by "Units with individual well, Drilled, source of water"; "Units with individual well, Dug, source of water" and "Units with Other source of water".

For each ring, CENTRACTS then shows the Block Groups that are within that ring, the Block Group's total area in square miles, the partial area of the Block Group within that ring, and the partial percentage within the ring. The areas of the included Block Group and the partial areas are then totaled.

The last section tallies the demographic data within each ring. The percentage of area for each Block Group is multiplied times the census data for that Block Group and totaled for all Block Group's within the ring. Ring totals are then determined by subtracting the three mile data from the four mile, the two mile from the three mile, one from the two, etc... Population on private wells is calculated using the formula: $((\text{Drilled} + \text{Dug Wells}) / \text{Households}) * \text{Population}$

Dec 16, 1992

No.	City	Block Group ID	Blk Grp People	House Holds	Public Water	Drilled Wells	Dug Wells	Other
1	St. Louis	29510 1155	1 881	483	00	00	00	00
2	St. Louis	29510 1156	1 1319	445	00	00	00	00
3	St. Louis	29510 1156	3 675	363	00	00	00	00
4	St. Louis	29510 1156	6 746	355	00	00	00	00
5	St. Louis	29510 1156	7 1599	884	00	00	00	00
6	St. Louis	29510 1156	8 805	439	00	00	00	00
7	St. Louis	29510 1157	1 259	161	00	00	00	00
8	St. Louis	29510 1157	2 586	275	00	00	00	00
9	St. Louis	29510 1157	3 800	391	00	00	00	00
10	St. Louis	29510 1157	4 480	259	00	00	00	00
11	St. Louis	29510 1157	5 1013	482	00	00	00	00
12	St. Louis	29510 1164	1 981	523	00	00	00	00
13	St. Louis	29510 1164	2 761	400	00	00	00	00
14	St. Louis	29510 1164	3 1044	515	00	00	00	00
15	St. Louis	29510 1164	4 606	330	00	00	00	00
16	St. Louis	29510 1164	5 674	438	00	00	00	00
17	St. Louis	29510 1164	6 609	298	00	00	00	00
18	St. Louis	29510 1164	7 425	185	00	00	00	00
19	St. Louis	29510 1165	1 803	394	00	00	00	00
20	St. Louis	29510 1165	2 394	229	00	00	00	00
21	St. Louis	29510 1165	3 575	318	00	00	00	00
22	St. Louis	29510 1165	4 924	418	00	00	00	00
23	St. Louis	29510 1165	5 716	333	00	00	00	00
24	St. Louis	29510 1165	6 815	366	00	00	00	00
25	St. Louis	29510 1165	7 780	375	00	00	00	00
26	St. Louis	29510 1173	1 338	153	00	00	00	00
27	St. Louis	29510 1173	2 762	337	00	00	00	00
28	St. Louis	29510 1173	5 500	195	00	00	00	00
29	St. Louis	29510 1174	1 1106	474	00	00	00	00
30	St. Louis	29510 1174	2 840	368	00	00	00	00
31	St. Louis	29510 1174	3 927	467	00	00	00	00
32	St. Louis	29510 1174	4 976	492	00	00	00	00
33	St. Louis	29510 1184	1 618	500	00	00	00	00
34	St. Louis	29510 1184	2 297	299	00	00	00	00
35	St. Louis	29510 1185	1 140	88	00	00	00	00
36	St. Louis	29510 1185	2 216	109	00	00	00	00
37	St. Louis	29510 1211	6 1191	1148	00	00	00	00
38	St. Louis	29510 1213	1 713	521	00	00	00	00
39	St. Louis	29510 1213	2 0	1	00	00	00	00
40	St. Louis	29510 1213	5 169	66	00	00	00	00
41	St. Louis	29510 1214	1 157	3	00	00	00	00
42	St. Louis	29510 1214	2 45	1	00	00	00	00
43	St. Louis	29510 1214	3 47	21	00	00	00	00
44	St. Louis	29510 1221	1 0	0	00	00	00	00
45	St. Louis	29510 1221	2 662	372	00	00	00	00
46	St. Louis	29510 1221	3 638	370	00	00	00	00
47	St. Louis	29510 1221	4 437	155	00	00	00	00
48	St. Louis	29510 1221	5 10	5	00	00	00	00
49	St. Louis	29510 1222	1 1	0	00	00	00	00
50	St. Louis	29510 1222	2 0	0	00	00	00	00
51	St. Louis	29510 1222	3 195	2	00	00	00	00
52	St. Louis	29510 1224	1 0	0	00	00	00	00

Dec 16, 1992

53	St. Louis	29510 1224	2	0	0	00	00	00	00
54	St. Louis	29510 1224	3	132	65	00	00	00	00
55	St. Louis	29510 1224	4	1409	815	00	00	00	00
56	St. Louis	29510 1224	5	384	210	00	00	00	00
57	St. Louis	29510 1224	6	1105	654	00	00	00	00
58	St. Louis	29510 1231	1	290	161	00	00	00	00
59	St. Louis	29510 1231	2	268	152	00	00	00	00
60	St. Louis	29510 1231	3	809	482	00	00	00	00
61	St. Louis	29510 1231	4	1244	535	00	00	00	00
62	St. Louis	29510 1231	5	200	94	00	00	00	00
63	St. Louis	29510 1231	6	259	127	00	00	00	00
64	St. Louis	29510 1231	7	1212	621	00	00	00	00
65	St. Louis	29510 1232	1	593	215	00	00	00	00
66	St. Louis	29510 1232	2	287	204	00	00	00	00
67	St. Louis	29510 1232	3	488	331	00	00	00	00
68	St. Louis	29510 1232	4	428	246	00	00	00	00
69	St. Louis	29510 1232	5	720	371	00	00	00	00
70	St. Louis	29510 1233	1	267	179	00	00	00	00
71	St. Louis	29510 1233	2	467	217	00	00	00	00
72	St. Louis	29510 1233	3	752	461	00	00	00	00
73	St. Louis	29510 1233	4	420	270	00	00	00	00
74	St. Louis	29510 1233	5	246	129	00	00	00	00
75	St. Louis	29510 1233	6	1023	563	00	00	00	00
76	St. Louis	29510 1233	7	179	108	00	00	00	00
77	St. Louis	29510 1234	1	8	9	00	00	00	00
78	St. Louis	29510 1234	2	476	361	00	00	00	00
79	St. Louis	29510 1234	3	522	404	00	00	00	00
80	St. Louis	29510 1234	4	542	436	00	00	00	00
81	St. Louis	29510 1234	5	391	300	00	00	00	00
82	St. Louis	29510 1234	6	672	376	00	00	00	00
83	St. Louis	29510 1234	7	299	184	00	00	00	00
84	St. Louis	29510 1234	8	145	110	00	00	00	00
85	St. Louis	29510 1235	1	0	0	00	00	00	00
86	St. Louis	29510 1235	2	0	0	00	00	00	00
87	St. Louis	29510 1235	3	0	0	00	00	00	00
88	St. Louis	29510 1241	1	485	161	00	00	00	00
89	St. Louis	29510 1241	2	502	264	00	00	00	00
90	St. Louis	29510 1241	3	504	275	00	00	00	00
91	St. Louis	29510 1241	4	663	344	00	00	00	00
92	St. Louis	29510 1241	5	652	336	00	00	00	00
93	St. Louis	29510 1241	6	939	468	00	00	00	00
94	St. Louis	29510 1241	7	1170	564	00	00	00	00
95	St. Louis	29510 1241	8	1027	526	00	00	00	00
96	St. Louis	29510 1242	1	431	215	00	00	00	00
97	St. Louis	29510 1242	2	535	317	00	00	00	00
98	St. Louis	29510 1242	3	611	276	00	00	00	00
99	St. Louis	29510 1242	4	733	355	00	00	00	00
100	St. Louis	29510 1242	5	688	354	00	00	00	00
101	St. Louis	29510 1242	6	1005	493	00	00	00	00
102	St. Louis	29510 1242	7	402	227	00	00	00	00
103	St. Louis	29510 1243	1	771	411	00	00	00	00
104	St. Louis	29510 1243	2	353	212	00	00	00	00
105	St. Louis	29510 1243	3	719	368	00	00	00	00
106	St. Louis	29510 1243	4	673	347	00	00	00	00
1	St. Louis	29510 1243	5	190	114	00	00	00	00

Dec 16, 1992

108	St. Louis	29510 1243 6	734	438	00	00	00	00
109	St. Louis	29510 1243 7	529	333	00	00	00	00
110	St. Louis	29510 1243 8	405	225	00	00	00	00
111	St. Louis	29510 1246 1	36	38	00	00	00	00
112	St. Louis	29510 1246 2	746	355	00	00	00	00
113	St. Louis	29510 1246 3	1254	684	00	00	00	00
114	St. Louis	29510 1246 4	171	106	00	00	00	00
115	St. Louis	29510 1255 1	70	60	00	00	00	00
116	St. Louis	29510 1255 2	1805	1875	00	00	00	00
117	St. Louis	29510 1255 3	224	0	00	00	00	00
118	St. Louis	29510 1256 1	97	111	00	00	00	00
119	St. Louis	29510 1256 2	46	43	00	00	00	00
120	St. Louis	29510 1256 3	366	269	00	00	00	00
121	St. Louis	29510 1256 4	0	0	00	00	00	00
122	St. Louis	29510 1256 5	5	6	00	00	00	00
123	St. Louis	29510 1256 6	637	810	00	00	00	00
124	St. Louis	29510 1257 1	0	0	00	00	00	00
125	St. Louis	29510 1257 2	1555	994	00	00	00	00
126	St. Louis	29510 1257 3	176	117	00	00	00	00
127	St. Louis	29510 1257 4	746	555	00	00	00	00
128	St. Louis	29510 1257 5	1435	774	00	00	00	00
129	St. Louis	29510 1257 6	7	9	00	00	00	00
130	St. Louis	29510 1257 7	316	124	00	00	00	00
131	St. Louis	29510 1266 1	0	0	00	00	00	00
132	St. Louis	29510 1266 2	56	31	00	00	00	00
133	St. Louis	29510 1266 9	554	259	00	00	00	00
-----			-----	-----	-----	-----	-----	-----
Totals:			71515	40039	0	0	0	0

For Radius of 4 Mi., Circle Area = 50.265482

No.	City	Block Group ID	Total Area	Partial Area	% Within Radius
1	St. Louis	29510 11551	0.073543	0.007978	10.85
2	St. Louis	29510 11561	0.616762	0.434446	70.44
3	St. Louis	29510 11563	0.070161	0.017766	25.32
4	St. Louis	29510 11566	0.065840	0.003449	5.24
5	St. Louis	29510 11567	0.133312	0.128384	96.30
6	St. Louis	29510 11568	0.063842	0.046435	72.73
7	St. Louis	29510 11571	0.119442	0.119442	100.00
8	St. Louis	29510 11572	0.048145	0.048145	100.00
9	St. Louis	29510 11573	0.049077	0.049077	100.00
10	St. Louis	29510 11574	0.063233	0.059221	93.65
11	St. Louis	29510 11575	0.062996	0.000857	1.36
12	St. Louis	29510 11641	0.069158	0.069158	100.00
13	St. Louis	29510 11642	0.061288	0.061288	100.00
14	St. Louis	29510 11643	0.061010	0.061010	100.00
15	St. Louis	29510 11644	0.053603	0.013255	24.73
16	St. Louis	29510 11645	0.055078	0.024945	45.29
17	St. Louis	29510 11646	0.041746	0.032837	78.66
18	St. Louis	29510 11647	0.043227	0.017116	39.60
19	St. Louis	29510 11651	0.047747	0.047747	100.00
20	St. Louis	29510 11652	0.067342	0.067342	100.00
21	St. Louis	29510 11653	0.037287	0.037287	100.00
22	St. Louis	29510 11654	0.044525	0.026154	58.74
23	St. Louis	29510 11655	0.039035	0.039035	100.00
24	St. Louis	29510 11656	0.063492	0.030768	48.46
25	St. Louis	29510 11657	0.046267	0.026112	56.44
26	St. Louis	29510 11731	0.065834	0.064283	97.64
27	St. Louis	29510 11732	0.150218	0.083352	55.49
28	St. Louis	29510 11735	0.099760	0.005616	5.63
29	St. Louis	29510 11741	0.152124	0.099730	65.56
30	St. Louis	29510 11742	0.039019	0.039019	100.00
31	St. Louis	29510 11743	0.054709	0.054709	100.00
32	St. Louis	29510 11744	0.063201	0.022175	35.09
33	St. Louis	29510 11841	0.190839	0.047580	24.93
34	St. Louis	29510 11842	0.360061	0.105196	29.22
35	St. Louis	29510 11851	0.054109	0.052685	97.37
36	St. Louis	29510 11852	0.063753	0.011757	18.44
37	St. Louis	29510 12116	0.097156	0.006342	6.53
38	St. Louis	29510 12131	0.085955	0.042842	49.84
39	St. Louis	29510 12132	0.036092	0.012665	35.09
40	St. Louis	29510 12135	0.163617	0.000284	0.17
41	St. Louis	29510 12141	0.072728	0.072728	100.00
42	St. Louis	29510 12142	0.154609	0.120735	78.09
43	St. Louis	29510 12143	0.107356	0.041143	38.32
44	St. Louis	29510 12211	0.047358	0.047358	100.00
45	St. Louis	29510 12212	0.098297	0.098297	100.00
46	St. Louis	29510 12213	0.042894	0.042894	100.00
47	St. Louis	29510 12214	0.039527	0.039527	100.00
	St. Louis	29510 12215	0.052334	0.052334	100.00

Dec 16, 1992

49 St. Louis	29510 12221	0.212940	0.212940	100.00
50 St. Louis	29510 12222	0.155400	0.155400	100.00
51 St. Louis	29510 12223	0.320977	0.320977	100.00
52 St. Louis	29510 12241	0.112256	0.112256	100.00
53 St. Louis	29510 12242	0.039955	0.039955	100.00
54 St. Louis	29510 12243	0.046662	0.046662	100.00
55 St. Louis	29510 12244	0.082132	0.082132	100.00
56 St. Louis	29510 12245	0.065934	0.065934	100.00
57 St. Louis	29510 12246	0.050024	0.050024	100.00
58 St. Louis	29510 12311	0.046294	0.046294	100.00
59 St. Louis	29510 12312	0.045531	0.045531	100.00
60 St. Louis	29510 12313	0.096761	0.096761	100.00
61 St. Louis	29510 12314	0.059580	0.059580	100.00
62 St. Louis	29510 12315	0.038220	0.038220	100.00
63 St. Louis	29510 12316	0.032872	0.032872	100.00
64 St. Louis	29510 12317	0.070402	0.070402	100.00
65 St. Louis	29510 12321	0.065173	0.065173	100.00
66 St. Louis	29510 12322	0.074645	0.074645	100.00
67 St. Louis	29510 12323	0.094679	0.094679	100.00
68 St. Louis	29510 12324	0.127661	0.127661	100.00
69 St. Louis	29510 12325	0.068138	0.068138	100.00
70 St. Louis	29510 12331	0.040223	0.040223	100.00
71 St. Louis	29510 12332	0.032676	0.032676	100.00
72 St. Louis	29510 12333	0.053024	0.053024	100.00
73 St. Louis	29510 12334	0.048995	0.048995	100.00
74 St. Louis	29510 12335	0.030880	0.030880	100.00
75 St. Louis	29510 12336	0.098714	0.098714	100.00
76 St. Louis	29510 12337	0.045053	0.045053	100.00
77 St. Louis	29510 12341	0.051461	0.051461	100.00
78 St. Louis	29510 12342	0.074312	0.074312	100.00
79 St. Louis	29510 12343	0.082409	0.082409	100.00
80 St. Louis	29510 12344	0.061812	0.061812	100.00
81 St. Louis	29510 12345	0.043645	0.043645	100.00
82 St. Louis	29510 12346	0.043571	0.043571	100.00
83 St. Louis	29510 12347	0.044544	0.044544	100.00
84 St. Louis	29510 12348	0.042694	0.042694	100.00
85 St. Louis	29510 12351	0.591519	0.591519	100.00
86 St. Louis	29510 12352	0.104872	0.104872	100.00
87 St. Louis	29510 12353	0.259748	0.259748	100.00
88 St. Louis	29510 12411	0.047817	0.047817	100.00
89 St. Louis	29510 12412	0.045918	0.045918	100.00
90 St. Louis	29510 12413	0.045990	0.045990	100.00
91 St. Louis	29510 12414	0.047210	0.047210	100.00
92 St. Louis	29510 12415	0.047591	0.047591	100.00
93 St. Louis	29510 12416	0.047829	0.047829	100.00
94 St. Louis	29510 12417	0.065113	0.065113	100.00
95 St. Louis	29510 12418	0.063317	0.063317	100.00
96 St. Louis	29510 12421	0.032806	0.032806	100.00
97 St. Louis	29510 12422	0.035150	0.035150	100.00
98 St. Louis	29510 12423	0.040904	0.040904	100.00
99 St. Louis	29510 12424	0.046341	0.046341	100.00
100 St. Louis	29510 12425	0.041801	0.041801	100.00
101 St. Louis	29510 12426	0.052511	0.052511	100.00
102 St. Louis	29510 12427	0.049618	0.049618	100.00
1 St. Louis	29510 12431	0.066819	0.066819	100.00

Dec 16, 1992

104 St. Louis	29510 12432	0.037126	0.037126	100.00
105 St. Louis	29510 12433	0.099732	0.099732	100.00
106 St. Louis	29510 12434	0.033310	0.033310	100.00
107 St. Louis	29510 12435	0.039903	0.039903	100.00
108 St. Louis	29510 12436	0.066634	0.066634	100.00
109 St. Louis	29510 12437	0.046943	0.046943	100.00
110 St. Louis	29510 12438	0.053222	0.053222	100.00
111 St. Louis	29510 12461	0.674471	0.674471	100.00
112 St. Louis	29510 12462	0.102784	0.102784	100.00
113 St. Louis	29510 12463	0.105159	0.105159	100.00
114 St. Louis	29510 12464	0.165716	0.165716	100.00
115 St. Louis	29510 12551	0.096211	0.096211	100.00
116 St. Louis	29510 12552	0.119914	0.119914	100.00
117 St. Louis	29510 12553	0.198122	0.198122	100.00
118 St. Louis	29510 12561	0.112987	0.112987	100.00
119 St. Louis	29510 12562	0.105599	0.105599	100.00
120 St. Louis	29510 12563	0.084807	0.084807	100.00
121 St. Louis	29510 12564	0.142823	0.142823	100.00
122 St. Louis	29510 12565	0.156828	0.156828	100.00
123 St. Louis	29510 12566	0.365310	0.365310	100.00
124 St. Louis	29510 12571	0.204682	0.204682	100.00
125 St. Louis	29510 12572	0.074027	0.074027	100.00
126 St. Louis	29510 12573	0.042539	0.042539	100.00
127 St. Louis	29510 12574	0.076325	0.076325	100.00
128 St. Louis	29510 12575	0.072012	0.059425	82.52
129 St. Louis	29510 12576	0.057023	0.057023	100.00
130 St. Louis	29510 12577	0.048132	0.048132	100.00
131 St. Louis	29510 12661	0.603522	0.177154	29.35
132 St. Louis	29510 12662	0.139141	0.119123	85.61
133 St. Louis	29510 12669	0.129329	0.023938	18.51
----- Totals: -----		13.076165	10.755596	-----

For Radius of 3 Mi., Circle Area = 28.274334

No.	City	Block Group ID	Total Area	Partial Area	% Within Radius
7 St. Louis	29510 11571	0.119442	0.005395	4.52	
49 St. Louis	29510 12221	0.212940	0.212940	100.00	
50 St. Louis	29510 12222	0.155400	0.153174	98.57	
51 St. Louis	29510 12223	0.320977	0.020143	6.28	
52 St. Louis	29510 12241	0.112256	0.112256	100.00	
53 St. Louis	29510 12242	0.039955	0.039955	100.00	
54 St. Louis	29510 12243	0.046662	0.046662	100.00	
55 St. Louis	29510 12244	0.082132	0.082132	100.00	
56 St. Louis	29510 12245	0.065934	0.012903	19.57	
57 St. Louis	29510 12246	0.050024	0.049649	99.25	
65 St. Louis	29510 12321	0.065173	0.064918	99.61	
66 St. Louis	29510 12322	0.074645	0.074645	100.00	
67 St. Louis	29510 12323	0.094679	0.070642	74.61	
68 St. Louis	29510 12324	0.127661	0.000565	0.44	
St. Louis	29510 12325	0.068138	0.013566	19.91	

Dec 16, 1992

70	St. Louis	29510 12331	0.040223	0.040223	100.00
71	St. Louis	29510 12332	0.032676	0.032676	100.00
72	St. Louis	29510 12333	0.053024	0.053024	100.00
73	St. Louis	29510 12334	0.048995	0.014650	29.90
74	St. Louis	29510 12335	0.030880	0.008121	26.30
75	St. Louis	29510 12336	0.098714	0.044656	45.24
76	St. Louis	29510 12337	0.045053	0.045053	100.00
77	St. Louis	29510 12341	0.051461	0.051461	100.00
78	St. Louis	29510 12342	0.074312	0.074312	100.00
79	St. Louis	29510 12343	0.082409	0.082409	100.00
80	St. Louis	29510 12344	0.061812	0.061812	100.00
81	St. Louis	29510 12345	0.043645	0.043645	100.00
82	St. Louis	29510 12346	0.043571	0.043571	100.00
83	St. Louis	29510 12347	0.044544	0.044544	100.00
84	St. Louis	29510 12348	0.042694	0.042694	100.00
85	St. Louis	29510 12351	0.591519	0.591519	100.00
86	St. Louis	29510 12352	0.104872	0.104872	100.00
87	St. Louis	29510 12353	0.259748	0.259748	100.00
103	St. Louis	29510 12431	0.066819	0.047491	71.07
104	St. Louis	29510 12432	0.037126	0.031153	83.91
105	St. Louis	29510 12433	0.099732	0.069079	69.26
106	St. Louis	29510 12434	0.033310	0.031424	94.34
107	St. Louis	29510 12435	0.039903	0.039903	100.00
108	St. Louis	29510 12436	0.066634	0.066634	100.00
109	St. Louis	29510 12437	0.046943	0.017082	36.39
110	St. Louis	29510 12438	0.053222	0.008943	16.80
111	St. Louis	29510 12461	0.674471	0.658068	97.57
112	St. Louis	29510 12462	0.102784	0.101825	99.07
113	St. Louis	29510 12463	0.105159	0.033208	31.58
114	St. Louis	29510 12464	0.165716	0.165716	100.00
117	St. Louis	29510 12553	0.198122	0.008383	4.23
118	St. Louis	29510 12561	0.112987	0.004973	4.40
119	St. Louis	29510 12562	0.105599	0.049910	47.26
121	St. Louis	29510 12564	0.142823	0.132218	92.58
122	St. Louis	29510 12565	0.156828	0.057409	36.61
123	St. Louis	29510 12566	0.365310	0.365027	99.92
Totals:			5.959660	4.486984	

For Radius of 2 Mi., Circle Area = 12.566371

No.	City	Block Group ID	Total Area	Partial Area	% Within Radius
49	St. Louis	29510 12221	0.212940	0.022911	10.76
52	St. Louis	29510 12241	0.112256	0.035603	31.72
85	St. Louis	29510 12351	0.591519	0.528024	89.27
86	St. Louis	29510 12352	0.104872	0.028900	27.56
87	St. Louis	29510 12353	0.259748	0.103413	39.81
111	St. Louis	29510 12461	0.674471	0.042457	6.29
Totals:			1.955806	0.761308	

Dec 16, 1992

For Radius of 1 Mi., Circle Area = 3.141593

No.	City	Block Group ID	Total Area	Partial Area	% Within Radius
Totals:			0.000000	0.000000	

For Radius of .5 Mi., Circle Area = 0.785398

No.	City	Block Group ID	Total Area	Partial Area	% Within Radius
Totals:			0.000000	0.000000	

For Radius of .25 Mi., Circle Area = 0.196350

No.	City	Block Group ID	Total Area	Partial Area	% Within Radius
Totals:			0.000000	0.000000	

===== Site Data =====

Population: 60391.47
 Households: 33773.91
 Drilled Wells: 0.00
 Dug Wells: 0.00
 Other Wells: 0.00

===== Partial (RING) data =====

---- Within Ring: 4 Mile(s) and 3 Mile(s) ----

Population: 45716.94
 Households: 24631.12
 Drilled Wells: 0.00
 Dug Wells: 0.00
 Other Wells: 0.00

** Population On Private Wells: 0.00

---- Within Ring: 3 Mile(s) and 2 Mile(s) ----

Population: 14672.15
 Households: 9140.40
 Drilled Wells: 0.00
 Dug Wells: 0.00
 Other Wells: 0.00

** Population On Private Wells: 0.00

---- Within Ring: 2 Mile(s) and 1 Mile(s) ----

Population: 2.37
 Households: 2.39
 Drilled Wells: 0.00
 Dug Wells: 0.00
 Other Wells: 0.00

** Population On Private Wells: 0.00

---- Within Ring: 1 Mile(s) and .5 Mile(s) ----

Population: 0.00
 Households: 0.00
 Drilled Wells: 0.00
 Dug Wells: 0.00
 Other Wells: 0.00

** Population On Private Wells: Not Applicable

----- Within Ring: .5 Mile(s) and .25 Mile(s) -----

Population:	0.00
Households:	0.00
Drilled Wells:	0.00
Dug Wells:	0.00
Other Wells:	0.00

** Population On Private Wells: Not Applicable

----- Within Ring: .25 Mile(s) and 0 Mile(s) -----

Population:	0.00
Households:	0.00
Drilled Wells:	0.00
Dug Wells:	0.00
Other Wells:	0.00

** Population On Private Wells: Not Applicable

** Total Population On Private Wells: 0.00

APPENDIX H

REMOVAL CRITERIA

**THE FOLLOWING FACTORS SHALL BE CONSIDERED IN DETERMINING THE
APPROPRIATENESS OF A REMOVAL ACTION**

.

- Actual or potential exposure to nearby human populations, animals, or food chain from hazardous substances or pollutants or contaminants.
- Actual or potential contamination of drinking water supplies or sensitive ecosystems.
- Hazardous substances or pollutants or contaminants in drums, barrels, tanks or other bulk storage containers, that may pose a threat of release.
- High levels of hazardous substances or pollutants or contaminants in soils largely at or near the surface, that may migrate.
- Weather conditions that may cause hazardous substances or pollutants or contaminants to migrate or be released.
- Threat of fire or explosion.
- The availability of other appropriate federal or state response mechanisms to respond to the release.
- Other situations or factors that may pose threats to public health or welfare or the environment.